VILLAGE OF DOWNERS GROVE REPORT FOR THE VILLAGE COUNCIL MEETING MAY 15, 2012 AGENDA

| SUBJECT: | TYPE: | | SUBMITTED BY: |
|---------------------------|--------------|------------------------|--------------------------|
| | | Resolution | |
| | | Ordinance | |
| Bid: Oakwood Avenue Storm | \checkmark | Motion | Nan Newlon, P.E. |
| Sewer Replacement | | Discussion Only | Director of Public Works |

SYNOPSIS

A motion is requested to award a contract for the Oakwood Avenue Storm Sewer Replacement project to Swallow Construction, Inc. of Downers Grove, Illinois in the amount of \$453,620.00.

STRATEGIC PLAN ALIGNMENT

The goals for 2011-2018 include Top Quality Infrastructure.

FISCAL IMPACT

The FY12 budget includes \$500,000 in the Stormwater Fund for this project.

UPDATE & RECOMMENDATION

This item was discussed at the May 8, 2012 Village Council meeting. The Council asked staff for additional information from the references, a contractor evaluation for the second-lowest bidder, as well as information regarding the ability of the Village to withhold payment to ensure successful completion of the project. Staff contacted Swallow Construction's references and received one response from the City of Wood Dale. They stated Swallow completed the project on time, within budget, and was responsive to the needs of staff and residents.

The second lowest bidder was H. Linden & Sons, who successfully constructed the Pershing Ave Storm Sewer for the Village in 2011. A report card is attached.

Below is additional information regarding the performance requirements for this contract:

- Typically 10% of the progress payments are withheld as retainage until project completion. This percentage can be reduced over the course of the project if the contractor is progressing satisfactorily, but the Village can continue to retain 10% should staff feel the work is not progressing in a satisfactory manner. If work is being performed that does not meet the requirements of the contract, full payment can be withheld until the contractor corrects deficiencies.
- The Village will have a Staff Engineer assigned to this project full time. Expectations will be established up-front, prior to the start of construction. Unsatisfactory work will be rejected and will need to be replaced by the contractor at no additional cost.
- A performance bond is required for this contract. If, at any time during the project, project requirements are not being met, staff will give the contractor 10 days to comply. If they do not comply, the contractor may be declared in default of their contract and the Village will have the option of either calling upon the contractor's bond to complete the work, completing the work with Village resources, or hiring an alternate contractor to complete the work. In the case of contract default, any additional cost to the Village would be the responsibility of the contractor.
 Staff recommends approval on the May 15, 2012 Active Agenda.

BACKGROUND

The existing 10" clay storm sewer along Oakwood Avenue from Chicago Avenue to Grant Street is in extremely poor condition and is in need of replacement. The existing system's inlet spacing and capacity are also inadequate. This project involves the installation of a new storm sewer system along Oakwood Avenue from Chicago Avenue to Grant Street. The system will also provide the residents with the opportunity to connect sump pumps and yard drains.

| Contractor | Base Bid Amount |
|-----------------------------------|-------------------|
| Swallow Construction Corp. | \$453,620.00 |
| H. Linden & Sons Sewer and Water | \$527,840.00 |
| Fox Excavating, Inc. | \$569,420.00 |
| J. Condgdon Sewer Service, Inc. | Non-Compliant Bid |
| Archon Construction Company, Inc. | Non-Compliant Bid |

Bids were received on Friday, April 20, 2012. A synopsis of the bids is as follows:

The low bidder is Swallow Construction, Inc. The Village was not satisfied with this company's performance on a project completed in 2009. However, the construction crew is under new management and the bidder has received good references for work performed in the City of Wooddale, Village of Mount Prospect, City of Warrenville, and City of Naperville within the last two construction seasons.

ATTACHMENTS

Contract Form Campaign Disclosure Form Capital Project Sheet SW-070 Contractor Report Card

VILLAGE OF DOWNERS GROVE

COUNCIL ACTION SUMMARY

| INITI | ATED: | Public Works (Name) | DATE: | May 15, 2012 | |
|-----------------------------|------------|------------------------|-----------------------------------|---|--|
| RECOMMENDATION FROM: | | | (Board or Department) | | |
| NATURE OF ACTION: | | TION: | STEPS NEEDED TO IMPLEMENT ACTION: | | |
| | Ordinance | | | act for the Oakwood Storm ect to Swallow Construction, | |
| | Resolution | | Inc. in the amount of \$45: | | |
| X | Motion | | | | |
| | Other | | | | |

SUMMARY OF ITEM:

Adoption of this motion shall award a contract for the Oakwood Storm Sewer Replacement Project to Swallow Construction, Inc. in the amount of \$453,620.00.

RECORD OF ACTION TAKEN:

1\wp8\cas.12\PW-Oakwood-SS



CALL FOR BIDS – FIXED WORKS PROJECT

I. Name of Company Bidding: SWALLOW CONSTRUCTION, Inc

II. Instructions and Specifications:

- A. Bid No.: SW-070-12
- B. For: OAKWOOD AVE STORM SEWER REPLACEMENT
- C. Bid Opening Date/Time: FRIDAY, APRIL 20, 2012 @ 10:00AM
- D. Pre-Bid Conference Date/Time: FRIDAY, APRIL 13, 2012 @ 10:00AM
- E. Pre-Bid Conference Location: <u>PUBLIC WORKS BUILDING</u>, 5101 WALNUT AVENUE, DOWNERS GROVE, IL 60515
- III. Required of All Bidders:
 - A. Bid Deposit: <u>5%</u>
 - B. Letter of Capability of Acquiring Performance Bond: <u>YES</u>
- IV. Required of Awarded Contractor(s)
 - A. Performance Bond or Letter of Credit: YES
 - B. Certificate of Insurance: YES

Legal Advertisement Published: <u>APRIL 9, 2012</u>

This document comprises <u>79</u> pages

RETURN <u>ORIGINAL</u> BID IN SEALED ENVELOPE MARKED WITH THE BID NUMBER AS NOTED ABOVE TO :

JIM TOCK, P.E. STAFF ENGINEER VILLAGE OF DOWNERS GROVE 5101 WALNUT AVENUE DOWNERS GROVE, IL 60515 PHONE: 630/434-2453 FAX: 630/434-5495 www.downers.us

<u>CALL FOR BIDS – FIXED WORKS PROJECT</u>

Bid No.: <u>SW-070-12</u>

The VILLAGE OF DOWNERS GROVE will receive bids Monday thru Friday, 8:00 A.M. to 5:00 P.M. at the Public Works Building, 5101 Walnut Avenue, Downers Grove, IL 60515.

The Village Council reserves the right to accept or reject any and all bids, to waive technicalities and to accept or reject any item of any Bid.

The documents constituting component parts of this Contract are the following:

- I. CALL FOR BIDS
- II. TERMS & CONDITIONS
- III. GENERAL PROVISIONS
- IV. SPECIAL PROVISIONS
- V. BID & CONTRACT FORM

All Bidders MUST submit the entire bid package, with one original Bid Form. Upon formal Award, the successful Bid will automatically convert to a Contract, and the successful Bidder will receive a copy of the executed contract upon formal award of the Bid with the Notice of Award.

DO NOT DETACH ANY PORTION OF THIS DOCUMENT. INVALIDATION COULD RESULT.

I. CALL FOR BIDS and INSTRUCTIONS TO BIDDERS

1. GENERAL

1.1 Notice is hereby given that Village of Downers Grove will receive sealed bids up to: APRIL 20, 2012 @ 10:00AM

1.2 Defined Terms:

- 1.2.1 Village the Village of Downers Grove acting through its officers or agents.
- 1.2.2 Contract Documents this document plus any drawings issued therewith, any addenda and the Bidder's completed proposal, bonds and all required certifications.
- 1.2.3 Bid this document completed by an individual or entity and submitted to the Village.
- 1.2.4 Bidder the individual or entity who submits or intends to submit a bid proposal to the Village.
- 1.2.5 Contractor the individual or entity whose bid is selected by the Village and who enters into a contract with the Village.
- 1.2.6 Work the construction or service defined herein.
- 1.2.7 Day unless otherwise stated all references to day "Day" "Days", "day" or "days" shall refer to calendar days.
- 1.2.8 Proposal Guaranty the required bid deposit.
- 1.3 Bids must be received at the Village by the time and date specified. Bids received after the specified time and date will not be accepted and will be returned unopened to the Bidder.
- 1.4 Bids shall be sent to the Village of Downers Grove, ATTN: Jim Tock, in a sealed envelope marked "SEALED BID". The envelope shall be marked with the name of the project, date, and time set for receipt of Bids. The bid package may be submitted any time prior to the time set for receipt of Bids.
- 1.5 All Bids must be submitted on the forms supplied by the Village and signed by a proper official of the company submitting the Bid. Telephone, email and fax Bids will not be accepted.
- 1.6 Under penalty of perjury, the Bidder certifies by submitting this Bid that he has not acted in collusion with any other Bidder or potential Bidder.

2. BID PREPARATION

- 2.1 It is the responsibility of the Bidder to carefully examine the Contract Documents and to be familiar with all of the requirements, stipulations, provisions, and conditions surrounding the proposed Work.
- 2.2 The Bidder shall inspect the site of the proposed Work in detail, investigate and become familiar with all the local conditions affecting the Work and become fully acquainted with the detailed requirements

of the Work. Submitting a Bid shall be a conclusive assurance and warranty that the Bidder has made these examinations and that the Bidder understands all requirements for the performance of the Work. If the Bid is accepted, the Bidder will be responsible for all errors in the Bid resulting from his willing or neglectful failure to comply with these instructions. IN NO CASE WILL THE VILLAGE BE RESPONSIBLE FOR ANY COSTS, EXPENSES, LOSSES OR CHANGES IN ANTICIPATED MARGINS OF PROFIT RESULTING FROM THE WILLING OR NEGLECTFUL FAILURE OF THE BIDDER TO MAKE THESE EXAMINATIONS. THE VILLAGE WILL NOT BE RESPONSIBLE FOR ANY COSTS, EXPENSES, LOSSES OR CHANGES IN ANTICIPATED MARGINS OF PROFIT RESULTING FROM THE WILLING OR NEGLECTFUL FAILURE OF THE CONTRACTOR TO PROVIDE THE KNOWLEDGE, EXPERIENCE AND ABILITY TO PERFORM THE WORK REQUIRED BY THIS CONTRACT. No changes in the prices, quantities or contract provisions shall be made to accommodate the inadequacies of the Bidder, which might be discovered subsequent to award of contract. The Bidder shall take no advantage of any error or omission in the Contract Documents nor shall any error or omission in the Contract Documents serve as the basis for an adjustment of the amounts paid to the Bidder.

- 2.3 When the Contract Documents include information pertaining to subsurface explorations, borings, test pits, and other preliminary investigations, such information is included solely for the convenience of the Bidder. *The Village assumes no responsibility whatsoever with respect to the sufficiency of the information, and does not warrant, neither expressly nor by implication, that the conditions indicated represent those existing throughout the Work, or that unanticipated developments may not occur.*
- 2.4 Any information shown in the Contract Documents regarding the locations of underground utility facilities is included solely for the convenience of the Bidder. The Village assumes no responsibility whatsoever with respect to the sufficiency, accuracy or inadequacy of such information. It shall be the Bidder's responsibility to obtain detailed information from the respective utility companies relating to the location of their facilities and the work schedules of the utility companies for removing or adjusting them. Utilities whose facilities may be affected by the work include, but may not be limited to, the following: Nicor, ComEd, SBC, Comcast Cable, Downers Grove Sanitary District, and Village water, storm sewer, and street lighting systems.
- 2.5 No oral or telephone interpretations of specifications shall be binding upon the Village. All requests for interpretations or clarifications shall be made in writing and received by the Village at least five (5) business days prior to the date set for receipt of Bids or the pre-bid conference, if offered. The Village shall make all changes or interpretations of the Contract Documents in a written addendum and shall provide an addendum to any Bidder of record. Any and all changes to the Contract Documents are valid only if they are included by written addendum to all Bidders. Each Bidder must acknowledge receipt of any addenda by indicating same on the Bid Form. Each Bidder, by acknowledging receipt of any addenda, is responsible for the contents of the addenda and any changes to the Bid therein. Failure to acknowledge any addenda may cause the Bid to be rejected. The Village will not assume responsibility for receipt of any addenda. In all cases, it will be the Bidder's responsibility to obtain all addenda issued. Bidders will provide written acknowledgement of receipt of each addendum issued with the bid submission.
- 2.6 An estimate of the quantities of Work to be performed and the materials to be furnished is shown in the Bid Form. It is given as a basis for comparing the properly submitted Bids, and shall be used by the Village in awarding the Contract. The Village does not expressly warrant nor imply that the

estimated quantities shown will correspond with those quantities required to perform the Work. No Bidder shall plead misunderstanding or deception because of such an estimate of quantities, or because of the character, location or other conditions pertaining to the Work. Payment shall be based on the actual quantities of work properly performed in accordance with the Contract, at the Contract unit prices specified. The Village reserves the right to increase, decrease or omit entirely, any or all items. No allowance will be made for any change in anticipated profits due to an increase or decrease in the original estimate of quantities.

- 2.7 The Bidder must submit his Bid on the form furnished by the Village. The Bid shall be executed properly, and Bids shall be made for all items indicated in the Bid Form. The Bidder shall indicate, in figures, a unit price or lump sum price for each of the separate items called for in the Bid Form. The Bidder shall show the products of the respective quantities and unit prices in the column provided for that purpose. The gross sum shown in the place indicated in the Bid Form shall be the summation of said products. All writing shall be with ink or typewriter, except the signature of the Bidder, which shall be written with ink.
- 2.8 In case of error in the extension of prices in the Bid, the hourly rate or unit price will govern. In case of discrepancy in the price between the written and numerical amounts, the written amount will govern.
- 2.9 All costs incurred in the preparation, submission, and/or presentation of any Bid including the Bidder's travel or personal expenses shall be the sole responsibility of the Bidder and will not be reimbursed by the Village.
- 2.10 The Bidder hereby affirms and states that the prices quoted herein constitute the total cost to the Village for all work involved in the respective items, as well as the materials to be furnished in accordance with the collective requirements of the Contract Documents. The Bidder also affirms that this cost includes all insurance, bonds, royalties, transportation charges, use of all tools and equipment, superintendence, overhead expense, profits and other work, services and conditions necessarily involved in the work to be done.
- 2.11 The Bidder shall complete and submit with the Bid an "Affidavit" (IDOT Form BC-57, or similar)listing all uncompleted contracts, including subcontract work; all pending low bids not yet awarded or rejected, and equipment available.
- 2.12 The Bidder shall complete and submit with the Bid a "Municipal Reference List" indicating other municipalities for which the Bidder has successfully performed similar work.

3. PRE-BID CONFERENCE

- 3.1 A pre-bid conference may be offered to provide additional information, inspection or review of current facilities or equipment, and to provide an open forum for questions from Bidders. This pre-bid conference is not mandatory (unless stated "Required" on the cover of this document), but attendance by Bidders is strongly advised as this will be the last opportunity to ask questions concerning the Bid.
- 3.2 Questions may be posed in writing to the Village (faxed and emailed questions are acceptable), but must be received by the Village prior to the scheduled time for the pre-bid conference. Questions received will be considered at the conference. An addendum may be issued as a result of the pre-bid

conference. Such an addendum is subject to the provisions for issuance of an addendum as set forth in Section 2.5 above.

3.3 No Contract Documents will be issued after the pre-bid conference except to attendees.

4. **BID SUBMISSION**

- 4.1 An original copy of the sealed bid marked as indicated in Section 1 shall be submitted to the Village.
- 4.2 A bid deposit will be required, which shall not exceed ten percent (10%) of the estimated cost of the work to be furnished. Such bid deposit shall be in the form of a bid bond, certified check, cash or money order. Checks shall be drawn upon a bank of good standing payable to the order of the Village and said deposit shall be forfeited to the Village in the event the Bidder neglects or refuses to enter into a contract and bond when required, with approved sureties, to execute the Work or furnish the material for the price mentioned in his Bid and according to the plans and specifications in case the contract shall be awarded to him.
- 4.3 Bids shall be publicly opened at the hour and place indicated above.

5. BID MODIFICATION OR WITHDRAWAL

- 5.1 A Bid that is in the possession of the Village may be altered by a letter bearing the signature or name of the person authorized for submitting a Bid, provided that it is received prior to the time and date set for the bid opening. Telephone, email or verbal alterations of a Bid will not be accepted.
- 5.2 A Bid that is in the possession of the Village may be withdrawn by the Bidder, up to the time set for the bid opening, by a letter bearing the signature or name of the person authorized for submitting Bids. Bids may not be withdrawn after the bid opening and shall remain valid for a period of ninety (90) days from the date set for the bid opening, unless otherwise specified.
- 5.3 Any Bidder who does not submit a Bid is requested to return the enclosed Statement of "No Bid" postcard. Bidders not submitting Bids or "No Bid Statement" may otherwise be removed from the Village's bid mailing list.

6. **BID REJECTION**

6.1 Bids that contain omissions, erasures, alterations, additions not called for, conditional bids or alternate bids not called for, or irregularities of any kind, shall be rejected as informal or insufficient. Bids otherwise acceptable, which are not accompanied by the proper Proposal Guaranty, shall also be rejected as informal or insufficient. The Village reserves the right however, to reject any or all Bids and to waive such technical error as may be deemed best for the interest of the Village.

7. BIDDER COMPETENCY

7.1 No Bid will be accepted from or contract awarded to any person, firm or corporation that is in arrears or is in default upon any debt or contract. The Bidder, if requested, must present evidence to the Village of ability and possession of necessary facilities, and financial resources to comply with the terms of the Contract Documents. Evidence must be presented within three (3) business days.

8. **BIDDER DISQUALIFICATION**

8.1 Any one or more of the following causes may be considered as sufficient for the disqualification of a

Bidder and the rejection of their Bid.

- 8.1.1 More than one Bid for the same Work from an individual, firm partnership, or corporation under the same or different names.
- 8.1.2 Evidence of collusion among Bidders.
- 8.1.3 Unbalanced Bids in which the prices for some items are substantially out of proportion to the prices for other items.
- 8.1.4 Failure to submit a unit price for each item of Work listed in the Bid Form.
- 8.1.5 Lack of competency as revealed by financial statement or experience questionnaire.
- 8.1.6 Unsatisfactory performance record as shown by past work, judged from the standpoint of workmanship and progress.
- 8.1.7 Uncompleted work which, in the judgment of the Village, might hinder or prevent the prompt completion of this Work.
- 8.1.8 Failure to submit a signed Bidder's Certificate stating the following:
 - 8.1.8.1 That the Bidder is not barred from bidding on this Contract as a result of a violation of Sections 720 ILCS 5/33-E3 and 720 ILCS 5/33-E4 of the Illinois Compiled Statutes; and
 - 8.1.8.2 The Bidder is not delinquent in the payment of any tax administered by the Illinois Department of Revenue; and
 - 8.1.8.3 The Bidder will maintain the types and levels of insurance required by the terms of this contract; and
 - 8.1.8.4 The Bidder will comply with the Illinois Prevailing Wage Act, 820 ILCS 130/1 et seq.

9. BASIS OF AWARD

9.1 The Village reserves the exclusive right to accept or reject any and all Bids or to waive sections, technicalities and irregularities, or to accept or reject any Bid or any item of any Bid.

10. AWARD OF CONTRACT

- 10.1 Unless the Village exercises its right to reject all Bids, the Contract will be awarded to that responsible Bidder whose Bid, conforming to the Contract Documents, will be most advantageous to the Village, price and other factors considered. (the credentials, financial information, bonding capacity, insurance protection, qualifications of the labor and management of the firm, past experience and ability to complete the project within time frame required lowest responsible bidder)
- 10.2 Unless otherwise specified, if a Contract is not awarded within ninety (90) days after the opening of

Bids, a Bidder may file a written request with the Village for the withdrawal of their Bid. The Village will have a maximum of ten (10) days after the receipt of such request to award the Contract or release the Bidder from further obligation by return of the Bidder's bid deposit. Any attempt or actual withdrawal or cancellation of a Bid by the awarded contractor who has been notified by the Village of the acceptance of said Bid shall be considered a breach of contract.

11. RETURN OF BID DEPOSIT

11.1 The bid deposit of all except the three (3) lowest responsive bidders on each contract will be returned within fifteen (15) days after the opening of Bids. The remaining bid deposits of each contractor will be returned within fifteen (15) days after the Village Council has awarded the contract and the required appurtenances to the contract have been received.

12. FAILURE TO ENTER INTO CONTRACT

- 12.1 Failure on the part of the successful Bidder to execute a Contract and provide acceptable bonds, as provided herein, within ten (10) days from the date of receipt of the Contract and Notice of Award from the Village, will be considered as just cause for the revocation of the award. The Bidder's bid security shall then be forfeited to the Village, not as a penalty but in payment of liquidated damages sustained as a result of such failure.
- 12.2 The Bidder shall not be allowed to claim lack of receipt where the Contract and Notice of Award was mailed by U.S. Postal Services certified mail to the business address listed in his Bid. In case the Village does not receive evidence of receipt within ten (10) days of the date of Notice of Award, the Village may revoke the award. The Bidder shall then forfeit the bid security to the Village, not as a penalty but in payment of liquidated damages sustained as the result of such failure to execute the Contract.
- 12.3 By submitting a Bid, the Bidder understands and agrees that, if his Bid is accepted, and he fails to enter into a contract forthwith, he shall be liable to the Village for any damages the Village may thereby suffer.

13. SECURITY FOR PERFORMANCE

13.1 The successful Bidder shall, within ten (10) days after acceptance of the Bidder's Bid by the Village, furnish a Performance Bond and a Materials and Labor Payment Bond acceptable to the Village in the full amount of the Bid. Said bonds shall guarantee the Bidder's performance under the Contract Documents and shall guarantee payment of all subcontractors and material suppliers. Any bond shall include a provision as will guarantee faithful performance of the Illinois Prevailing Wage Act, 820 ILCS 130/1 et seq.

14. TAX EXEMPTION

14.1 The Village is exempt from Illinois sales or use tax for direct purchases of materials and supplies. A copy of the Illinois Sales Tax Exemption Form will be issued upon request. The Village's federal identification number will also be provided to the selected Bidder.

15. RESERVED RIGHTS

15.1 The Village reserves the right to waive sections, irregularities, technicalities and informalities to this Contract and to accept any Bid and to reject any and all Bids and to disapprove of any and all subcontractors as may be in the best interest of the Village. Time and date requirements for receipt of Bids, however, will not be waived.

16. CATALOGS AND SHOP DRAWINGS

16.1 Each Bidder shall submit catalogs, descriptive literature, and detailed drawings, where applicable, to fully illustrate and describe the work or material he proposes to furnish.

17. TRADE NAMES AND SUBSTITUTIONS

17.1 Certain materials and equipment are specified by a manufacturer or trade name to establish standards or quality and performance and not for the purpose of limiting competition. Products of other manufacturers may be substituted, if, in the opinion of the Village, they are equal to those specified in quality, performance, design, and suitability for intended use. If the Bidder proposes to furnish an "equal", the proposed "equal" item must be so indicated in the written Bid. Where two or more items are specified, the selection among those specified is the Bidder's option, or he may submit his Bid on all such items. Detail specification sheets shall be provided by Bidder for all substituted items.

II. TERMS AND CONDITIONS

18. VILLAGE ORDINANCES

18.1 The successful Bidder, now the Contractor, will strictly comply with all ordinances of the Village of Downers Grove and laws of the State of Illinois.

19. USE OF VILLAGE'S NAME

19.1 The Contractor is specifically denied the right of using in any form or medium the name of the Village for public advertising unless the Village grants express permission.

20. HOURS OF WORK

20.1 The Contractor shall do no work between the hours of 7:00 p.m. and 7:00 a.m., nor on Saturdays, Sundays or legal holidays, unless otherwise approved in writing by the Village. However, such work may be performed at any time if necessary, for the proper care and protection of work already performed, or in case of an emergency. All after-hour work is still subject to the permission of the Village.

21. PERMITS AND LICENSES

21.1 The Contractor shall obtain all necessary permits and licenses required to complete the Work. The cost of acquisition of all necessary permits, bonds, insurance and services as specified herein shall be considered INCIDENTAL, and no additional compensation will be allowed the Contractor.

22. INSPECTION

22.1 The Village shall have a right to inspect, by its authorized representative, any material, components or workmanship as herein specified. Materials, components or workmanship that have been rejected by the Village as not in accordance with the terms of the contract specifications shall be replaced by the Contractor at no cost to the Village.

23. **DELIVERIES**

23.1 All materials shipped to the Village must be shipped F.O.B. designated location, Downers Grove, Illinois.

24. SPECIAL HANDLING

24.1 Prior to delivery of any product that is caustic, corrosive, flammable or dangerous to handle, the Contractor will provide written directions as to methods of handling such products, as well as the antidote or neutralizing material required for its first aid before delivery. Contractor shall also notify the Village and provide material safety data sheets for all substances used in connection with this Contract which are defined as toxic under the <u>Illinois Toxic Substances Disclosure to Employees Act</u>.

25. NONDISCRIMINATION

- 25.1 Contractor shall, as a party to a public contract:
 - 25.1.1 Refrain from unlawful discrimination in employment and undertake affirmative action to assure equality of employment opportunity and eliminate the effects of past discrimination;
 - 25.1.2 By submission of this Bid, the Contractor certifies that he is an "equal opportunity employer" as defined by Section 2000(e) of Chapter 21, Title 42, U.S. Code Annotated and Executive

Orders #11246 and #11375, which are incorporated herein by reference. The Equal Opportunity clause, Section 6.1 of the Rules and Regulations of the Department of Human Rights of the State of Illinois, is a material part of any contract awarded on the basis of this Bid.

25.2 It is unlawful to discriminate on the basis of race, color, sex, national origin, ancestry, age, marital status, physical or mental handicap or unfavorable discharge for military service. Contractor shall comply with standards set forth in Title VII of the Civil Rights Act of 1964, 42 U.S.C. Secs. 2000 et seq., The Human Rights Act of the State of Illinois, 775 ILCS 5/1-101 et. seq, and The Americans With Disabilities Act, 42 U.S.C. Secs. 12101 et. seq.

26. SEXUAL HARASSMENT POLICY

- 26.1 The Contractor, as a party to a public contract, shall have a written sexual harassment policy that:
 - 26.1.1 Notes the illegality of sexual harassment;
 - 26.1.2 Sets forth the State law definition of sexual harassment;
 - 26.1.3 Describes sexual harassment utilizing examples;
 - 26.1.4 Describes the Contractor's internal complaint process including penalties;
 - 26.1.5 Describes the legal recourse, investigative and complaint process available through the Illinois Department of Human Rights and the Human Rights Commission and how to contact these entities; and
 - 26.1.6 Describes the protection against retaliation afforded under the Illinois Human Rights Act.

27. EQUAL EMPLOYMENT OPPORTUNITY

- 27.1 In the event of the Contractor's non-compliance with the provisions of this Equal Employment Opportunity Clause, the Illinois Human Rights Act or the Rules and Regulations of the Illinois Department of Human Rights ("Department"), the Contractor may be declared ineligible for future contracts or subcontracts with the State of Illinois or any of its political subdivisions or municipal corporations, and the contract may be canceled or voided in whole or in part, and such other sanctions or penalties may be imposed or remedies invoked as provided by statute or regulation. During the performance of this Contract, the Contractor agrees as follows:
 - 27.1.1 That it will not discriminate against any employee or applicant for employment because of race, color, religion, sex, marital status, national origin or ancestry, age, physical or mental disability unrelated to ability, military status, order of protection status, sexual orientation, sexual identity, or an unfavorable discharge from military service; and further that it will examine all job classifications to determine if minority persons or women are underutilized and will take appropriate affirmative action to rectify any such underutilization.
 - 27.1.2 That, if it hires additional employees in order to perform this Contract or any portion thereof, it will determine the availability (in accordance with the Department's Rules and Regulations) of minorities and women in the area(s) from which it may reasonably recruit and it will hire

for each job classification for which employees are hired in such a way that minorities and women are not underutilized.

- 27.1.3 That, in all solicitations or advertisements for employees placed by it or on its behalf, it will state that all applicants will be afforded equal opportunity without discrimination because of race, color, religion, sex, marital status, national origin or ancestry, age, physical or mental disability unrelated to ability, military status, order of protection status, sexual orientation, or an unfavorable discharge from military services.
- 27.1.4 That it will send to each labor organization or representative of workers with which it has or is bound by a collective bargaining or other agreement or understanding, a notice advising such labor organization or representative of the Contractor's obligations under the Illinois Human Rights Act and the Department's Rules and Regulations. If any such labor organization or representative fails or refuses to cooperate with the Contractor in its efforts to comply with such Act and Rules and Regulations, the Contractor will promptly so notify the Department and the contracting agency and will recruit employees from other sources when necessary to fulfill its obligations thereunder.
- 27.1.5 That it will submit reports as required by the Department's Rules and Regulations, furnish all relevant information as may from time to time be requested by the Department or the contracting agency, and in all respects comply with the Illinois Human Rights Act and the Department's Rules and Regulations.
- 27.1.6 That it will permit access to all relevant books, records, accounts and work sites by personnel of the contracting agency and the Department for purpose of investigation to ascertain compliance with the Illinois Human Rights Act and the Department's Rules and Regulations.
- 27.1.7 That it will include verbatim or by reference the provisions of this clause in every subcontract it awards under which any portion of the contract obligations are undertaken or assumed, so that such provisions will be binding upon such subcontractor. In the same manner as with other provisions of this Contract, the Contractor will be liable for compliance with applicable provisions of this clause by such subcontractors; and further it will promptly notify the contracting agency and the Department in the event any subcontractor fails or refuses to comply therewith. In addition, the Contractor will not utilize any subcontractor declared by the Illinois Human Rights Commission to be ineligible for contracts or subcontracts with the State of Illinois or any of its political subdivision or municipal corporations.

28. DRUG FREE WORK PLACE

28.1 Contractor, as a party to a public contract, certifies and agrees that it will provide a drug free workplace by:

28.1.1 Publishing a statement:

(1) Notifying employees that the unlawful manufacture, distribution, dispensation, possession or use of a controlled substance, including cannabis, is prohibited in the Village's or Contractor's workplace.

(2) Specifying the actions that will be taken against employees for violations of such prohibition.

(3) Notifying the employee that, as a condition of employment on such contract or grant, the employee will:

(A) abide by the terms of the statement; and

(B) notify the employer of any criminal drug statute conviction for a violation occurring in the workplace no later than five (5) days after such conviction.

28.1.2 Establishing a drug free awareness program to inform employees about:

(1) the dangers of drug abuse in the workplace;

- (2) the Village's or Contractor's policy of maintaining a drug free workplace;
- (3) any available drug counseling, rehabilitation and employee assistance programs;
- (4) the penalties that may be imposed upon employees for drug violations.
- 28.1.3 Providing a copy of the statement required by subparagraph 1.1 to each employee engaged in the performance of the contract or grant and to post the statement in a prominent place in the workplace.
- 28.1.4 Notifying the contracting or granting agency within ten (10) days after receiving notice under part (3)(B) of subparagraph 1.1 above from an employee or otherwise receiving actual notice of such conviction.
- 28.1.5 Imposing a sanction on, or requiring the satisfactory participation in a drug abuse assistance or rehabilitation program by, any employee who is so convicted as required by section 5 of the Drug Free Workplace Act.
- 28.1.6 Assisting employees in selecting a course of action in the event drug counseling, treatment and rehabilitation is required and indicating that a trained referral team is in place.
- 28.1.7 Making a good faith effort to continue to maintain a drug free workplace through implementation of the Drug Free Workplace Act.

29. SUBSTANCE ABUSE PREVENTION ON PUBLIC WORKS PROJECTS ACT

29.1 In the event this is a public works project as defined under the Prevailing Wage Act, 820 ILCS 130/2, Contractor agrees to comply with the Substance Abuse Prevention on Public Works Projects Act, 820 ILCS 265/1 *et seq.*, and further agrees that all of its subcontractors shall comply with such Act.. As required by the Act, Contractor agrees that it will file with the Village prior to commencing work its written substance abuse prevention program and/or that of its subcontractor(s) which meet or exceed the requirements of the Act.

30. PREVAILING WAGE ACT

- 30.1 Contractor agrees to comply with the Illinois Prevailing Wage Act, 820 ILCS 130/1 *et seq.*, for all work completed under this Contract. Contractor agrees to pay the prevailing wage and require that all of its subcontractors pay prevailing wage to any laborers, workers or mechanics who perform work pursuant to this Contract or related subcontract. For applicable rates, go to the State of Illinois Department of Labor website and use the most current DuPage County rate.
- 30.2 Contractor and each subcontractor shall keep or cause to be kept an accurate record of names, occupations and actual wages paid to each laborer, workman and mechanic employed by the

Contractor in connection with the contract. This record shall be open to inspection at all reasonable hours by any representative of the Village or the Illinois Department of Labor and must be preserved for four (4) years following completion of the contract.

- 30.3 Since this is a contract for a public works project, as defined in 820 ILCS 130/2, Contractor agrees to post at the job site in an easily accessible place, the prevailing wages for each craft or type of worker or mechanic needed to execute the contract or work to be performed.
- 30.4 Because this is a public works project as defined under the Prevailing Wage Act, 820 ILCS 130/2, any and all contractors and subcontractors shall submit certified payroll records to the Village no later than the tenth (10th) day of each calendar month for the immediately preceding month in which construction on a public works project has occurred. WITHOUT THIS PAPERWORK, NO INVOICE SHALL BE PAID BY THE VILLAGE. Contractors and subcontractors must also submit a statement affirming that the records are true and accurate, that the wages paid to each worker are not less than the prevailing rate, and that the contractor and subcontractor are aware that filing false records is a Class A misdemeanor. The records must include the name, address, telephone number, social security number, job classification, hours of work, hourly rate, and start and end time of work each day for every worker employed on the public work. The Village reserves the right to check the pay stubs of the workers on the job. The Village further cautions that payment for any services rendered pursuant to this Contract may be predicated upon receipt of said records.
- 30.5 In the event that this is a construction project where Motor Fuel tax monies or state grant monies are used in the construction, maintenance and extension of municipal streets, traffic control signals, street lighting systems, storm sewers, pedestrian subways or overhead crossings, sidewalks and off-street parking facilities, and the like, the Village will require an Apprenticeship and Training Certification, attached after the Bidder's Certification.
- 30.6 Any bond furnished as security for performance shall include a provision as will guarantee faithful performance of the Illinois Prevailing Wage Act, 820 ILCS 130/1 et seq.

31. PATRIOT ACT COMPLIANCE

31.1 The Contractor represents and warrants to the Village that neither it nor any of its principals, shareholders, members, partners, or affiliates, as applicable, is a person or entity named as a Specially Designated National and Blocked Person (as defined in Presidential Executive Order 13224) and that it is not acting, directly or indirectly, for or on behalf of a Specially Designated National and Blocked Person. The Contractor further represents and warrants to the Village that the it and its principals, shareholders, members, partners, or affiliates, as applicable are not, directly or indirectly, engaged in, and are not facilitating, the transactions contemplated by this Contract on behalf of any person or entity named as a Specially Designated National and Blocked Person. The Contractor hereby agrees to defend, indemnify and hold harmless the Village, and its elected or appointed officers, employees, agents, representatives, engineers and attorneys, from and against any and all claims, damages, losses, risks, liabilities and expenses(including reasonable attorney's fees and costs) arising from or related to any breach of the foregoing representations and warranties.

32. INSURANCE REQUIREMENTS

32.1 Prior to starting the Work, Contractor and any Subcontractors shall procure, maintain and pay for such insurance as will protect against claims for bodily injury or death, or for damage to property,

including loss of use, which may arise out of operations by the Contractor or Subcontractor or any Sub-Sub Contractor or by anyone employed by any of them, or by anyone for whose acts any of them may be liable. Such insurance shall not be less than the greater of coverages and limits of liability specified below or any coverages and limits of liability specified in the Contract Documents or coverages and limits required by law unless otherwise agreed to by the Village.

| Workers Compensation | \$500,000 | Statutory |
|---|---|--|
| Employers Liability | \$1,000,000 \$1,000,000 \$1,000,000 | Each Accident Disease Policy Limit Disease Each Employee |
| Comprehensive General Liability | \$2,000,000 \$2,000,000 | Each Occurrence Aggregate (Applicable on a Per Project Basis) |
| Commercial Automobile Liability | \$1,000,000 | Each Accident |
| Professional Errors & Omissions (pursuant to section.9 below) | \$2,000,000 \$2,000,000 | Each Claim Annual Aggregate |
| Umbrella Liability | \$ 5,000,000 | |

- 32.2 Comprehensive General Liability Insurance required under this paragraph shall be written on an occurrence form and shall include coverage for Products/Completed Operations, Personal Injury with Employment Exclusion (if any) deleted, Blanket XCU and Blanket Contractual Liability insurance applicable to defense and indemnity obligations and other contractual indemnity assumed under the Contract Documents. The limit must be on a "Per Project Basis".
- 32.3 Commercial Automobile Liability Insurance required under this paragraph shall include coverage for all owned, hired and non-owned automobiles.
- 32.4 Workers Compensation coverage shall include a waiver of subrogation against the Village.
- 32.5 Comprehensive General Liability, Employers Liability and Commercial Automobile Liability Insurance may be arranged under single policies for full minimum limits required, or by a combination of underlying policies with the balance provided by Umbrella and/or Excess Liability policies.
- 32.6 Contractor and all Subcontractors shall have their respective Comprehensive General Liability (including products/completed operations coverage), Employers Liability, Commercial Automobile Liability, and Umbrella/Excess Liability policies endorsed to add the "Village of Downers, its officers, officials, employees and volunteers" as "additional insureds" with respect to liability arising

out of operations performed; claims for bodily injury or death brought against the Village by any Contractor or Subcontractor employees, or the employees of Subcontractor's subcontractors of any tier, however caused, related to the performance of operations under the Contract Documents. Such insurance afforded to the Village shall be endorsed to provide that the insurance provided under each policy shall be *Primary and Non-Contributory*.

- 32.7 Contractor and all Subcontractors shall maintain in effect all insurance coverages required by the Contract Documents at their sole expense and with insurance carriers licensed to do business in the State of Illinois and having a current A. M. Best rating of no less than A- VIII. In the event that the Contractor or any Subcontractor fails to procure or maintain any insurance required by the Contract Documents, the Village may, at its option, purchase such coverage and deduct the cost thereof from any monies due to the Contractor or Subcontractor, or withhold funds in an amount sufficient to protect the Village, or terminate this Contract pursuant to its terms.
- 32.8 All insurance policies shall contain a provision that coverages and limits afforded hereunder shall not be canceled, materially changed, non-renewed or restrictive modifications added, without thirty (30) days prior written notice to the Village. Renewal certificates shall be provided to the Village not less than five (5) days prior to the expiration date of any of the required policies. All Certificates of Insurance shall be in a form acceptable to the Village and shall provide satisfactory evidence of compliance with all insurance requirements. The Village shall not be obligated to review such certificates or other evidence of insurance, or to advise Contractor or Subcontractor of any deficiencies in such documents, and receipt thereof shall not relieve the Contractor or Subcontractor from, nor be deemed a waiver of the right to enforce the terms of the obligations hereunder. The Village shall have the right to examine any policy required and evidenced on the Certificate of Insurance.
- 32.9 If the Work under the Contract Documents includes design, consultation, or any other professional services, Contractor or the Subcontractor shall procure, maintain, and pay for Professional Errors and Omissions insurance with limits of not less than \$2,000,000 per claim and \$2,000,000 annual aggregate. If such insurance is written on a claim made basis, the retrospective date shall be prior to the start of the Work under the Contract Documents. Contractor and all Subcontractors agree to maintain such coverage for three (3) years after final acceptance of the Project by the Village or such longer period as the Contract Documents may require. Renewal policies during this period shall maintain the same retroactive date.
- 32.10 Any deductibles or self-insured retentions shall be the sole responsibility of the Insured. At the option of the Village, either: the insurer shall reduce or eliminate such deductibles or self-insured retentions as respects the Village, its officers, officials, employees and volunteers; or the Contractor shall procure a bond guaranteeing payment of losses and related investigations, claim administration and defense expenses.

33. INDEMNITY AND HOLD HARMLESS AGREEMENT

33.1 To the fullest extent permitted by law, the Contractor shall indemnify, keep and save harmless the Village and its agents, officers, and employees, against all injuries, deaths, strikes, losses, damages, claims, suits, liabilities, judgments, costs and expenses, which may arise directly or indirectly from any negligence or from the reckless or willful misconduct of the Contractor, its employees, or its subcontractors.

33.2 The Contractor shall at its own expense, appear, defend and pay all charges of attorneys and all costs and other expenses arising therefrom or incurred in connection therewith, and, if any judgment shall be rendered against the Village in any such action, the Contractor shall, at its own expense, satisfy and discharge the same. This agreement shall not be construed as requiring the Contractor to indemnify the Village for its own negligence. The Contractor shall indemnify, keep and save harmless the Village only where a loss was caused by the negligent, willful or reckless acts or omissions of the Contractor, its employees, or its subcontractors.

34. SUBLETTING OF CONTRACT

34.1 No contract awarded by the Village shall be assigned or any part subcontracted without the written consent of the Village. In no case shall such consent relieve the Contractor from his obligation or change the terms of this Contract.

All approved subcontracts shall contain language which incorporates the terms and conditions of this Contract.

35. TERMINATION OF CONTRACT

- 35.1 The Village reserves the right to terminate the whole or any part of this Contract, upon written notice to the Contractor, for any reason.
- 35.2 The Village further reserves the right to terminate the whole or any part of this Contract, upon ten (10) days` written notice to the Contractor, in the event of default by the Contractor. Default is defined as failure of the Contractor to perform any of the provisions of this Contract or failure to make sufficient progress so as to endanger performance of this Contract in accordance with its terms. In the event that the Contractor fails to cure the default upon notice, and the Village declares default and termination, the Village may procure, upon such terms and in such manner as it may deem appropriate, supplies or services similar to those so terminated. The Village may also contact the issuer of the Performance Bond to complete the Work. The Contractor shall be liable for any excess costs for such similar supplies or services. Any such excess costs incurred by the Village may be set-off against any monies due and owing by the Village to the Contractor.

36. BILLING AND PAYMENT PROCEDURES

- 36.1 Payment will be made upon receipt of an invoice referencing Village purchase order number. Once an invoice and receipt of materials or service have been verified, the invoice will be processed for payment in accordance with the Village's payment schedule. The Village will comply with the Local Government Prompt Payment Act, 50 ILCS 505/1 et seq., in that any bill approved for payment must be paid or the payment issued to the Contractor within 60 days of receipt of a proper bill or invoice. If payment is not issued to the Contractor within this 60 day period, an interest penalty of 1.0% of any amount approved and unpaid shall be added for each month or fraction thereof after the end of this 60 day period, until final payment is made.
- 36.2 The Village shall review each bill or invoice in a timely manner after its receipt. If the Village determines that the bill or invoice contains a defect making it unable to process the payment request, the Village shall notify the Contractor as soon as possible after discovering the defect pursuant to rules promulgated under 50 ILCS 505/1 et seq. The notice shall identify the defect and any additional information necessary to correct it.

- 36.3 As this Contract is for work defined as a "fixed public work" project under the Illinois Prevailing Wage Act, 820 ILCS 130/2, any contractor or subcontractor is required to submit certified payroll records along with the invoice. No invoice shall be paid without said records.
- 36.4 Please send all invoices to the attention of: Village of Downers Grove Public Works, 5101 Walnut Ave, Downers Grove, IL 60515.

37. COMPLIANCE WITH OSHA STANDARDS

37.1 Equipment supplied to the Village must comply with all requirements and standards as specified by the Occupational Safety and Health Act. All guards and protectors as well as appropriate markings will be in place before delivery. Items not meeting any OSHA specifications will be refused.

38. CERCLA INDEMNIFICATION

- 38.1 The Contractor shall, to the maximum extent permitted by law, indemnify, defend, and hold harmless the Village, its officers, employees, agents, and attorneys from and against any and all liability, including without limitation, costs of response, removal, remediation, investigation, property damage, personal injury, damage to natural resources, health assessments, health settlements, attorneys' fees, and other related transaction costs arising under the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) of 1980, 42 U.S.C.A. Sec. 9601, <u>et seq.</u>, as amended, and all other applicable statutes, regulations, ordinances, and under common law for any release or threatened release of the waste material collected by the Contractor, both before and after its disposal.
- 38.2 If the Contractor encounters any waste material governed by the above Act, it shall immediately notify the Village and stop working in the area until the above requirements can be met.

39. COPYRIGHT or PATENT INFRINGEMENT

39.1 The Contractor agrees to indemnify, defend, and hold harmless the Village against any suit, claim, or proceeding brought against the Village for alleged use of any equipment, systems, or services provided by the Contractor that constitutes a misuse of any proprietary or trade secret information or an infringement of any patent or copyright.

40. BUY AMERICA

- 40.1 The Contractor agrees to comply with 49 U.S.C.5323(j), the Federal Transportation Administration's (FTA) Buy America regulations at 49 C.F.R. Part 661, and any amendments thereto, and any implementing guidance issued by the FTA, with respect to this Contract, when financed by Federal funds (through a grant agreement or cooperative agreement).
- 40.2 As a condition of responsiveness, the Contractor agrees to submit with its Bid submission, an executed Buy America Certificate, attached hereto.

41. CAMPAIGN DISCLOSURE

- 41.1 Any contractor, proposer, bidder or vendor who responds by submitting a bid or proposal to the Village of Downers Grove shall be required to submit with its bid submission, an executed Campaign Disclosure Certificate, attached hereto.
- 41.2 The Campaign Disclosure Certificate is required pursuant to the Village of Downers Grove

Council Policy on Ethical Standards and is applicable to those campaign contributions made to any member of the Village Council.

- 41.3 Said Campaign Disclosure Certificate requires any individual or entity bidding to disclose campaign contributions, as defined in Section 9-1.4 of the Election Code (10 ILCS 5/9-1.4), made to current members of the Village Council within the five (5) year period preceding the date of the bid or proposal release.
- 41.4 By signing the bid documents, contractor/proposer/bidder/vendor agrees to refrain from making any campaign contributions as defined in Section 9-1.4 of the Election Code (10 ILCS 5/9-1.4) to any Village Council member and any challengers seeking to serve as a member of the Downers Grove Village Council.

42. GUARANTEE PERIOD

42.1 The Contractor shall provide a guarantee in writing covering a minimum period of one (1) year after approval and acceptance of the Work. The Guarantee shall be in such form as the Village may prescribe, unless otherwise noted in the Specifications, and shall be submitted before receiving final payment. If longer guarantees are required, they will be noted in the Special Provisions for this project.

43. SUCCESSORS AND ASSIGNS

43.1 The terms of this Contract will be binding upon and inure to the benefit of the parties and their respective successors and assigns; provided, however, that neither party will assign this Contract in whole or in part without the prior written approval of the other. The Contractor will provide a list of key staff, titles, responsibilities, and contact information to include all expected subcontractors.

44. WAIVER OF BREACH OF CONTRACT

44.1 The waiver by one party of any breach of this Contract or the failure of one party to enforce at any time, or for any period of time, any of the provisions hereof will be limited to the particular instance and will not operate or be deemed to waive any future breaches of this Contract and will not be construed to be a waiver of any provision except for the particular instance.

45. CHANGE ORDERS

- 45.1 The contract price is a "not-to-exceed" cost. At any time additional work is necessary or requested, and the not-to-exceed price is increased thereby, all parties must agree to any change, addition or price increase in writing.
- 45.2 Change orders for public works projects which authorize an increase in the contract price in the is 50% or more of the original contract price or that authorize or necessitate any increase in the price of a subcontract under the contract that is 50% or more of the original subcontract price must be resubmitted for bidding in the same manner by which the original contract was bid. (50 ILCS 525/1)

46. SEVERABILITY OF INVALID PROVISIONS

46.1 If any provisions of this Contract are held to contravene or be invalid under the laws of any state, country or jurisdiction, contravention will not invalidate the entire Contract, but it will be construed as if not containing the invalid provision and the rights or obligations of the parties will be construed and enforced accordingly.

47 GOVERNING LAW

47.1 This Contract will be governed by and construed in accordance with the laws of the State of Illinois. Venue is proper only in the County of DuPage for state cases or the Northern District of Illinois for federal cases.

48. NOTICE

48.1 Any notice will be in writing and will be deemed to be effectively served when deposited in the mail with sufficient first class postage affixed, and addressed to the party at the party's place of business. Notices shall be addressed to the Village as follows:

Village Manager Village of Downers Grove 801 Burlington Ave. Downers Grove, IL 60515

And to the Contractor as designated on the Contract Form.

49. AMENDMENT

49.1 This Contract will not be subject to amendment unless made in writing and signed by all parties.

50. COOPERATION WITH FOIA COMPLIANCE

50.1 Contractor acknowledges that the Freedom of Information Act may apply to public records in possession of the Contractor or a subcontractor. Contractor and all of its subcontractors shall cooperate with the Village in its efforts to comply with the Freedom of Information Act. 5 ILCS 140/1 et.seq.

51. EMPLOYMENT OF ILLINOIS WORKERS ON PUBLIC WORKS ACT

51.1 If the work contemplated by this Contract is funded or financed in whole or in part with State Funds or funds administered by the State, Contractor agrees to comply with the terms of the Employment of Illinois Workers on Public Works Act by employing at least 90% Illinois laborers on the project. 30 ILCS 570/1 et seq. Contractor agrees further to require compliance with this Act by all of its subcontractors.

III. GENERAL PROVISIONS

1. STANDARD SPECIFICATIONS

- 1.1 The following standards shall govern the construction of the proposed improvements:
 - 1.1.1 <u>Standard Specifications for Water and Sewer Main Construction in Illinois</u>, Sixth Edition, 2009 (the Water & Sewer Specs.); and
 - 1.1.2 <u>Standard Specifications for Road and Bridge Construction</u> as adopted by the Illinois Department of Transportation, January 1, 2012; along with <u>Supplemental Specifications and Recurring Special Provisions</u> (collectively the "SSRBC") as adopted by the Illinois Department of Transportation, January 1, 2012; and
 - 1.1.3 Water Distribution Specifications, Village of Downers Grove, Illinois, revised March, 2006.
- 1.2 These Contract Documents shall take precedence whenever there are conflicts in the wording or statements made by the above specifications and these Contract Documents.
- 1.3 Unless otherwise referenced herein, Division I of the Water and Sewer Specs and Section 102 and Articles 104.02, 104.03, 104.07, 107.02, 107.27, 107.35, 108.10, 108.11, and 108.12 of the SSRBC are hereby suspended.

2. COOPERATION OF CONTRACTOR

- 2.1 The Contractor will be supplied with a minimum of 2 sets of approved plans and contract assemblies including Special Provisions, one set of which the Contractor shall keep available on the work site at all times. The Contractor shall give the work site constant attention necessary to facilitate the progress thereof, and shall cooperate with the Village in every way possible.
- 2.2 The Contractor shall have on the work site at all times, as the Contractor's agent, a competent Englishspeaking representative capable of reading and thoroughly understanding the Contract Documents, and thoroughly experienced in the type of work being performed. The representative shall also be capable of receiving instruction from the Village, and shall have full authority to promptly respond to such instruction. He shall be capable of supplying such materials, equipment, tools, labor and incidentals as may be required. The Contractor shall not replace him without prior written notification to the Village.

3. LEGAL REGULATIONS AND RESPONSIBILITY TO THE PUBLIC

- 3.1 Section 107 of the SSRBC shall govern the Contractor's legal regulations and responsibility to the public, with the following additions:
 - 3.1.1 PROJECT SAFETY. Add the following to Article 107.28:
 - 3.1.1.1 The Contractor shall conduct his work in such a manner as to provide an environment consistent with the safety, health and well being of those engaged in the completion of the Work specified in this Contract.
 - 3.1.1.2 The Contractor shall comply with all State and Federal Safety Regulations as

outlined in the latest revisions of the Federal Construction Safety Standards (Series 1926) and with applicable provisions and/or regulations of the Occupation Safety and Health Administration (OSHA) and Standards of the Williams-Stelger Occupational Health Safety Act of 1970 (Revised). SPECIAL ATTENTION SHALL BE PAID TO COMPLIANCE WITH OSHA'S SUBPART P – EXCAVATIONS STANDARD.

- 3.1.1.3 The Contractor and Village shall each be responsible for their own respective agents and employees.
- 3.1.2 BACKING PRECAUTIONS. Pursuant to Sections 14-139(b) and 14-171.1 of the Downers Grove Municipal Code, any motor vehicle which has an obstructed view to the rear and is to be operated at any time in reverse gear on the public streets of the Village by the Contractor or any subcontractor shall either be equipped with a reverse signal alarm (backup alarm) audible above and distinguishable from the surrounding noise level, or shall provide an observer to signal that it is safe to back up.
- 3.1.3 OVERWEIGHT, OVERWIDTH AND OVERHEIGHT PERMITS. The Village has and supports an overweight truck enforcement program. Contractors are required to comply with weight requirements and safety requirements as established by Illinois Law or Village Ordinance, for vehicles, vehicle operators and specialty equipment. In some instances, specialty equipment for road repairs or construction projects requires the movement of overweight, overwidth, or overheight loads utilizing a Village roadway. Such movement will require obtaining a permit from the Village Police Department's Traffic Supervisor.
- 3.1.4 BARRICADES AND WARNING SIGNS. The Contractor shall provide the Village with a telephone number of a person or company who is available 24 hours per day, seven days per week, to erect additional barricades or signs. If the Village or its representative deems it necessary for the Public's safety to erect additional barricades or signs during normal working hours, the Contractor will furnish the necessary barricades or signs, and have them in place within 30 minutes. If, after normal working hours, the requested signs are not in place within three hours after the request is made, the Village reserves the right to have the barricades and signs erected. The cost of erecting the barricades and signs shall be deducted by the Village from any payments due the Contractor.

4. **PROSECUTION AND PROGRESS**

- 4.1 Section 108 of the SSRBC shall govern the prosecution and progress of the work, with the following additions:
 - 4.1.1 Prior to commencing construction, a meeting will be held with the Contractor and the Village. Any questions concerning procedures, general conditions, special provisions, plans or specific items related to the project shall be answered and clarified. No Pre-Construction meeting shall be scheduled until submittals, performance bonds, and certificates of insurance are delivered to, and approved by, the Village.
 - 4.1.2 Weekly progress meetings may be required by the Village. If required, the Contractor shall have a capable person, such as a site superintendent or project manager, attend such meetings

and be prepared to report on the prosecution of the Work according to the progress schedule.

5. MEASUREMENT AND PAYMENT

- 5.1 Section 109 of the SSRBC shall govern measurement and payment, with the following additions:
 - 5.1.1 Modifies Article 109.07 Partial payments will be made per Section 36 of Part II of this document (Billing and Payment Procedures.)
 - 5.1.2 The Village will require that partial and final affidavits for all labor, materials and equipment used on the Project, be submitted with the partial and final payment requests. Such waivers shall indicate that charges for all labor, materials and equipment used on the project have been paid. Partial waivers from suppliers and subcontractors may be submitted after the first payment to the Contractor, and before the subsequent payment to that which they apply. However, partial waivers from the Contractor must accompany the invoice of the payment to which it applies. All final waivers, from all suppliers and subcontractors MUST accompany the Contractor's invoice upon submittal for final payment. A sworn statement by the Contractor shall accompany full waivers. Such requirement for full waivers is solely for the benefit of the Village and shall not be construed to benefit any other person. Partial payment for work done shall in no way imply acceptance of the work to that date.

IV. SPECIAL PROVISIONS

The following Special Provisions shall modify, supercede, or supplement the Standard Specifications referred to in Section III - General Provisions.

Where any section, subsection, paragraph, or subparagraph of the Standard Specifications is *supplemented* by any of the following paragraphs, the provisions of such section, subsection, paragraph, or subparagraph shall remain in effect. The Special Provisions shall govern in addition to the particular Standard Specification so supplemented, and not in lieu thereof.

Where any section, subsection, paragraph, or subparagraph of the Standard Specifications is *amended*, *voided*, *or superceded* by any of the following paragraphs, any provision of such section, subsection, paragraph, or subparagraph standing unaffected, shall remain in effect. The Special Provisions shall govern in lieu of any particular provision of the Standard Specification so amended, voided, or superceded, and not in addition to the portion changed.

GENERAL SCOPE OF WORK

Description: The Oakwood Avenue Storm Sewer Replacement Project shall generally consist of the following:

Base Bid:

- Open cut, remove, and replace bituminous pavement
- Construct new storm sewer and structures, including manholes, inlets and catch basins
- Restore all disturbed turf areas with sod
- Reconstruct northwest parkway/curb and gutter at intersection of Chicago and Oakwood
- Grind and overlay bituminous pavement for areas of road not directly impacted by storm sewer installation, patching poor areas as necessary

SP-1 GENERAL CONSTRUCTION REQUIREMENTS

The following general requirements are intended to govern the overall priority for the performance of the Work described in this Contract. As general requirements, they are not intended to dictate to the Contractor the precise method by which these tasks shall be performed.

All street openings made prior to November 15th shall be fully restored according to the applicable special provisions, and the street reopened to regular traffic upon the availability of hot-mix bituminous concrete. The Contractor shall assume the risk of restoration over those reaches of pipe installed but not yet pressure-tested for pipe integrity.

No more than three hundred linear feet (300 LF) of pavement may be open-cut and closed to use by the motoring public. Access to <u>all</u> individual drives within the current work zone must be restored at the end of each workday.

The Contractor shall maintain traffic flow on ALL STREETS during the day in accordance with the applicable special provision. Adequate signing and flagging is of particular importance for safe travel of all residents.

SP-2 CONSTRUCTION STAKING AND RECORD DRAWINGS

Description: Section 5-7 of the Water and Sewer Specs shall be replaced in its entirety by the following:

The Contractor shall furnish and place all construction layout stakes for this Project. Competent personnel with suitable equipment shall conduct this work, supervised by a licensed Illinois Land Surveyor. The Contractor shall be responsible for having the finished work conform substantially to the lines, grades, elevations and dimensions shown on the plans.

The Contractor shall provide adequate control points to construct the individual Project elements, and shall provide the Engineer with adequate control in close proximity to check the compliance of the elements constructed.

The Contractor shall record all field notes in standard survey field notebooks and those books shall become the property of the Village at the completion of the Project. All notes shall be neat, orderly and in an accepted format.

Prior to final payment, the Contractor shall provide the Village with record drawings showing the lines, grades, elevations and dimensions of all work constructed. The Contractor shall also provide digital files listing all constructed manholes, catch basins, inlets, vaults, and any other storm or water structures and/or critical items defined by the Engineer as part of the Project. The digital files shall list the items above as points with supplemental data as shown below in the Stormwater and Watermain GPS Code Lists.

Watermain GPS Code List

| Description | Entry |
|---------------------------------|--|
| Short Unique ID (1,2,3) | |
| special notes | |
| Location quality of valve point | good, fair, poor, hand |
| Unique ID, if applicable | |
| How was point collected? | HQGPS, locates, hand |
| Who collected point? | |
| Who owns valve? | VDG, private, other |
| What type of valve is it? | main line, interconnect, fire protection, domestic |
| | Short Unique ID (1,2,3,.) special notes Location quality of valve point Unique ID, if applicable How was point collected? Who collected point? Who owns valve? |

Stormwater GPS Code List

| Field Name | Description | Entry |
|--------------------------|--|--|
| Lid_Type | frame and grate type | solid, open, b-hive, rollback, square, guard, other, none |
| Structure | | inlet, manhole, catch basin, endsection, culvert, bridge, bilnd tap, other, none |
| Inverts (no inverts = 0) | # of inverts | |
| Strot_Dept (ft) | structure depth | |
| Invert_Dep (ft) | invert depths, starting at north position going clockwise | |
| Invert_Siz (in) | invert sizes, starting at north position going clockwise | |
| Invert_Mat | invert material starting at north position going clockwise | RCP, CMP, PVC, clay, ductile iron, plastic, other, none |
| Flow_Angle | | 90 degrees, 135 degrees, straight through, 1 hole, junction, other, none |
| Flow_Direc | | north, south, east, west, NE, NW, SE, SW, divide |
| Strct_Matr | structure material | cast, block, brick, unknown, other, none, clay |
| Condition | structure condition | new, good, repair, replace, clean, unknown |
| Point_Loca | location of shot taken on rim | Center, Rim, Centr StSide, Invert, Top Pipe, Top Center Wall, Nrim, Srim, |
| | | Erim, Wrim, Hand Marked, Flow Line |
| Comment1 | special comments | |
| Comment2 | special comments cont'd | |
| CollType | How point was collected | HQGPS, locates, hand |
| CollSource | Who collected point? | |
| Outfall | is the structure an outfall? | yes, no |

Basis of Payment: This work will be paid for at the contract LUMP SUM price for:

CONSTRUCTION STAKING AND RECORD DRAWINGS,

which price shall be payment in full for the work as specified herein.

SP-3 PRECONSTRUCTION VIDEOTAPING

Description: This work shall consist of furnishing all materials and labor required to perform a videotape survey of the construction limits, adjacent right-of-way, and adjacent structures bordering the work. This shall include, but not be limited to, existing buildings, garages, pavements, curb and gutter, sidewalks, fences, trees and landscaping. Two (2) copies of the videotape shall be furnished to the Village in DVD format. Videotaping shall be performed by a reputable company meeting the approval of the Village, in the presence of a representative of the Village, and shall be performed prior to the commencement of construction. The videotape survey shall serve as a basis for establishing damage that has occurred as a result of construction operations.

Basis of Payment: This work will be paid for at the contract LUMP SUM price for:

PRECONSTRUCTION VIDEOTAPING,

which price shall be payment in full for the work as specified herein.

SP-4 ACCESS AND WATER SHUT-OFF NOTIFICATION

If access to a driveway will be blocked, or water will be turned off, the Contractor shall give that resident or business proper written notification at least 24 hours in advance. The Contractor must provide them the opportunity to remove their cars from the drive or make other arrangements, and prepare for any shutdown of the water system. Samples of written notices shall be submitted to the Engineer for approval.

In addition, the Contractor shall be responsible for notifying the resident or business verbally on the morning of any driveway closure, to ensure awareness of the lack of access.

Basis of Payment: This work shall be considered INCIDENTAL to the project.


SP-5 TREE PROTECTION

Municipal Codes regarding trees, including tree protection requirements for public parkway trees, are located in Chapter 24 of the Downers Grove Municipal Code. Specifically, Municipal Codes 24-7 and 24-8 detail the public parkway tree protection sizes and fines for violations. The Village Forester shall approve all tree protection measures and any deviations. All tree protection measures and any deviations shall be noted in the contract specifications and on approved project plan sheets and permits using the guidelines listed below.

Tree protection shall include avoiding damage to the above ground tree branches and trunk, and the below ground root system and surrounding soil. Tree crowns and trunks shall not suffer any branch or bark loss. Roots shall be protected from compaction, storage of materials, severing, regrading of the parkway or excavation unless specifically noted on the project plan sheets.

The Critical Root Zone, or CRZ, is the area immediately surrounding a tree that must be protected from damage. In a municipal parkway setting with utilities and paved or concrete surfaces, the size of the CRZ has been adjusted to form a rectangle around the parkway tree trunk with minimum dimensions listed in the following table. The depth of the CRZ extends to 4 feet below the natural ground surface level.

| | Parkway <u>Tree diameter at 4.5'</u> 0 - 12.0 inches 12.1 - 24.0 inches 24.1 or more inches | Width street to property (<u>min. curb to sidewalk</u>) 10.0 feet 10.0 feet 10.0 feet | Length along street street(minimum) 10 feet 20 feet 30 feet | Depth 4 feet 4 feet 4 feet | |
|--|---|---|---|-------------------------------------|--|
| | | | | | |



For projects that involve excavations of less than one (1) foot in depth in the parkway or street and are replacing structures in the same location, fencing of the public parkway trees shall not be required. Example projects include, but are not limited to, street pavement resurfacing, curb removal/replacement, driveway removal/replacement, or sidewalk removal/repairs or new sidewalk installations. Contractors shall be mindful of the CRZ dimensions and potential for fines if any parkway trees suffer any unauthorized damage as determined by the Village Forester.

For projects that involve excavations of one (1) foot or more in depth in the parkway or street or both, fencing of the public parkway trees shall be required. Example projects include, but are not limited to, watermain

replacements with new roundway keystops and domestic service box installations, sanitary line replacements and new service connections, new or replacement natural gas services, new or replacement phone or fiber optic lines, or new or replacement storm sewers, or projects that widen roads which in turn decreases the parkway soil volume around public parkway trees.

Projects that require fencing (listed above) shall fence the public parkway trees with six (6) foot high chain link construction fence secured to metal posts driven in the ground which are spaced no further than ten (10) feet apart. The dimensions of the fence shall depend on the tree diameter size and shall follow the table listed for the CRZ above, or as large as practical dependent on driveways and other field conditions. The fenced rectangle shall have three (3) sides with the opening facing the adjacent residences for easy access for mowing or tree care. Under no circumstances shall any items be stored within the fence. All fences shall be maintained daily in an upright good condition. The size and location of all fencing shall be shown on the project plan sheets.

To avoid damage to the CRZ, utilities must be augered underneath the public parkway trees. Excavation pits for augering equipment are to be outside the fenced area and are to be shown on the project plan sheets. Excavation pits for roundway keystops and domestic service boxes are to be as small as practical with excavation occurring in a direction away from the adjacent public parkway tree.

In cases when severing of roots within a portion of the CRZ may be unavoidable (ex. sidewalk installation, curb replacement, water or sanitary service replacement), subject to the approval of the Village Forester, sharp clean cuts shall be made on root ends to promote wound closure and root regeneration. Root pruning and excavation activities shall occur such that the smallest volume of soil and roots is disturbed, and the locations shall be shown on the project plan sheets.

In addition to fines and citations that may be assessed for violations of any section of Chapter 24 of the Municipal Code (such as not maintaining fencing around the CRZ or unauthorized removal of protected trees), the Contractor may be subject to the following provisions:

- issuance of an invoice for the value or partial value of the tree lost due to damage to either the above ground or below ground portions of the parkway tree, or unauthorized tree removal.
- costs of repairs, such as pruning or cabling, or costs for removal of the damaged parkway tree along with the stump if the tree cannot remain in the right-of-way.
- fines of \$500 for the 1st offense; \$1,000 for the 2nd offense; \$2,500 for the 3rd and subsequent offenses.
- each day during which a violation continues shall be construed as a separate and distinct offense.

The value or partial value of the tree lost shall be determined by the Village Forester using the most current edition of the <u>Guide for Plant Appraisal</u> (prepared by the Council of Tree & Landscape Appraisers and the International Society of Arboriculture) and the most current edition of the <u>Species Ratings & Appraisal</u> <u>Factors</u> for Illinois (prepared by the Illinois Arborist Association). The total cost determined for the damage shall be deducted from the payments made to the Contractor for the Project. Should the Village hire another Contractor or tree service to complete pruning work, these costs shall also be deducted from the payments made to the Contractor.

Basis of Payment: This work will be paid for at the contract unit price per FOOT for:

TREE PROTECTION,

which price shall be payment in full for the work as specified herein, except tree removal as defined by the standard specifications, which will be paid for separately.

SP-6 TREE ROOT PRUNING

Description: All trees, public or private, affected by the proposed improvements within its root protection zone, shall be root pruned prior to any excavation taking place. Root pruning shall be performed in accordance with the Tree Protection Zone detail of the Plans, and shall be done only to the depth of the excavation necessary for installing the proposed improvements. Root pruning shall start and proceed uninterrupted for the length of travel through the root protection zone. Root pruning shall be made no more than 10 inches from the tree-side edge of the proposed sidewalk, edge of pavement, or back of curb.

Approval by the Village Forester of the equipment to be used for root pruning, as well as the proposed path of the root pruning work, is required prior to the work being performed. The Engineer or his representative shall permit no excavation until written approval is obtained by the Contractor from the Village Forester. No materials or equipment may be stored or kept in the Tree Protection Zone. Tree damage, as determined by the Village Forester, shall be assessed to the Contractor using the most recent edition of the Guide for Plant Appraisal, published by the International Society of Arboriculture. **Root pruning shall not take place until the location of such is approved by the Engineer.**

Basis of Payment: This work shall be paid for at the contract unit price per **FOOT** for:

TREE ROOT PRUNING,

which price shall be payment in full for the work as specified herein and as measured in place.

SP-7 EROSION AND SEDIMENTATION CONTROL

Description: Throughout each and every phase of the Project, all downstream ditches and storm sewers shall be protected from the run-off of roadway surfaces, excavations, and other construction activities generating the movement of dirt, mud, dust and debris. This work shall consist of constructing temporary erosion and sedimentation control systems as shown on the plans or as directed by the Engineer. The work shall be placed by methods and with materials in accordance with Sections 280, 1080 and 1081 of the SSRBC, except as amended herein.

All downstream ditches shall be protected from erosion and sedimentation by the installation of silt fence ditch checks; straw bales shall not be used. Piles of excavated material and/or trench backfill material, allowed to be in place in excess of three (3) days, shall be protected against erosion and sedimentation runoff by use of silt fence. Storm sewer inlet structures or manholes shall be protected by temporary placement of geotextile fabric, filter baskets, or solid lids, as authorized in the field by the Engineer.

Erosion and sedimentation control measures as indicated in the Erosion Control Plan, or as directed by the Engineer shall be installed on the project site prior to beginning any construction activities which will potentially create conditions subject to erosion. Erosion control devices shall be in place and approved by the Engineer as to proper placement and installation prior to beginning other work. Erosion control protection for Contractor equipment storage sites, plant sites, and other sites shall be installed by the Contractor and approved by the Engineer prior to beginning construction activities at each site.

<u>Silt Fence</u> Placement, maintenance, and removal of silt fence at areas designated by the Engineer. The work shall be placed by methods and materials in accordance with Sections 280 and 1080 of the SSRBC, except as amended herein.

Basis of Payment: This work shall be considered INCIDENTAL to the project.

SP-8 STREET SWEEPING AND DUST CONTROL

All roadway surfaces shall be kept free of dirt, mud, dust and debris of any kind throughout every phase of the Project. Dirt, mud, dust and debris of any kind shall be removed from the roadway surface to the satisfaction of the Engineer by any one or combination of the following: approved mechanical sweeping equipment, manual labor, or other approved techniques.

Whenever ordered by the Engineer, especially for locations subject to a particularly high volume of traffic, the Contractor shall mechanically sweep the work site.

Basis of Payment: This work will be paid for at the contract unit price per HOUR for

STREET SWEEPING AND DUST CONTROL,

SP-9 TRAFFIC CONTROL, MAINTENANCE OF TRAFFIC, DETOURS

Description: This item shall include the furnishing, installing, maintaining, relocating and removing of all traffic control devices and personnel used for the purpose of regulating, warning, or directing traffic during the construction of this Project. All traffic control devices used on this Project shall conform to the <u>Standard</u> <u>Specifications for Traffic Control Devices</u> and the <u>Illinois Manual on Uniform Traffic Control Devices</u>.

No waiving of these requirements will be allowed without prior written approval of the Engineer.

The Contractor shall protect all workers engaged in the Project, and shall provide for safe and convenient public travel by providing adequate traffic control under all circumstances. Such circumstances may include, but not be limited to work performed along the route under construction, road closures for construction operations of any type, or when any section of the road is opened to traffic prior to completion of all work. The Contractor shall ensure that work zone in question is properly signed, barricaded and otherwise marked.

The Contractor will be responsible for the proper location, installation, and arrangement of all traffic control devices during the period of construction. All open excavations shall be protected by Type I barricades equipped with working bi-directional flashing lights at each end of the excavation, as well as at 50-foot intervals between ends for excavations greater than 50 feet in length and weighted down by **one sandbag per each barricade**. All street closures shall be protected by Type III barricades equipped with working bi-directional flashing lights and weighted down by **eight sandbags per each barricade**.

The Contractor shall plan his work so that there will be no open excavations during non-working hours and that all barricades not necessary have been removed from the pavement during non-working hours.

In the event that one direction of vehicular travel must be closed, the Contractor has the option of setting up a detour route or using flaggers (minimum of two) to direct traffic around the work area. The Engineer shall approve proper signing and barricading of the detour route and lane closures, and shall issue written authorization prior to closure.

In the event that both directions of vehicular travel must be closed, the Contractor shall set up a detour route to direct traffic around the work area. The Engineer shall approve proper signing and barricading of the detour route and shall issue written authorization prior to closure.

The Contractor shall maintain his operations in a manner such that traffic flow shall not be substantially impeded during the construction of the proposed improvements. Where traffic must cross open trenches during a given work day, the Contractor shall provide steel plates at street intersections and driveways. Prior to the end of a given work day, the pavement surface shall be temporarily restored.

No open excavation may be left overnight or on the weekend without the express written permission of the Engineer.

No street closure shall be permitted without the express written permission of the Engineer. No street closure may exceed 800 linear feet, nor be in effect from Friday night at 4:30PM to Monday morning at 9:00AM. Where it is necessary to establish a temporary detour, all the requirements of the Standard Specifications and MUTCD shall be met.

As the condition and location of the work changes, the Contractor shall maintain all traffic control devices

and personnel engaged in traffic control, in a manner that will accommodate the changing particulars of the work at any given time. Advance warnings, detour and directional information and other controls or directions necessary for safe passage of traffic around the work site shall be reviewed and changed, if necessary, to meet the needs of the situation. Signage erected, but not necessary or proper for the situation ahead shall be covered or taken down. Barricading and signage shall be monitored by the Contractor on a daily basis to ensure that it meets the requirements for work zone safety for the conditions of the particular work being performed.

The Contractor shall provide a name and phone number of a responsible party capable of providing emergency service, 24 hours per day, for the duration of the Project.

Basis of Payment: This work shall be paid for at the contract LUMP SUM price for:

TRAFFIC CONTROL, MAINTENANCE OF TRAFFIC, DETOURS,

which price shall be payment in full for the installation and maintenance of proper traffic control to protect the work and public for the duration of the Project.

SP-10 DRAINAGE STRUCTURE TO BE REMOVED

1.2

Description: This work shall consist of removing and disposing of existing manholes, catch basins and inlets in accordance with Section 605 of the Standard Specifications and as specified herein.

In addition to the requirements of Article 605.03 of the Standard Specifications, the Contractor shall saw cut a square area around the structure to be removed sufficient to remove the structure and construct the replacement structure.

Basis of Payment: This work shall be measured and paid for at the contract unit price per EACH for:

DRAINAGE STRUCTURES TO BE REMOVED

The word DRAINAGE STRUCTURE shall be understood to mean manhole, catch basin or inlet as the case may be.

SP-11 HOT-MIX ASPHALT DRIVEWAY REMOVAL & REPLACMENT (3")

Description: This work shall consist of the removal and replacement of asphalt driveways at locations indicated on the plan and/or as required by the Engineer.

The replacement of the driveways shall consist of preparing a subgrade at all required locations, shaping of slopes adjacent to the driveways, the placement and compacting of six inches (6") of CA-6 Aggregate Base, and the placement and compacting of three inches (3") of Hot-Mix Asphalt Surface, Mixture C, N50 (IL 9.5).

At locations noted on Schedule of Quantities, asphalt driveways shall be replaced with the six inches (6") of CA-6 aggregate base along with eight inches (8") of Hot-Mix Asphalt comprised of six inches (6") of Hot-Mix Asphalt Binder, IL-19.0, N50 and finished with a minimum of two inches (2") of Hot-Mix Asphalt Surface, Mixture C, N50 (IL 9.5). Asphalt to be placed in compacted layers not to exceed four inches (4").

This work shall also include the adjustment to proper grade of all water valve or private utility boxes encountered.

The locations at which this work will be measured for payment will consist of only those areas bounded by combination concrete curb and gutter. Those areas where the surface course of the pavement flares into existing driveways beyond the limits of the fully improved areas will not be included for payment.

Basis of Payment: This work shall be paid for at the contract unit price per SQUARE YARD for

HMA DRIVEWAY REMOVAL & REPLACMENT (3"),

SP-12 PCC DRIVEWAY REMOVAL & REPLACMENT (6")

Description: This work shall consist of the removal and replacement of concrete driveways in accordance with the applicable parts of Sec. 423 of the SSRBC except as amended herein.

This work shall include the placement of ³/₄" premolded expansion joints where new concrete abuts existing concrete or as directed by the Engineer.

This work shall also include the adjustment to proper grade of all water valve or private utility boxes encountered.

Replacement of the driveways shall include the application of membrane curing compound, Type III, in accordance with Articles 1020.13 and 1022.01 of the SSRBC, unless otherwise directed by the Engineer. If replacement of the driveways takes place prior to April 15, or after October 15, the driveway shall be properly cured and that followed by the application of protective coat in accordance with Article 420.18 of the Standard Specifications.

Basis of Payment: This work shall be paid for at the contract unit price per SQUARE YARD for

PCC DRIVEWAY REMOVAL & REPLACMENT (6"),

<u>SP-13 PORTLAND CEMENT CONCRETE SIDEWALK REMOVAL AND REPLACE</u> or PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH, NEW

Description: This work shall consist of installation of new P.C.C. and the removal and replacement of existing P.C.C. sidewalk as indicated by location or shown on the plans. All P.C.C. sidewalks shall be removed and replaced by methods and with materials in accordance with Articles 424 and 1020.04 of the SSRBC, except as amended herein.

Removal of existing sidewalk shall include saw cutting and disposal of existing concrete as directed by the Engineer, removal of tree roots, bituminous paved sidewalks and/or bituminous overlayment of existing sidewalks.

Excavation for new sidewalk shall be performed with a Gradall. Operating the Gradall on the parkways will not be allowed. All excavation shall be made from the street unless otherwise approved by the Engineer. Excavation work utilizing a skid steer loader shall not be allowed.

Placement of sidewalk shall include the following:

- a) Any necessary excavation, clearing, and proper disposal of excavated materials, removal and disposal of all obstructions such as fences, walls, foundations and buildings;
- b) The placement of four inches (4") of Type B, CA-6 compacted aggregate base;
- c) The set up of form work such that the maximum longitudinal slope of the finished walk does not exceed 8.33 percent (1 inch in 12 inches), and the lateral slope is not less than 1/4 inch per 12 inches, nor more than 1/2 inch per 12 inches.
- d) The placement of five inch (5") thick, Class SI Portland Cement Concrete, 6.05 cwt/cy mix, with 6% air entrainment, 3"-5" slump, and six inch (6") thickness through or in driveways or where subject to vehicular traffic, to the width specified on the plans or as directed by the Engineer;
- e) The tooling of contraction joints, 3/4-inch radius and 1 inch deep, 5 feet on center;
- f) The placement of 3/4 inch thick premoulded expansion joints at 100 foot intervals on center, or abutting existing concrete sidewalk, or at the end of a pour;
- g) The adjustment to proper grade of all utility structures encountered;
- h) The replacement of all traffic control devices or parking meters removed;
- i) The proper curing of all concrete work utilizing methods and materials outlined in Articles 424 and 1022.01 of the SSRBC, (Type III membrane curing compound white pigmented);
- j) The complete restoration of abutting asphalt driveways damaged as a result of installation, or where new sidewalk surface is more than 1/2 inch higher or lower than the original grade of the asphalt drive. Restoration shall consist of a minimum of one foot either side of the sidewalk; with a minimum of three inch (3") thick Hot-Mix Asphalt Surface, Mixture C, N50 (IL 9.5) surface course; and restoration of gravel drives with similar HMA restoration.

Except for damaged parkway areas due to rutting or not designated by the Engineer, restoration will be paid for in accordance with the specification PARKWAY RESTORATION, SALT TOLERANT SOD, SPECIAL.

Basis for Payment: This work shall be paid for at the contract unit price per SQUARE FOOT for:

P.C.C. SIDEWALK REMOVAL AND REPLACE or P.C.C. SIDEWALK, 5 INCH, NEW

SP-14 SANITARY SERVICE RECONNECTION

Description: This work shall consist of the reconnection of existing sanitary services disturbed during the installation of the proposed storm sewer. A service reconnection shall be considered whenever the storm sewer passes less than eighteen inches above or any distance below the service. THE CONTRACTOR MUST MAKE AN ATTEMPT TO AVOID DISTURBING THE SERVICE. ANY SERVICES DETERMINED BY THE ENGINEER TO BE DELIBERATELY DISTURBED WILL NOT BE CONSIDERED FOR PAYMENT. NO RECONNECTION SHALL BE CONSIDERED FOR PAYMENT UNLESS WITNESSED AND APPROVED BY THE ENGINEER.

The existing service pipe shall be cut one and one-half foot beyond the walls of the water main trench in a manner that provides a neat and smooth joint. The reconnection of the new and existing pipes shall be made with PVC pipe grade SDR 26, ASTM D2241, 160 psi pressure pipe, or better with push-on bell and spigot type with rubber ring seal gasket ASTM D3139. See detail in "Standard Detail" section of this document.

Non-shear couplings (couplings with stainless steel shear ring) shall be used to connect pipes of dissimilar material or size – FLEX-SEAL Adjustable Repair Couplings. The excavation shall be backfilled with TRENCH BACKFILL to a point one foot above the top of the sanitary service. Backfill shall be placed in lifts and firmly compacted such that no future settlement occurs. NO RECONNECTION SHALL BE BACKFILLED UNTIL INSPECTED AND APPROVED BY A REPRESENTATIVE OF THE DOWNERS GROVE SANITARY DISTRICT (630-969-0664).

Basis of Payment: This work will be paid for at the contract unit price EACH for:

SANITARY SERVICE RECONNECTION,

SP-15 STORM SEWERS (CLASS, MATERIAL, SIZE SPECIFIED)

Description: This item shall consist of the construction of Storm Sewer. Storm sewer shall be constructed with new Reinforced Concrete Pipe (RCP) per the SSRBC (AASHTO M315), and Ductile Iron Pipe with gasket (DIP), AWWA C -1 Class 52 with SuperCoat interior lining, asphalt exterior coating, and rubber-gasketed joints AWWA C – 111 of the diameter shown, watermain quality Polyvinyl Chloride (PVC) Pipe C900 with gasketed, bell and spigot, push on type joints conforming to ASTM D3212, or Polyvinyl Chloride (PVC) Pipe SDR 26 with gasketed, bell and spigot, push on type joints conforming to ASTM D3212 of the diameter shown on the Drawings.

The pipe shall be placed so that the entire length of the pipe will have full bearing. No blocking of any kind shall be used to adjust the pipe to grade except when used with concrete encasement.

Laying of sewer pipe shall be accomplished to line and grade in the trench only after it has been de-watered and the foundation and/or bedding has been prepared. Mud, silt, gravel, and other foreign material shall be kept out of the pipe and off the jointing surface.

All pipe laid shall be retained in position so as to maintain alignment and joint closure until sufficient backfill has been completed to adequately hold the pipe in place. All pipes shall be laid to conform to the prescribed line and grade shown on the Plans. The sewer pipe, unless otherwise approved by the Engineer, shall be laid up grade from point of connection on the existing sewer or from a designated starting point. The sewer pipe shall be installed with the bell end forward or upgrade, unless approved otherwise. When pipe laying is not in progress, the forward end of the pipe shall be kept tightly closed with an approved temporary plug.

If deemed necessary by the Engineer, all pipe and manholes shall pass an ex-filtration test in accordance with ASTM C-969-02 prior to acceptance. All testing shall be done under supervision of the Engineer, who shall be notified 48 hours prior to testing.

The following specific items shall be considered incidental to storm sewer pipe construction and their costs shall be merged into the contract unit price per **FOOT** of the storm sewer pipe.

- 1. Excavation and removal of all surplus trench excavation from site.
- 2. Placement and compaction of trench backfill for bedding, haunching, and initial backfill as defined in the Sewer and Water Specs.
- 3. Support of trenches, including any necessary bracing or shoring.
- 4. De-watering of trench or excavation.
- 5. Saw cutting of pavement and/or curb and gutter.

Basis of Payment: This work shall be paid for at the contract unit price per **FOOT** for:

STORM SEWERS (CLASS, MATERIAL, SIZE SPECIFIED),

which price shall include all labor, material, and equipment and incidental work herein specified, except TRENCH BACKFILL used as final backfill as defined by the Sewer and Water Specs, which will be paid for separately.

SP-16 TRENCH BACKFILL

Description: All trenches and excavations beneath pavements and driveways, as shown on plans or as directed by the Engineer in the field, will require selected granular backfill meeting the gradation specified herein and in section 208 of the SSRBC.

Trench Backfill shall meet the requirements of Section 1004.04 of the SSRBC, gradation to be "CA-6", except that GR-7 gravel will not be allowed. Select granular backfill as CA-6 should be used when under or within 2' of paved areas or structures, and shall extend from 1' above the pipe to at least 9" below the street surface. Selected granular backfill as CA-11 shall be used to a height of one (1) foot above the top of the storm sewer pipe.

Backfill shall be compacted by vibrating plate or other mechanical compacting device in a manner consistent with the Standard Specifications, to ensure that no future settlement occurs.

All backfilling shall be done in accordance with Section 550.07 of the SSRBC. Specifically, all trenches and excavations other than those shown on the plans or designated by the Engineer to receive TRENCH BACKFILL shall be backfilled by any acceptable method which will not dislodge or damage the pipe, or cause bridging action in the trench. Spoil material may be used as backfill in turf areas. In turf areas, TRENCH BACKFILL as CA-11 shall be used to a height of one (1) foot above the top of the storm sewer pipe, and the balance of the backfill may be approved excavated material.

Payment will not be made for the placement of selected granular backfill as granular bedding, haunching and initial backfill, as defined in the Water and Sewer Specs. These shall be considered incidental to the placement of the utility pipe.

Payment shall be made only for the placement of TRENCH BACKFILL as final backfill as defined in the Sewer and Water Specs. Backfill of approved excavated material shall be considered incidental to the contract price.

Where granular bedding as encasement material is not specified, selected excavation material free from clods or stones shall be used between the bottom of the trench and a point six inches above the top of the pipe.

Selected granular backfill shall be furnished for backfilling to the full width of the trench. It will be measured in cubic yards in place, except that the quantity for which payment will be made shall not exceed the volume of the trench as computed by using the maximum width of trench permitted by the SSRBC. Any selected granular material required in excess of the maximum quantity herein specified shall be furnished by the Contractor at his own expense

This item also includes the disposal of the surplus excavated material that is replaced by selected granular backfill. Any material meeting the aforementioned gradation that has been excavated from the trenches may be used for backfilling the trenches. However, no compensation will be allowed as selected granular backfill for the portion of the trench backfilled with excavated material.

Basis of Payment: This work will be paid for at the contract unit price per CUBIC YARD for

TRENCH BACKFILL

which price shall be payment in full for the work as specified herein and as measured in place.

SP-17 ADJUSTING DIP WATERMAIN (SIZE AND TYPE SPECIFIED)

Description. This work shall consist of adjusting watermain of the size specified in conflict with sewer to be constructed.

Materials: Watermain pipe materials shall meet all of the requirements of the following standards:

| Ductile Iron Pipe (DIP) - | ANSI/AWWA - C151/A21.51, |
|---------------------------|-------------------------------------|
| - · | ANSI Class 52 |
| - | Cement Lined ANSI/AWWA - C104/A21.4 |

The coupling of these watermain pipes shall meet the requirements of the following standards:

Ductile Iron Pipe (DIP) - Compression (push-on) rubber gasket joints in accordance with ANSI/AWWA C111/A21.11.

Unless otherwise shown on plans or directed by the Engineer, all ductile iron watermain pipes shall be installed without granular or concrete cradles. Although bell holes may not be required, the trench bottom shall be excavated and shaped such that the pipe is uniformly supported over its entire length.

The pipe shall be installed so that the entire length of pipe shall have full bearing. No blocking shall be used to adjust the pipe to grade except in conjunction with concrete thrust blocking or encasements.

Laying of watermain pipe shall be accomplished to line and grade in the trench only after it has been completely de-watered and the bedding is free of mud, loose silt, or gravel. All foreign material shall be kept out of the pipe.

All pipe laid shall be retained in position such to maintain joint closure, alignment, and grade until sufficient backfill has been completed to adequately hold the pipe in place.

At the end of each work day, the end of installed watermain pipe shall be protected and the excavation backfilled. No excavation or trench shall be left open overnight. The following specific items shall be considered **incidental** to watermain pipe installation and their costs shall be considered incidental to the contract unit price for watermain pipe:

- 1. All ductile iron pipe, fittings, and thrust blocking required to perform the adjustment;
- 2. Removal of all surplus trench excavation from site;
- 3. Excavation for and placement of granular bedding and encasement material when shown on the plans and/or ordered by the Engineer;
- 4. Support of trenches, including any necessary bracing or shoring;
- 5. De-watering of trenches or any excavation; and
- 6. Further adjustments to horizontal and vertical alignment due to unforeseen utility conflicts.

Measurement and Payment. This work shall be measured and paid for at the contract unit price PER FOOT, as measured along the centerline of the pipe, for:

ADJUSTING WATERMAIN (SIZE SPECIFIED)

Said price shall include the cost of all pipe, fittings, joint materials, hydrostatic test, disinfection of watermain, removal and disposal of old watermain and all excavation, and incidental work specified herein. Trench backfill will be measured and paid for as specified in the SPECIAL PROVISION for TRENCH BACKFILL, included elsewhere herein.

SP-18 ADJUSTING WATER SERVICE LINES

Description. This work shall consist of adjusting (replacing) water service lines required where the proposed storm sewer is in direct conflict with the existing water service line in accordance with Section 563 of the Standard Specifications and as specified herein. The service shall be replaced from the corporation to the b-box valve. It is recommended that all water services to be adjusted will be either pushed or augered. If open cutting the road is necessary, excavation, removal of excavation from site, support of trenches, material (pipe, fittings, valves), trench backfill, compacting of trench backfill, and all other items required to perform the work will be considered incidental. Pavement removal and pavement restoration will be paid for under FULL DEPTH PAVEMENT REMOVAL and HMA SURFACE AND BINDER COURSES.

Materials. The water service line shall be copper tube – Type "K" of the required diameter with Ford or McDonald Compression Type Fittings.

Measurement and Payment. The work shall be paid for at the contract unit price per EACH for:

ADJUSTING WATER SERVICE LINES

which price shall include all work as described above.

SP-19_TEMPORARY SURFACE OVER TRENCH – (AGGREGATE)

Description: This work shall consist of construction, maintenance, and removal of an aggregate surface course for temporary roads and approaches as specified in Section 107.09 of the SSRBC. The depth of the temporary surface over trench shall equal the depth of the proposed, final asphalt patch (11").

Construction Requirements:

Aggregate surface shall be constructed in accordance with the applicable portions of Section 402 of the SSRBC, except that the equipment required for the work will be as directed by the Engineer. Maintenance shall consist of placing and compacting additional aggregate of the same type and gradation as the surface aggregate.

Materials:

Aggregate used for temporary access shall be of CA-6 gradation and shall meet the requirements of Section 1004.04 of SSRBC, except the use of crushed concrete and slag will not be allowed. The top portion of the temporary aggregate surface will be capped with four inches (4") of bituminous grindings to assist with dust control.

When the use of the aggregate for temporary roads and approaches is discontinued, the surface aggregate placed in its construction and maintenance shall be removed and either utilized in the permanent construction or otherwise disposed of as specified in Section 202.03.

Basis of Payment: This work shall be paid for at the contract unit price per SQUARE YARD for:

TEMPORARY SURFACE OVER TRENCH – (AGGREGATE),

which price shall include all the labor, material, and equipment necessary for furnishing, placing, maintaining, removing and disposing of the aggregate surface or the bituminous patching material surface with aggregate sub-base, used in the construction of temporary road and drive approach surfaces. These items shall also include the maintenance of the temporary pavement.

SP-20 PARKWAY RESTORATION, SALT TOLERANT SOD, SPECIAL

Description: This item shall be done in accordance with the applicable portions of Section 252 of the Standard Specifications and the following provisions.

As contract work progresses through the Village, parkway restoration work shall commence in a timely manner in areas where permanent placement of new curb and gutter, driveways, sidewalks, etc., has been completed. Under no circumstances shall the Contractor prolong final grading, shaping and sod placement so that the entire project can be permanently restored at the same time.

This work shall consist of the excavation, topsoiling and sodding from a minimum of one and one-half (1-1/2) feet to a maximum of three (3) feet behind or adjacent to all curbs, sidewalks and driveways removed and replaced during the course of construction or as directed by the Engineer. Restoration will also be performed on areas disturbed by storm sewer or culvert construction.

All topsoil to be used for parkway restoration shall be obtained from outside the limits of this improvement, transported to the site and placed at required locations to a minimum depth of 4". All materials shall meet the requirements of Art. 1081.05 of the Standard Specifications. All placement of topsoil shall meet the requirements of Section 211 of the Standard Specifications.

All sod shall be salt tolerant meeting the requirements of Art. 1081.03 of the Standard Specifications. All placement of sod shall meet the requirements of Section 252 of the Standard Specifications.

For that period prior to full parkway restoration, the Contractor shall backfill and grade all disturbed areas so as to insure the safety of the general public. Parkways shall be left in a safe, clean and usable condition conducive to foot traffic and to the satisfaction of the Village. The Contractor shall protect these unfinished areas against erosion and work to keep them weed free.

Basis of Payment: This work will be paid for at the contract unit price per SQUARE YARD for:

PARKWAY RESTORATION, SALT TOLERANT SOD, SPECIAL,

which price shall be payment in full for any excavation and grading necessary, the furnishing, transporting and placement of all topsoil and sod and the **full watering of sod**. Unless otherwise directed by the Engineer restoration of disturbed parkways more than three (3) feet behind the back of curb or more than three (3) feet adjacent to newly constructed driveway or sidewalk or more than six (6) feet either side of the newly placed storm sewer or pipe culvert will not be paid for separately but shall be considered incidental to the Contract.

SP-21 DETECTABLE WARNINGS

Description: This work shall consist of the installation of new detectable warning material as shown in the plans. All detectable warnings shall be placed by methods and with materials in accordance with Article 424 and 424.09 of the SSRBC.

Each Detectable Warning shall consist of brick red 2' x 4' panels inserted into wet concrete. Detectable Warning shall be Access-Tile Cast-In-Place Replaceable or equivalent.

Basis for Payment: This work shall be paid for at the contract unit price per SQUARE FOOT for:

DETECTABLE WARNINGS,

which price shall include all material, labor, and equipment necessary to complete this item.

SP-22 IEPA CLEAN CONSTRUCTION OR DEMOLITION DEBRIS

Description: If construction activities will result in removal and disposal of excavation spoils, per Illinois Public Act 96-1416 and the Illinois Environmental Protection Agency, soil sampling and analysis, along with certification from a licensed professional engineer that the soil is uncontaminated, will be required prior to clean construction and demolition debris (CCDD) landfill acceptance. However, if the subject property has never been used for industrial or commercial purposes, then the site owner or operator may certify that the soil is uncontaminated by use of IEPA form LPC-662.

To facilitate meeting the above requirements, the Village will supply a signed Source Site Certification by Owner or Operator Form LPC-662 for all streets designated for improvement.

Construction Requirements: The Contractor shall be responsible for satisfactory removal and disposal of all waste material, asphalt, concrete, stone, and uncontaminated or contaminated dirt or debris generated or discovered in the course of the work. Removal and disposal of excavation items being disposed of at a landfill or clean construction and demolition debris (CCDD) fill site shall meet the requirements of Public Act 96-1416.

The temporary storing of excavated materials on the parkways or right of way, and re-handling them later for disposal will not be allowed due to additional damage caused to tree root systems, parkways, existing equipment, and conditions. It shall be the contractor's responsibility to find an approved dumpsite for debris and any excavated materials. The Village will not provide for one.

All additional work to satisfy these requirements shall be the responsibility of the Contractor. All costs associated with meeting these requirements shall not be paid for separately but shall be included in the unit price cost for the associated removal or excavation items in the contract. These costs shall also include but are not limited to all required testing, lab analysis, and certification by a licensed professional engineer.

Basis of Payment: This work shall not be paid for separately but shall be considered included in the cost of the project.

SP-23 ADJUSTING SANITARY SERVICE LINES

Description. This work shall consist of adjusting (replacing) sanitary service lines required where the proposed storm sewer is in direct conflict with the existing sanitary service line in accordance with Section 563 of the Standard Specifications and as specified herein, with the exception that adjustments (replacements) shall be constructed in addition to the "Sewer and Water Specs" per the Downers Grove Sanitary District's specifications for sewer construction, and that this item will be paid for per EACH adjustment. **Excavation, removal of excavation from site, support of trenches, material (pipe, fittings, etc.), trench backfill, compacting of trench backfill, and all other items required to perform the work will be considered incidental. Pavement and parkway restoration will be paid for separately under pavement removal, sidewalk removal, HMA surface and binder placement, sidewalk placement, and sod restoration.**

Materials. All material shall abide by Downers Grove Sanitary District specifications for sewer construction.

Measurement and Payment. The work shall be paid for at the contract unit price per EACH for:

ADJUSTING SANITARY SERVICE LINES

which price shall include all work as described above.

SP-24 EXPLORATION TRENCH

Description: This work shall consist of constructing a trench for the purpose of locating existing utilities potentially in conflict with the proposed improvements. All exploratory trenches shall be constructed and restored per Section 213 in the SSRBC.

Basis for Payment: This work shall be paid for at the contract unit price per FOOT/60-INCH DEPTH for:

EXPLORATION TRENCH,

which price shall include all material, labor, and equipment necessary to complete this item, which includes backfilling with spoils and/or approved backfill. Maintenance of the backfilled trench shall be incidental.

SP-25 COMBINATION CONCRETE CURB AND GUTTER REMOVAL (B6.18)

Description: This work shall consist of the removal of existing P.C.C. Curb and Gutter of the type and size at the locations noted in Schedule of Quantities. This work shall be performed in accordance with Section 440 of the Standard Specifications, except as amended herein.

At those locations where curb removal operations fall within the Critical Root Zone (CRZ) the Contractor will be required to trench with a "chain" driven trencher immediately back of curb prior to curb removal. This procedure will proceed uninterrupted through the CRZ and insure general tree root pruning. The width of the CRZ shall be determined as noted in the general provision for TREE PROTECTION elsewhere in these documents. If it is determined that proposed removal methods do not cause undo harm to adjacent roots, the Village Forester may waive the need to perform trenching.

During removal operations Contractor shall take special care not to damage or extend sawed joint into adjacent appurtenances such as driveways and sidewalks which are to remain in place. During machine sawing operations Contractor shall also take special care to remove, clean, or otherwise account for any residue / slurry produced by the sawing so material will not be tracked by either vehicular or foot traffic onto adjacent appurtenances which are to remain in place.

Basis of Payment: This work will be paid for at the contract unit price per FOOT for

COMBINATION CONCRETE CURB AND GUTTER REMOVAL (B6.18),

SP-26 COMBINATION CONCRETE CURB AND GUTTER (B6.18)

Description: This work shall consist of the replacement of existing PCC Curb and Gutter in accordance with the applicable parts of Sec. 606 of the Standard Specifications, except as amended herein.

Replacement of curb and gutter shall include the placement of three-quarter inch (3/4") premolded expansion joint filler along the back of curb, for the full depth of the curb and gutter, where abutting existing concrete.

Transverse expansion joints with $\frac{3}{4}$ " joint filler shall be constructed at five feet (5') either side of utility structures, and at no more than ninety foot (90') intervals. All expansion joints shall include the placement of two (2) three-quarter inch ($\frac{3}{4}$ ") dowel bars with pinched stop caps as specified on detail sheet. Two (2) three quarter inch ($\frac{3}{4}$ ") dowel bars shall also be placed at all construction joints as specified on detail sheet and shall be drilled into existing curb and gutter a minimum of six inches (6").

New curb and gutter shall be backfilled with existing excavated earth.

Transverse contraction joints shall be constructed at no more than fifteen foot (15') intervals.

When new curb and gutter is placed adjacent to concrete pavement or base, it shall be tied along the longitudinal construction joint with No. 6(3/4") bars at 24" centers in accordance with the applicable portions of Article 420.05 of the Standard Specifications.

Placement of curb and gutter as noted on Schedule of Quantities to be reinforced shall also include the placement of two (2) No. 4 ($\frac{1}{2}$ ") epoxy coated deformed reinforcement bars meeting the applicable portions of Section 508 of the Standard Specifications. Bars shall be placed at one-half depth of the body of the gutter running the entire length of newly placed sections. Curb and gutter placed as described in this paragraph will be paid for as COMBINATION CONCRETE CURB AND GUTTER (TYPE SPECIFIED), REINFORCED.

All voids existing between newly placed curb and gutter and the adjacent roadway pavement shall be filled with Class SI concrete, prior to bituminous surface placement, to a point 1-1/2 inches below finish grade. This work shall be considered **incidental**.

Placement of curb and gutter shall include the application of membrane curing compound, Type III, in accordance with Articles 1020.13 and 1022.01 of the Standard Specifications unless otherwise directed by the Engineer.

If placement of curb and gutter takes place prior to April 15, or after October 15, the curb and gutter shall be properly cured and that followed by the application of protective coat in accordance with Article 420.18 of the Standard Specifications.

Basis of Payment: This work will be paid for at the contract unit price per FOOT for

COMBINATION CONCRETE CURB AND GUTTER (B6.18),

SP-27 POROUS GRANULAR EMBANKMENT, SUBGRADE SPECIAL

Description: This work shall be done in accordance with the included District One special provision for Porous Granular Embankment, Subgrade and the following provisions.

This work shall also consist of removing and disposing of unsuitable sub-grade per the applicable portions of Section 202 of the SSRBC.

HMA grindings resulting from hot-mix asphalt surface removal, substantially meeting the gradation of CA-6, shall also be permitted for use as the specified granular cap. The granular cap shall be compacted to the satisfaction of the Engineer. It shall be the Contractor's responsibility that all proposed bituminous replacement regarding patching and paving operations in these areas will meet the specified performance criteria of their respective pay items.

This work will be measured for payment in accordance with Article 207.04 of the SSRBC. When specified on the contract, the theoretical elevation of the bottom of the aggregate subgrade shall be used to determine the upper limit of Porous Granular Embankment, Subgrade. The volume will be computed by the method of average end areas.

Basis of Payment: This work shall be paid for at the contract unit price per CUBIC YARD for

POROUS GRANULAR EMBANKMENT, SUBGRADE SPECIAL,

which price shall be payment in full for the work as specified herein. The Porous Granular Embankment, Subgrade Special shall be used as field conditions warrant at the time of construction. No adjustment in unit price will be allowed for an increase or decrease in quantities from the estimated quantities shown on the plans.

SP-28 RESTRICTOR PLATE (12")

n 1997 - 19

Description: This work shall consist of the installation of an 12" restrictor plate into an existing storm structure as shown on plans or as directed by the Engineer.

Materials: The restrictor plate shall be fabricated $\frac{1}{4}$ " – (Size) square stainless steel curved to conform to the curvature of the storm structure. An (Size) hole shall be drilled in the plate so that the invert of the hole shall meet the invert of the outlet pipe. $\frac{1}{2}$ " stainless steel lag bolts with anchors suitable for concrete use shall be tack welded to the stainless steel plate to be used to mount the plate to the storm structure. The bolts shall be used around the outer edge of the plate so that the plate can be easily removed by sliding upward. A pulling hook shall be welded to the top of the plate for removal of the plate.

Construction Requirements: The depth of the bolts into the structure shall be a minimum of three inches. An epoxy sealant between the structure and the plate shall be provided for a watertight seal.

Basis of Payment: This work shall be paid for at the contract unit price per EACH for:

12" RESTRICTOR PLATE

Unit prices shall include all labor, material, and equipment necessary to complete work. The repair of any damage done to the storm structure due to the installation of the plate shall not be paid for separately but shall be considered **INCIDENTAL** to the contract.

DOWNERS GROVE SANITARY DISTRICT SPECIFICATIONS

DOWNERS GROVE SANITARY DISTRICT

SPECIFICATION


<u>FOR</u>

BUILDING SANITARY SERVICE AIR TESTING

Effective Date: August 24, 2001

- 1. The entire building sanitary service shall be air tested from the public sewer to the building, including the machine tap, wye or tee, the outside cleanout(s) and all service piping. If a new wye or tee is installed on an existing public sewer, the pipe connections on the public sewer on both sides of the wye or tee must also be air tested, as described in Item 11.
- 2. Prior to testing, flush and clean the sewers by a method acceptable to the District. If a new wye or tee is installed on a existing public sewer, clean the inside of all existing pipes to allow the test plugs to properly seal during testing.
- 3. Isolate the building sanitary service from the existing public sewer by installing two airtight plugs in the public sewer, by installing one airtight plug with a void positioned at the connection between the building service connection and the public sewer, or by other method acceptable to the District.
- 4. Install an airtight plug on the cleanout inside the building.
- 5. Properly brace the outside cleanout cap and collar to withstand air testing.
- 6. Whenever the sewer to be tested is submerged under groundwater, determine the groundwater hydrostatic pressure by a method approved by the District.
- 7. Add air to the plugged sewer sections under test through the cleanout or public sewer plug until initial air pressure reaches 4.0 psig greater than any groundwater hydrostatic pressure.
- 8. Allow at least two minutes for air temperature to stabilize, adding air to maintain the initial test pressure.
- 9. Shut off the air supply after stabilizing the air temperature and record the time in seconds using an approved stopwatch for the internal sewer pressure to drop from 3.5 psig to 2.5 psig greater than any groundwater hydrostatic pressure.
- 10. The building sanitary service shall pass if the recorded time for the allowable pressure drop equals or exceeds 2 minutes for a 4-inch and 6-inch diameter service less than 300

1



Revision Date July 7, 2005

DOWNERS GROVE SANITARY DISTRICT SEWER CONTRACTOR'S CHECKLIST 630-969-0664

A. BUILDING SERVICE CONNECTIONS

- 1. No work may be started unless the contractor is bonded with the District, in addition to any Village, Township, County or State requirements. Call 969-0664 for bond requirements.
- 2. No work may be started unless a Sewer Permit has been picked up by the contractor and posted on the job. All repairs require a no-charge permit. All work must be inspected.
- 3. A Sewer Permit will not be issued until all fees have been paid. The District must approve plans for new buildings. No sewer connection may be done until foundation is in and cast iron can be connected. Existing buildings must be inspected and approved by the District and any violations must be corrected before connection to the sewer.
- 4. Any excavation with the right-of-way requires a separate permit from the appropriate Village, Township, County or State jurisdiction.
- 5. Pipe Size 6" diameter minimum for building services.
- 6. Pipe Material must meet the following requirements:
 - PVC pipe with a SDR of 26, complying with ASTM D2241, 160 psi pressure pipe push-on bell and spigot type with rubber ring seal gasket ASTM D3139.
 - Ductile Iron Pipe, AWWA C-151, Class 51, with rubber-gasket joints AWWA C-111. All pipe and fittings must have corrosion protection using H2Sewer Safe by Griffin Products (SuperCoat Lining) or approved equal and exterior polyethylene tube complying with ANSI/AWWA C105/A 21.5-93, with a thickness not less than 8 mils.
- 7. Utilities site plan is required for all new building sanitary services, including septic system conversions. This shall be provided on a topographic survey, which shows the rim elevation of the nearest upstream and downstream sanitary manholes.
- 8. An agreement for District access to the building sanitary service, signed by the property owner, is required for all new building sanitary services.
- 9. Service stubs must be perpendicular to the main sewer to the property line.
 - Whenever possible, it is requested that the service be laid straight from the stub or property line to the building. Any changes in alignment must be made with 45° (or less) bends, no 90° bends are allowed. It is recommended that the service not be located under any existing or proposed driveway or sidewalk. <u>Under no circumstances may drain tiles be connected to the service</u>.

- 10. Outside Cleanouts
 - An outside cleanout shall be installed on each new building sanitary service at the transition from 4-inch waste line to 6-inch service pipe just outside the foundation or other location approved by the District. Refer to Downers Grove Sanitary District Specification for details.
- 11. Pipe Bedding
 - No pipe may be laid when there is water in the trench. If there is water in the trench it must be pumped out prior to placing any bedding material. No water from the trench may be allowed to enter the existing sanitary sewer. Any Contractor allowing this to happen will have his bond revoked.
 - ¼" to ¾" washed chipped limestone, must be placed at least 4" below the bottom of the pipe and compacted. Dig bell-holes before the pipe is laid.
- 12. Pipe Trench
 - The pipe must be laid at a slope of at least 1.0%, starting from the stub or main sewer.
 - The maximum trench width is 2' 0", measured above the top of the pipe. Over 12" above the top of the pipe, the sides of the trench may be stepped or sloped back.
 - Maximum depth is 10' 0", measured from the top of the pipe to the finished grade.
 - Minimum depth is 4' 0", measured from the top of the pipe to the existing grade. Anything
 - less than 4' must be insulated.
 - Water and sewer services must be placed in separate trenches at least 10 feet apart. Only when it is impossible to maintain 10 feet of separation may sewer and water services be placed in the same trench. When placed in the same trench, services must be at least 3 feet apart with 18 inches of vertical separation.
 - Any water services that cross house sewers, storm drains, or sanitary sewers must also maintain an 18-inch vertical separation for a distance of 10 feet on both sides of the sewer. The excavated area between each pipe and the full width of the water service for a distance of 3 feet on both sides of the sewer must be replaced with compacted granular backfill.

13. Pipe Backfilling

- ¹/₄" to ³/₄" washed chipped limestone, must be carefully placed under the sides of the pipe and firmly tapped into place. Granular backfill must be carefully placed to a level 12" above the top of the pipe and compacted.
- Selected excavated material, free of rocks and sticks, may be used to backfill from 12" above the top of the pipe to the surface, except under roadways and sidewalks.
- Parkway restoration shall comply with applicable village, township, county, or state requirements.
- Under roadways (and to 2' behind the back of the curb) and under sidewalks, granular material, from ¼" to ¾", must be used to backfill from 12" above the top of the pipe, to the subgrade elevation.

• Roadway and sidewalk restoration shall comply with applicable village, township, county, or state requirements.

14. Foundation Over Dig & Double Wall Foundations

- The foundation over dig at the point where sanitary sewer service enters the building shall be filled with 4" to 3/4" washed chipped limestone from the footing to the bottom of service to provide support for this pipe.
- Service sewers passing through double foundation wall or under concrete porches shall be constructed of ductile iron pipe. Cast iron or PVC pipe will not be allowed in these situations.

15. Service Risers

 $\left(\right)$

- A service riser must be constructed where the main sewer is more than 12' deep, measured from the invert of the pipe to the finished grade. Refer to Downers Grove Sanitary District Specification for details.
- 16. No-Shear Couplings
 - No-shear couplings (couplings with stainless steel shear ring) shall be used to connect pipes of dissimilar material or size Flex-Seal Adjustable Repair Couplings or approved equal.
- 17. Building Sanitary Service Air Testing
 - All new building sanitary services shall be tested in accordance with District specifications for building sanitary service air testing. Refer to Downers Grove Sanitary District Specification for details.
- 18. Building Sanitary Service Televising
 - All new building sanitary services shall be televised in accordance with District specifications for building sanitary service televising. Refer to Downers Grove Sanitary District Specification for details.

19. Inspections

- All sewer services shall be left completely exposed until the District inspector has accepted it. 24 hours notice is required for such inspection. Inspections may be scheduled Monday through Friday, between 8:00 a.m. and 4:00 p.m.
- A representative of the sewer contractor shall be in attendance at time of all inspections.
- 20. Record of Work Performed
 - Upon completion of a new building sanitary service or any repairs to an existing building sanitary service, the sewer contractor or property owner must submit to the District a

3

written record of the work completed, including a sketch, pipe sizes, footages, depths, fittings and measurements from property lines or building corners, before final acceptance of said work will be granted by the District. This information should be in sufficient detail to allow the location of the building sanitary service to be clearly marked at a future date.

21. Inspection Manhole*

• For all non-residential buildings, an inspection manhole is required on the service between the building and the main sewer. It must be placed so that all flow from the building passes through the manhole. The inspection manhole must be 4 feet in diameter and have a District standard manhole cover. Refer to Downers Grove Sanitary District Specification for details. Manholes must pass a vacuum test before acceptance.

*Also pertains to Flood Control Manhole.

- 22. Grease, Oil and Sand Traps
 - When required as a condition of the Sewer Permit for non-residential buildings, such traps shall be of a design approved by the District and shall be located where easily accessible for cleaning and inspection. Grease traps shall be located outside where possible and shall be below the ground. Where outside installation is impossible, the grease trap may be located inside but must be below the floor. Dishwashing machines cannot be discharged through any grease trap. All grease traps must be cleaned on a monthly basis. Oil separators shall be triple-basin type. Sand traps may be a single manhole with sump. All such installations shall conform to the requirements of the DuPage County Health Department and Village and State Plumbing Codes.
- 23. Overhead Sewer
 - Overhead sewer is required for all new construction and septic system conversions.
- 24. Blockings/Demolitions
 - All buildings to be demolished shall have their sanitary sewer service blocked at the main sewer connection; this work shall be done prior to the actual demolition. Rebuilds will be required to install a new service out to the main sewer. Existing tee or wye connections may be reused only upon approval by the District inspector. It shall be the responsibility of the contractor to determine the point of disconnection on the public sanitary sewer. The contractor shall televise and electronically locate the building sanitary service to the connection point to public sanitary sewer.

Prior to the issuance of sanitary disconnection permit, the contractor shall submit to the District a copy of the VHS video tape of the building sanitary service televising and a corresponding written report for District review and approval. The written report shall note all observations and shall indicate the location of the building sanitary service connection point on the public sanitary sewer, measured from the nearest District manhole. The televising shall comply with the District Specification for Building Sanitary Service

Televising. The intent of the televising and locating is to determine that the building sanitary service is not shared with any other building and to locate the connection point to the public sanitary sewer.

25. Machine Taps

- Whenever there is not a tee or wye for a service connection, a machine tap shall be made. The connection shall be made with a Geneco Sealtite Sewer Saddle (Model S) or approved equal.
- 26. Septic System Conversion
 - When an existing building is to be connected to the District sanitary sewer system (septic system conversion), the new building sanitary service pipe must extend all the way to the existing building foundation; i.e., no existing service pipe may remain in service.
- 27. Special Conditions
 - Special conditions may be required as a condition of the Sewer Permit. The contractor is advised to check such conditions on the Sewer Permit and the set of plans approved by the District before starting the work. All sewers must be installed in accordance with the Standard Specifications for Sanitary Sewer Construction of the Downers Grove Sanitary District.

28. Lateral Lining

• The District restricts the use of lateral liners for all building sanitary service sewer construction or rehabilitation. The decision to allow the use of lateral liners will be made by the District. Request to use a lateral liner shall be done it writing and shall be made at the time of permit application. The District will evaluate each situation and determine if a lateral liner is appropriate. If the District approves a location for the use of a liner, the liner construction must meet all District requirements for sewer construction. The District also reserves the right to specify approved liner manufactures, installers and products.

B. MAIN SEWER EXTENSIONS

- 1. All extensions must be constructed in accordance with plans approved by the District.
- 2. No work may be started unless the contractor is bonded with the District.
- 3. No work may be started until the Illinois EPA permit and all village or county permits are obtained.
- 4. All sewers must pass an air test and a lamping inspection. All PVC sewers must pass a deflection test. Refer to the plans or to Downers Grove Sanitary District Specification for details.

5. All public sanitary sewers shall be laid with straight alignment and uniform slope between manholes. The alignment shall be checked by lamping in accordance with District construction inspection procedures. Contractors are required to use a pipe laser to set pipe slope and alignment for public sanitary sewer main construction

- 6. All manholes must pass a vacuum pressure test, Refer to Downers Grove Sanitary District Specification for details.
- 7. The constructed sewers must be televised under simulated flow conditions. District personnel must be present during televising. No sags greater than 25% of the pipe diameter will be accepted. All unacceptable sags must be replaced in a manner acceptable to the District.
- 8. Maximum trench widths measured at a point 12" above the top of the pipe are as follows:

| Trench Excavations | | | | |
|--------------------|--------------|--|--|--|
| Pipe Size | Trench Width | | | |
| | | | | |
| .6" | 2' 0" | | | |
| 8" | 2' 6" | | | |
| 10" | 2' 6" | | | |
| 12" | 3'.0" | | | |
| 15" | 3' 0" | | | |
| 18" | 3' 0" | | | |
| 21" | 3' 6" | | | |
| 24" | 3' 9" | | | |

б

V. BID and CONTRACT FORM (Village)

***THIS BID WHEN ACCEPTED AND SIGNED BY AN AUTHORIZED SIGNATORY OF THE VILLAGE OF DOWNERS GROVE SHALL BECOME A CONTRACT BINDING UPON BOTH PARTIES.

Entire Form Must Be Completed If a Submitted Bid Is To Be Considered For Award BIDDER:

| DIDDEIN | |
|---|--|
| SWALLOW WNSTRILTION Company Name | <u> </u> |
| <u>42 SO LACET PD</u> Street Address of Company | AWTHINY @ SWALLOW CONSTRUCTION, MIJ E-mail Address |
| DOWNIPS GROVE ZL GUSIS City, State, Zip | ANTHONY RENSINA Contact Name (Print) |
| <u>630-S12-9900</u> Business Phone 630-S12-9902 | 630-417-7883 24-Hour Telephone |
| $\frac{\varphi_{30}}{\text{Business Fax}}$ | Signature of Officer, Partner or Sole Proprietor |
| ATTEST: if a Corporation | ANONIO PENDINA, PRESIDENT Print Name & Title |
| | ers Grove all necessary materials, equipment, labor, etc. to m the date of the Notice to Proceed in accordance with the |

provisions, instructions and specifications for the unit prices shown on the Schedule of Prices.

VILLAGE OF DOWNERS GROVE:

ATTEST:

Authorized Signature

Village Clerk

Title

Date

Date

In compliance with the specifications, the above-signed offers and agrees, if this Bid is accepted within 90 calendar days from the date of opening, to furnish any or all of the services upon which prices are quoted, at the price set opposite each item, delivered at the designated point within the time specified above.

V. BID and CONTRACT FORM (Contractor)

***THIS BID WHEN ACCEPTED AND SIGNED BY AN AUTHORIZED SIGNATORY OF THE VILLAGE OF DOWNERS GROVE SHALL BECOME A CONTRACT BINDING UPON BOTH PARTIES.

Entire Form Must Be Completed If a Submitted Bid Is To Be Considered For Award BIDDER:

SWALLOW CONSTRUCTION Company Name AWTHONY QS WALLOW CONSTRUCTION, NET E-mail Address Street Address of Company 26 6051R City, State, Zip Contact Name (I **Business** Phone 24-Hour Telephone 070-0 Signature of Officer, Partner or Sole Proprietor **Business** Fax ANTONIO RENXINA Print Name & Title ATTEST: if a Corporation Signature of Corporation Secretary We hereby agree to furnish the Village of Downers Grove all necessary materials, equipment, labor, etc. to complete the project within 60 calendar days from the date of the Notice to Proceed in accordance with the provisions, instructions and specifications for the unit prices shown on the Schedule of Prices. VILLAGE OF DOWNERS GROVE: ATTEST:

Authorized Signature

MILDI.

Village Clerk

Title

Date

Date

In compliance with the specifications, the above-signed offers and agrees, if this Bid is accepted within 90 calendar days from the date of opening, to furnish any or all of the services upon which prices are quoted, at the price set opposite each item, delivered at the designated point within the time specified above.

SCHEDULE OF PRICES:

<u>Base Bid</u>

Demolition & Debris Removal

| # | ITEM | UNIT | QUANTITY | UNIT COST | TOTAL COST |
|----------|--|-------|----------|-----------|------------|
| 67100100 | MOBILIZATION | LSUM | 1 | | |
| SP-2 | CONSTRUCTION STAKING AND RECORD DRAWINGS | LSUM | 1 | | |
| SP-3 | PRECONSTRUCTION VIDEOTAPING | LSUM | 1 | | |
| SP-5 | TREE PROTECTION | FOOT | 2,300 | | |
| SP-6 | TREE ROOT PRUNING | FOOT | 100 | | |
| SP-8 | STREET SWEEPING AND DUST CONTROL | HOUR | 25 | | |
| SP-9 | TRAFFIC CONTROL, MAINTENANCE OF TRAFFIC, DETOURS | LSUM | 1 | | |
| SP-25 | COMBINATION CONCRETE CURB AND GUTTER REMOVAL (B | FOOT | 400 | | |
| SP-10 | DRAINAGE STRUCTURES TO BE REMOVED | EACH | 11 | | |
| SP-11 | HMA DRIVEWAY REMOVAL AND REPLACEMENT (3") | SQ YD | 40 | | |
| SP-12 | PCC DRIVEWAY REMOVAL & REPLACMENT (6") | SQ YD | 25 | | |
| SP-13 | P.C.C. SIDEWALK REMOVAL | SQ FT | 850 | | |
| X4401198 | VARIABLE HMA SURFACE REMOVAL, 2" TO 3.5" | SQ YD | 4,000 | | |
| 44000100 | FULL DEPTH PAVEMENT REMOVAL | SQ YD | 2,400 | | |

Subtotal

| # | ITEM | UNIT | QUANTITY | UNIT COST | TOTAL COST |
|----------|--|--------------------|----------|-----------|------------|
| SP-14 | SANITARY SERVICE RECONNECTION | EACH | 17 | | |
| SP-15 | STORM SEWER, RCP, CL IV, 12" | FOOT | 1450 | | |
| SP-15 | STORM SEWER, CLASS 52 DIP, 18" | FOOT | 25 | | |
| SP-16 | TRENCH BACKFILL | CU YD | 700 | | |
| SP-24 | EXPLORATION TRENCH (5' MINIMUM PER LOCATION) | FOOT/60-INCH DEPTH | 250 | | |
| 60218400 | MANHOLE, TYPE A, 4'-DIAMETER, TYPE 1 F&G, CL | EACH | 3 | | |
| 60219570 | MANHOLE, TYPE A, 4'-DIAMETER, TYPE 3V F&G | EACH | 1 | | |
| 60200205 | CATCH BASIN, TYPE A, 4'-DIAMETER, TYPE 1 F&G, CL | EACH | 9 | | |
| 60200310 | CATCH BASIN, TYPE A, 4'-DIAMETER, TYPE 3V F&G | EACH | 1 | | |
| 60204005 | CATCH BASIN, TYPE A, 5'-DIAMETER, TYPE 3V F&G | EACH | 1 | | |
| 60206602 | CATCH BASIN/INLET, TYPE B, TYPE 1 F&G, OL | EACH | 3 | | |
| 60206602 | CATCH BASIN/INLET, TYPE B, TYPE 3V F&G | EACH | з | | |
| X6020074 | INLETS, TYPE A, TYPE 3V F&G | EACH | 4 | | |
| X6023212 | INLETS, TYPE A, NEENAH R-3508-B F&G | EACH | 2 | | |
| SP-17 | ADJUSTING DIP WATERMAIN, 6", CL52 | FOOT | 40 | | |
| SP-18 | ADJUSTING WATER SERVICE LINES | EACH | 17 | | |
| SP-23 | ADJUSTING SANITARY SERVICE LINES | EACH | 17 | | |
| SP-28 | RESTRICTOR PLATE, 12" | EACH | 1 | | |

Pavement and Parkway Restoration Improvements

Subtotal

| # | ITEM | UNIT | QUANTITY | UNIT COST | TOTAL COST |
|----------|--|-------|----------|-----------|------------|
| 40600100 | BITUMINOUS MATERIALS, PRIME COAT | GAL. | 500 | | |
| 40600625 | VARIABLE DEPTH (0.5" TO 2") LEVELING BINDER, MACHINE M | TON | 500 | | |
| 40603310 | HOT MIX ASPHALT SURFACE COURSE, MIX C, N50 | TON | 500 | | |
| 40603080 | HOT MIX ASPHALT BINDER COURSE, IL-19.0, N50 | TON | 1,100 | | |
| SP-19 | TEMPORARY SURFACE OVER TRENCH | SQ YD | 1,500 | | |
| SP-20 | PARKWAY RESTORATION, SALT TOLERANT SOD, SPECIAL | SQ YD | 650 | | |
| SP-13 | P.C.C. SIDEWALK, 5 INCH, NEW | SQ FT | 1,200 | | |
| SP-26 | COMBINATION CONCRETE CURB AND GUTTER (B6.18) | FOOT | 460 | | |
| SP-21 | DETECTABLE WARNINGS | SQ FT | 140 | | |
| SP-27 | POROUS GRANULAR EMBANKMENT, SUBGRADE SPECIAL | CU YD | 500 | | |

Subtotal

Total Base Bid_____

BIDDER'S CERTIFICATION (page 1 of 3)

| With regard to OAKINGOD AVE STREMSWE | , Bidder SWALLOW CONSTRUCTION, ZWC, |
|--------------------------------------|-------------------------------------|
| (Name of Project) | (Name of Bidder) |
| hereby certifies the following: | |

1. Bidder is not barred from bidding this Contract as a result of violations of Section 720 ILCS 5/33E-3 (Bid Rigging) or 720 ILCS 5/33E-4 (Bid-Rotating);

2. Bidder certifies that it has a written sexual harassment policy in place and full compliance with 775 ILCS 5/2-105(A)(4);

Bidder certifies that not less than the prevailing rate of wages as determined by the Village of 3. Downers Grove, DuPage County or the Illinois Department of Labor shall be paid to all laborers, workers and mechanics performing work for the Village of Downers Grove. All bonds shall include a provision as will guarantee the faithful performance of such prevailing wage clause. Bidder agrees to comply with the Illinois Prevailing Wage Act, 820 ILCS 130/1 et seq., for all work completed. Bidder agrees to pay the prevailing wage and require that all of its subcontractors pay prevailing wage to any laborers, workers or mechanics who perform work pursuant to this Contract or related subcontract. Bidder and each subcontractor shall keep or cause to be kept an accurate record of names, occupations and actual wages paid to each laborer, workman and mechanic employed by the Bidder in connection with the contract. This record shall be sent to the Village on a monthly basis along with the invoice and shall be open to inspection at all reasonable hours by any representative of the Village or the Illinois Department of Labor and must be preserved for four (4) years following completion of the contract. Bidder certifies that Bidder and any subcontractors working on the project are aware that filing false payroll records is a Class A misdemeanor and that the monetary penalties for violations are to be paid pursuant to law by the Bidder, contractor and subcontractor. The Village shall not be liable for any underpayments. If applicable: Since this is a contract for a fixed public works project, as defined in 820 ILCS 130/2, Contractor agrees to post at the job site in an easily accessible place, the prevailing wages for each craft or type of worker or mechanic needed to execute the contract or work to be performed;

4. Bidder certifies that it is in full compliance with the Federal Highway Administrative Rules on Controlled Substances and Alcohol Use and Testing, 49 C.F.R. Parts 40 and 382 and that all employee drivers are currently participating in a drug and alcohol testing program pursuant to the Rules;

5. Bidder further certifies that it is not delinquent in the payment of any tax administered by the Department of Revenue, or that Bidder is contesting its liability for the tax delinquency or the amount of a tax delinquency in accordance with the procedures established by the appropriate Revenue Act. Bidder further certifies that if it owes any tax payment(s) to the Department of Revenue, Bidder has entered into an agreement with the Department' of Revenue for the payment of all such taxes that are due, and Bidder is in compliance with the agreement.

Village of Downers Grove

BIDDER'S CERTIFICATION (page 2 of 3)

BY: _

Bidder's Authorized Agent

FEDERAL TAXPAYER IDENTIFICATION NUMBER

or ___

Social Security Number

| Ĭ | OFFICIAL SEAL AICHAEL J. STRINGFELLOW NOTARY PUBLIC, STATE OF ILLINOIS MY COMMISSION EXPIRES 9-16-2015 | { |
|-------|---|---|
| - { i | NOTARY PUBLIC, STATE OF ILLINOIS | ļ |
| 1 | WY COMMISSION EXPIRES 9-16-2015 | Ì |

| Subscribed and sworn to before | re me |
|--------------------------------|--------|
| this 19th day of APRIL | , 20[사 |
| All | |
| Notary Putrii | |

(Fill Out Applicable Paragraph Below)

(a) **Corporation**

| The Bidder is a corporation organized and existing under the laws of the State of $\underline{-}$ operates under the Legal name of \underline{SWAUW} CMSTR4(7), \underline{TW} , \underline{TW} , | <u>HL</u> , which |
|---|----------------------|
| operates under the Legal name of SWAUW CONS (R40710W, ZWC, | , and the full names |
| of its Officers are as follows: | |
| President: <u>ANTONIO PENDINA</u> | |
| Secretary: AVTHONY RENDENA | |
| Treasurer: ANTHONY RENDINA | |

and it does have a corporate seal. (In the event that this bid is executed by other than the President, attach hereto a certified copy of that section of Corporate By-Laws or other authorization by the Corporation which permits the person to execute the offer for the corporation.)

(b) **<u>Partnership</u>**

Signatures and Addresses of All Members of Partnership:

.

BIDDER'S CERTIFICATION (page 3 of 3)

| The partnership does business under the legal name of: | |
|---|--------------------------------|
| which name is registered with the office of | in the state of |
| , | |
| (c) <u>Sole Proprietor</u> The Bidder is a Sole Proprietor whose full name is: | |
| and if operating under a trade name, said trade name is: | |
| which name is registered with the office of | in the state of |
| · | |
| 6. Are you willing to comply with the Village's insurance requirements with contract? (E) | within 13 days of the award of |
| INSURER'S NAME: WESTFIELS + CHUBB | |
| AGENT: ASSURANCE AGENCY, LTA | |
| Street Address: 750 E, GOLF P) | |
| City, State, Zip Code: SCHMM BURG, IL 60173 | |
| Telephone Number: 847-797-5700 | |

I/We hereby affirm that the above certifications are true and accurate and that I/we have read and understand them.

| Print Name of Company: SWALLOW CONSTRUCTION |
|---|
| Print Name and Tyle of Authorizing Signature: AW706V10 REWSINA, PRESIDENT Signature: |
| Date: 4-19-12 |

Village of Downers Grove

~

| | MUNICIPAL REFERENCE LIST | | |
|---|---|----|--------|
| Municipality: Address: Contact Name: Name of Project: Contract Value: | CITY OF WOOD DALE JTL 720 N. CENTRAL, WOODDALE JL JOHN KRAMER Phone #: 630766-490 DEER PATH PD F 1.1 MIL Date of Completion: 1/2011 | По | issues |
| Municipality: Address: Contact Name: Name of Project: Contract Value: | CITY OF WAPPENVILLE, ZL 28 W. (230 STAPPED), WARPENVILLE FL 60555 MILLE SMITH Phone #: 630-393-9427 LANDON AVE 1.2 MIL Date of Completion: 8-31-09 | I | |
| Municipality: Address: Contact Name: Name of Project: Contract Value: | CITY OF WARPENVILLE IL 28W. 630 STAFFOLD, WARPENVILLE IL (00555 MIKE SMITH WARPENVILLE RD PHASE III FI.9 MIL Date of Completion: 4-8-10 | | |
| Municipality: Address: Contact Name: Name of Project: Contract Value: | CITY OF ANDORA, ZL 44 E. DOWNER PL, ANDORA, ZL 60585 LOWNIE AVERY Phone #: 630-256-323 WELL CONFECTOR #29 41.0 MIL Date of Completion: (1-19-09 | 5/ | |
| Municipality: Address: Contact Name: Name of Project: Contract Value: | CITY OF ANDORA ZL "A4 E, DOWNER, MILONA, 7L 6 0555 LONNIE AVERY" Phone #: 630-256-323, NOLTH AVESTURN SEWERZMPROVEMENTS P2.2 MIL Date of Completion: [H16-09] | | |

÷ ...

Village of Downers Grove

SUBCONTRACTORS LIST

The Bidder hereby states the following items of work will not be performed by its organization. (List items to be subcontracted as well as the names, addresses and phone numbers of the subcontractors.)

| 1) <u>T.B.D.</u> | Type of Work | | |
|------------------|----------------|-------|-----|
| | City | | |
| 2) | Type of Work _ | | |
| Addr: | City | State | Zip |
| 3) | Type of Work _ | | |
| Addr: | City | State | Zip |
| 4) | Type of Work _ | | |
| Addr: | City | State | Zip |
| 5) | Type of Work _ | | |
| Addr: | City | State | Zip |
| 6) | Type of Work _ | | |
| Addr: | City | State | Zip |
| 7) | Type of Work _ | | |
| Addr: | City | State | Zip |
| 8) | Type of Work | - | |
| Addr: | City | State | Zip |



VENDOR W-9 REQUEST FORM

The law requires that we maintain accurate taxpayer identification numbers for all individuals and partnerships to whom we make payments, because we are required to report to the I.R.S all payments of \$600 or more annually. We also follow the I.R.S. recommendation that this information be maintained for all payees including corporations.

Please complete the following substitute W-9 letter to assist us in meeting our I.R.S. reporting requirements. The information below will be used to determine whether we are required to send you a Form 1099. Please respond as soon as possible, as failure to do so will delay our payments.

BUSINESS (PLEASE PRINT OR TYPE):

| NAME: | SWALLOW | |
|--|--|--|
| ADDRESS: | 4230 LAC | TY F) |
| CITY: | DOWNFLA | 5 GROVE |
| STATE: | - ZL | · · · · · |
| ZIP: | 605 | 15 |
| PHONE: 6 | 50-512-99V | V FAX: (630-5)2-9902 |
| TAX ID #(TIN): | 36 | -3042988 |
| | | ver, please give your full name) |
| | F DIFFERENT FROM A | ABOVE): |
| NAME: | | |
| NAME: | · · · · · · · · · · | |
| NAME: Address: City: | · · · · · · · · · · | |
| NAME: Address: City: State: PE OF ENTITY (0 | IRCLE ONE): | ZIP: |
| NAME: Address: City: State: PE OF ENTITY (C Indiv | IRCLE ONE): idual | ZIP: |
| NAME: Address: City: State: PE OF ENTITY (c Indiv Sole | IRCLE ONE): idual Proprietor | ZIP: Limited Liability Company –Individual/Sole Proprietor Limited Liability Company-Partnership |
| NAME: Address: City: State: PE OF ENTITY (C Indiv Sole Party | TRCLE ONE): idual Proprietor ership | ZIP: Limited Liability Company –Individual/Sole Proprietor Limited Liability Company-Partnership Limited Liability Company-Corporation |
| NAME: Address: City: State: PE OF ENTITY (C Indiv Sole Partr Med | IRCLE ONE): idual Proprietor ership ical | ZIP: Limited Liability Company –Individual/Sole Proprieton Limited Liability Company-Partnership Limited Liability Company-Corporation Corporation |
| NAME: Address: City: State: PE OF ENTITY (C Indiv Sole Partr Med | TRCLE ONE): idual Proprietor ership | ZIP: Limited Liability Company –Individual/Sole Proprietor Limited Liability Company-Partnership Limited Liability Company-Corporation |

Apprenticeship and Training Certification

(Does not apply to federal aid projects. Applicable only to maintenance and construction projects that use Motor Fuel Tax funds or state grant monies.)

Name of Bidder: SWAUDW CONSTRUCTION, FNG

In accordance with the provisions of Section 30-22 (6) of the Illinois Procurement Code, the Bidder certifies that it is a participant, either as an individual or as part of a group program, in the approved apprenticeship and training programs applicable to each type of work or craft that the bidder will perform with its own forces. The Bidder further certifies for work that will be performed by subcontract that each of its subcontractors submitted for approval either (a) is, at the time of such bid, participating in an approved, applicable apprenticeship and training program; or (b) will, prior to commencement of performance of work pursuant to this Contract, begin participation in an approved apprenticeship and training program applicable to the work of the subcontract. The Illinois Department of Labor, at any time before or after award, may require the production of a copy of each applicable Certificate of Registration issued by the United States Department of Labor evidencing such participation by the contractor and any or all of its subcontractors. Applicable apprenticeship and training programs are those that have been approved and registered with the United States Department of Labor. The Bidder shall list in the space below, the official name of the program sponsor holding the Certificate of Registration for all of the types of work or crafts in which the Bidder is a participant and that will be performed with the Bidder's forces. Types of work or craft work that will be subcontracted shall be included and listed as subcontract work. The list shall also indicate any type of work or craft job category that does not have an applicable apprenticeship or training program. The Bidder is responsible for making a complete report and shall make certain that each type of work or craft job category that will be utilized on the project is accounted for and listed. Return this with the Bid.

CHILAGO LAND LABOR FRY OPERATING ENGINEERY LOCAL #150

The requirements of this certification and disclosure are a material part of the Contract, and the Contractor shall require this certification provision to be included in all approved subcontracts. In order to fulfill this requirement, it shall not be necessary that an applicable program sponsor be currently taking or that it will take applications for apprenticeship, training or employment during the performance of the work of this Contract.

| Print Name and Title of Authorizing Signature: | ANDINO RENDINA PREDIDINT |
|--|--------------------------|
| Signature: | |
| Date: 4-19NZ | |

BUY AMERICA CERTIFICATION

Certification requirement for procurement of steel, iron, or manufactured products when Federal funds (Grant Agreement or Cooperative Agreement) are used.

Instructions:

Bidder to complete the Buy America Certification listed below. Bidder shall certify EITHER COMPLIANCE OR NON-COMPLIANCE (not both). This Certification MUST BE submitted with the Bidder's bid response. Special Note: Make sure you have signed only one of the above statements – either Compliance OR Non-Compliance (not both).

| Certificate of Compliance |
|---|
| The bidder or offeren hereby certifies that it willfmeet the requirements of 49 U.S.C. 5323(j)(1), as amended, and the applicable regulations in 49 CFR Part 661. |
| Company Name SWALLOW CONSTRUCTION |
| Title PREDDENT |
| Date 4-19-12 |

| Certificate of Non-Con | npliance |
|------------------------|---|
| | y certifies that it cannot comply with the requirements of 49 U.S.C. $5323(j)(1)$, as amended, and 49 y for an exception pursuant to 49 U.S.C. $5323(j)(2)(A)$, $5323(j)(2)(B)$, or $5323(j)(2)(D)$, and 49 C.F.R. |
| Signature | : |
| Company Name | ; |
| Title | - |
| Date | |

AFTER THIS CERTIFICATE HAS BEEN EXECUTED, A BIDDER MAY NOT SEEK A WAIVER.

Note: The U.S/Canadian Free Trade Agreement does not supersede the Buy America requirement.

Suspension or Debarment Certificate

Non-Federal entities are prohibited from contracting with or making sub-awards under covered transactions to parties that are suspended or debarred or debarred or debarred. Covered transactions include procurement for goods or services equal to or in excess of \$100,000.00. Contractors receiving individual awards for \$100,000.00 or more and all sub-recipients must certify that the organization and its principals are not suspended or debarred.

By submitting this offer and signing this certificate, the Bidder certifies to the best of its knowledge and belief, that the company and its principals:

1. Are not presently debarred, suspended, proposed for debarment, declared ineligible or voluntarily excluded from covered transactions by any federal, state or local governmental entity, department or agency;

2. Have not within a three-year period preceding this Bid been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction, or convicted of or had a civil judgment against them for a violation of Federal or state antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, or receiving stolen property;

3. Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State, or local) with commission of any of the offenses enumerated in paragraph (2) of this certification; and

4. Have not within a three-year period preceding this application/proposal/contract had one or more public transactions (Federal, State or local) terminated for cause or default.

If the Bidder is unable to certify to any of the statements in this certification, Bidder shall attach an explanation to this certification.

| Company Name: SWAUOW CUNJTRUCTION |
|--|
| Address: 4250 CACEY P |
| City: DOWNTRS GROVE IL Zip Code 605/5 |
| Telephone: (639) 512-9900 Fax Number: (639) 512-9902 |
| E-mail Address: MMHUNY SYALUW CONSTRUCTION, NF |
| Authorized Company Signature: |
| Print Signature Name: Aronio PENNIA Title of Official: PRESIDENT |
| Date: 4-19-12 |

CAMPAIGN DISCLOSURE CERTIFICATE

Any contractor, proposer, bidder or vendor who responds by submitting a bid or proposal to the Village of Downers Grove shall be required to submit with its bid submission, an executed Campaign Disclosure Certificate.

The Campaign Disclosure Certificate is required pursuant to the Village of Downers Grove Council Policy on Ethical Standards and is applicable to those campaign contributions made to any member of the Village Council.

Said Campaign Disclosure Certificate requires any individual or entity bidding to disclose campaign contributions, as defined in Section 9-1.4 of the Election Code (10 ILCS 5/9-1.4), made to current members of the Village Council within the five (5) year period preceding the date of the bid or proposal release.

By signing the bid documents, contractor/proposer/bidder/vendor agrees to refrain from making any campaign contributions as defined in Section 9-1.4 of the Election Code (10 ILCS 5/9-1.4) to any Village Council member and any challengers seeking to serve as a member of the Downers Grove Village Council.

Under penalty of perjury, I declare:

Bidder/vendor has not contributed to any elected Village position within the last five wears. Signature

Bidder/vendor has contributed a campaign contribution to a current member of the Village Council within the last five (5) years.

Print the following information: Name of Contributor:

(company or individual)

To whom contribution was made: _____

Year contribution made: _____ Amount: \$

Signature

Print Name

BID SUBMITTAL CHECKLIST

Each Bidder's Bid Package must be submitted with all requisite forms properly completed, and all documentation included. The following list is not all-inclusive, but is designed to facilitate a good, competitive bidding environment.

- 1. Instructions to Bidders read and understood. Any questions must be asked according to the instructions.
- 2. $\overleftarrow{\mathsf{X}}$ Cover sheet filled-in
- 3. Bid Form copies filled-in. All copies must have original signatures and seals on them.
- 4. Bid Bond or cashier's check enclosed with bid package.
- 5. Schedule of Prices completed. Check your math!
- 6. \square Bidder Certifications signed and sealed.
- 7. Letter from Surety ensuring issuance of Performance and Labor Bonds.
- 8. Letter from Insurance Agent or Carrier ensuring issuance of required job coverage.
- 9. Municipal Reference List completed.
- 10. \square Vendor request form W-9 completed.
- 11. Affidavit (IDOT Form BC-57, or similar).
- 12. Bid package properly sealed and labeled before delivery. If sending by mail or messenger, enclose in a second outer envelope or container. Project plan sheets do not have to be included with the bid package.

VILLAGE OF DOWNERS GROVE

DEPARTMENT OF PUBLIC WORKS

ADDENDUM NO. 1

FOR

OAKWOOD AVENUE STORM SEWER REPLACEMENT

SW-070-12

April 18, 2012

VILLAGE OF DOWNERS GROVE DEPARTMENT OF PUBLIC WORKS

OAKWOOD AVENUE STORM SEWER REPLACEMENT

SW-070-12 ADDENDUM NO. 1 April 18, 2012 ADDENDUM PAGE TOTAL INCLUDING ATTACHMENTS: 3 Attached are: a revised schedule of prices

ITEM AND DESCRIPTION:

- 1. The Acknowledgement of Receipt of Addendum for this addendum MUST be included in the bid package. Bid packages not including signed Acknowledgement Sheets may be REJECTED.
- All storm sewer structures called out as "CB-XXX (3' DIA., TYPE B)" are mislabeled. These storm sewer structures are Type B Inlets and should have the "INL" designation. The detail for Type B Inlets is shown on sheet 14. The plans will be revised to show the correct structure labeling and will be given to the successful bidder.
- 3. The "Schedule of Prices" in the advertised Call for Bid document and the summary of quantities on sheet 3 of the plans shall be replaced with the revised, attached "Schedule of Prices." Failure to submit the correct, attached "Schedule of Prices" will result in a REJECTED bid. Also, make sure your numbers are checked and verified.
- 4. Reminder that the advertised Call for Bid document includes a special provision for the IEPA's Clean Construction or Demolition Debris requirements. Please see Special Provision 22 (SP-22) in the Call for Bid document.

End of Addendum No. 1 April 18, 2012

<u>SCHEDULE OF PRICES – REVISED WITH ADDENDUM #1:</u>

Base Bid

| # | Debris Removal | | | s Ánnan an sanna an | |
|---|--|--|--|--|---------------|
| <u>#</u> | ITEM | UNIT | | Probleman and a Versite to get as the concernence of | 1 |
| 67100100 | MOBILIZATION | LSUM | QUANTITY | UNIT COST | TOTAL COST |
| SP-2 | CONSTRUCTION STAKING AND RECORD DRAWINGS | LSUM | 1 | 5.500- | 5500- |
| SP-3 | TERECONSTRUCTION VIDEOTAPING | | <u> 1</u> | 8000- | 8000- |
| <u>SP-5</u> | TREE PROTECTION | FOOT | 11 | 3000- | 3000- |
| <u>SP-6</u> | TREE ROOT PRUNING | FOOT | 2,300 | 2- | 4600 - |
| <u>SP-8</u> | STREET SWEEPING AND DUST CONTROL | HOUR | 100 | 10 - | 1000 - |
| <u>SP-9</u> | TRAFFIC CONTROL, MAINTENANCE OF TRAFFIC, DETOURS | | 25 | 50. | 1250- |
| SP-25 | COMBINATION CONCRETE CURB AND GUTTER REMOVAL (RE | FOOT | 1 | 8500- | 8500- |
| SP-10 | DISTINGUES TRUCTORES TO BE REMOVED | EACH | 400 | | 2000- |
| SP-11 | HMA DRIVEWAY REMOVAL AND REPLACEMENT (3") | SQ YD | 11 | 100- | 1100- |
| SP-12 | PCC DRIVEWAY REMOVAL & REPLACMENT (6") | | 40 | 37- | 1480- |
| <u>SP-13</u> | P.C.C. SIDEWALK REMOVAL | SQ YD | 25 | 64- | 1725- |
| X4401198 | VARIABLE HMA SURFACE REMOVAL, 2" TO 3.5" | SQ FT | 850 | 1- | 850- |
| 44000100 | FULL DEPTH PAVEMENT REMOVAL | SQ YD | 4,000 | 4 - | 16,000- |
| · · · · · · · · · · · · · · · · · · · | | SQYD | 2,400 | 10 - | 24,000- |
| alnage Impr | 'DVennents | | | Subtotal | |
| # | | · · · · · · · · · · · · · · · · · · · | and an | Subtotal | 11000 |
| SP-14 | SANITARY SERVICE RECONNECTION | UNIT | QUANTITY | UNIT COST | TOTAL COST |
| SP-15 | STORM SEWER, RCP, CL IV, 12" | EACH | 17 | 250- | 4250 |
| SP-15 | STORM SEWER, CLASS 52 DIP, 18" | FOOT | 1450 | 38- | 55,100 |
| | TRENCH BACKFILL | FOOT | 25 | 105- | 2625- |
| | | CU YD | 700 | 33- | 23,100 - |
| 50218400 | EXPLORATION TRENCH (5' MINIMUM PER LOCATION) | FOOT/60-INCH DEPTH | 250 | 6 - | 15,00 - |
| 60219570 | MANHOLE, TYPE A, 4-DIAMETER, TYPE 1 F&G, CL | EACH | 3 | 1700 - | 5-100- |
| | MANHOLE, TYPE A, 4'-DIAMETER, TYPE 3V F&G | EACH | 1 | 1750- | 1750 - |
| 60200310 | CATCH BASIN, TYPE A, 4'-DIAMETER, TYPE 1 F&G, CL | EACH | 9 | | 17.8001 |
| 30204005 | CATCH BASIN, TYPE A, 4'-DIAMETER, TYPE 3V F&G | EACH | 1 | 2 000- | 2000 - |
| 50206602 | CATCH BASIN, TYPE A, 5'-DIAMETER, TYPE 3V F&G | EACH | 1 | 2500- | 2500 - |
| | INLET, INPE BY MRE I F&G. OL | EACH | 3 | 900 - | 2700- |
| | NUET, TYREIB, TYPE BY Fag | EACH | 3 | 900 - | 2700 - |
| | INLETS, TYPE A, TYPE 3V F&G | EACH | 4 | 810 - | 3240- |
| | INLETS, TYPE A, NEENAH R-3508-B F&G | EACH | 2 | 810 - | - 05 6) |
| <u>SP-17</u> | ADJUSTING DIP WATERMAIN, 6", CL52 | FOOT | 40 | 125- | |
| SP-18 | ADJUSTING WATER SERVICE LINES | EACH | 17 | 1/00- | 5,000- |
| <u>SP-23</u> | ADJUSTING SANITARY SERVICE LINES | EACH | 17 | 280- | 18,700- 4760- |
| | RESTRICTOR PLATE, 12" | EACH | 1 | 3650- | |
| | | | | 0630- | 3650- |
| ement and | Parkway Restoration Improvements | analysis and a subsection of the sector of | | Subtotal | 157,395 |
| # | ITEM | I Kharte | | | |
| 0600100 | BITUMINOUS MATERIALS, PRIME COAT | | QUANTITY | UNIT COST | TOTAL COST |
| 0800625 | VARIABLE DEPTH (0.5" TO 2") LEVELING BINDER, MACHINE N | GAL, | 500 | 3- | 1500- |
| 0603310 | HOT MIX ASPHALT SURFACE COURSE, MIX C, N50 | TON | 500 | 82- | 41,000 - |
| 0603080 | HOT MIX ASPHALT BINDER COURSE, IL-19.0, N50 | TON | 500 | 62- | 41,000. |
| SP-19 | TEMPORARY SURFACE OVER TRENCH | TON | 1,100 | 86- | 94,600. |
| SP-20 | PARKWAY RESTORATION, SALT TOLERANT SOD, SPECIAL | SQYD | 1,500 | 5- | 7500- |
| SP-13 | P.C.C. SIDEWALK, 5 INCH, NEW | SQYD | 650 | 10- | 6500- |
| SP-26 | COMB/NATION CONCRETE CURB AND GUTTER (B6.18) | SQ FT | 1,200 | 6- | 7200- |
| SP-21 | DETECTABLE WARNINGS | FOOT | 460 | 22. | 10,120 - |
| | | SQ FT | 140 | 20- | 2800 |
| | POROUS GRANULAR EMBANKMENT, SUBGRADE SPECIAL | CUYD | 500 | 60- | 5000 - |
| | | | | | |
| • | | | | Subtotal | C11,000 |
| | | · · · · · · · · · · · · · · · · · · · | 0100 (100 (100 (F (100 (10) (100 (100 (10) (100 (10) (100 (10) | | 2,620 |
| 1 | | | | | |

VILLAGE OF DOWNERS GROVE DEPARTMENT OF PUBLIC WORKS

ACKNOWLEDGEMENT OF RECEIPT OF ADDENDUM

PROPOSAL/BID: OAKWOOD AVENUE STORM SEWER REPLACEMENT

PROPOSAL/BID NUMBER: SW-070-12

PROPOSAL/BID OPENING: APRIL 20, 2012

| ADDENDUM NO.: | 1 |
|----------------|---|
| PROPOSER/BIDDI | ER: <u>Swallow</u> Construction |
| ADDRESS: | 4250 Lacey Rd, Downers Groot, IL 60515 |
| RECEIVED BY: | <u>Nan Balek</u> (NAME) |
| | Danie Ballk (SIGNATURE) |
| | (SIGNATURE) |
| DATE: | 4-18-12 |

PAGE 03/03 Adriantistration, Nopremiticarthip Iraining, syer and Babor Service. Office of Apprenticeship Training, Amployer and Ashockerices And States Bepartment Ante Registered as part of the National Apprenticeship Priram in accordance with the basic standards of apprenticesp R.J. Che Jurt Com Pureau of Apprenticeship and Oraining established by the Secretary of Babor Por the Trade - Construction Craft Laborer secretary of Babar Chicagoland Laborers' J.A. 1.C. Carol Stream, Illinois Ortificate of Registration STUTION OF Dar REVISED August 13, 2004 L012990001 Se . Registration He

LABURER TRN ONTR

LABORER TRN CNTR



1200 Okl Gary Avenue Carol Stream, Illinois 60188

Tel: 630.653.6006 Fax: 630.653.2762

Chicagoland Laborers' District Council Training and Apprentice Fund

4 April 2012

Chicagoland

Training & Apprentice Fund

Swallow Construction Corp 4250 Lacey Road Downers Grove, IL 60515

Mr. Mike Stringfellow:

Enclosed you will please find a copy of the Department of Labor certification that you requested recently.

You may also use this letter as verification that Swallow Construction Corp is indeed signatory to the Laborers District Council and contribute to the Laborers Training and Apprenticeship Fund.

Should you require anything further, please do not hesitate to contact me.

Yours very truly,

Paul Hoetzer Apprentice Coordinator

Management Trustees David Lorig Donald Henderson Thomas Nordeen Robert G. Krug Larry Keefe Joseph Koppers



Peter Ruff Administrator Labor Trustees James P. Connolly Charles V. LoVerde III Liberato Naimoli Martin Flanagan Toby Koth Anthony DeLuca

02/28/2008 16:24 FAX Ø 003 Other of Apprendiceship Araining, Amployer and Qahor Services Registered as part of the National Apprenticeship Program in accordance with the basic standards of apprenticeship S. Ches Alanaidraha, Joneodicealin Iraining Dureus of Apprendiceship and Araining - Maren established by the Secretary of Babar Operating Engineers Local #150 Nainfield, Illinois Por the Trade of Operating Engineer Certificate of Reytstration lates Menary November 5, 2002 JL 008780173 Magistration 96 Dala

DIST 1 DISPATCH

1003

INTERNATIONAL UNION OF OPERATING ENGINEERS

LOCAL UNION NO. 150, 1509, 150A, 150C, 150RA, 150D, 150G, 150M APPILIATED WITH THE A.G.L.-C.I.O. AND BUILDING TRADES DEPARTMENT

JAMES M. S'VEENEY PRESIDENT-SUSINES : MANAGER



(708) 482-8800 - FAX (708) 482-7185 S200 JOLIET ROAD COUNTRYSIDE. IL 00525-3992

April 4, 2012

Swillow Construction Corp 425) Lacey Rd Do yners Grove, IL 60515

> Re: Proof of Compliance with 30 ILCS 500/30-22(6) Our File No. MI-00321

De ir Sir or Madam:

At the request of Swallow Construction Corp, I am providing you with evidence of the Company's compliance with the apprenticeship requirements in 30 ILCS 500/30-22(6) of the Illinois Procurement Code. I am submitting this letter along with apprenticeship ce tificates (Nos.IL012020003 and IL008780173).

A: a signatory contractor with the International Union of Operating Engineers, Local 150, AFL-CIO, Brothers Swallow Construction Corp, is required by Collective B: rgaining Agreement to participate in an applicable apprenticeship and training program ar proved by and registered with the United States Department of Labor's Bureau of A prenticeship and Training. The attached certificates are evidence of compliance with the U.S. Department of Labor's apprenticeship requirements.

T tank you for your cooperation in this matter. If you have any questions or concerns, please do not hesitate to contact me.

Very truly yours,

IUOE, Local 150, AFL-CIO District 1 dispatch office

autin Lectill

Pauline Leitzell

I'L/ag

Enclosures: Certificates



Tel: (815) 485-4100 Pax: (815) 485-2936

1005 Laraway Road P.O. Box 39 New Lenax, IL 60451

April 20, 2012

Village of Downers Grove 5101 Walnut Avenue Downers Grove, IL 60515

Re: Swallow Construction Corporation - Oakwood Ave Storm Sewer Replacement

To Whom It May Concern:

It is our understanding that Swallow Construction Corporation, intends to submit a bid proposal to you for the above referenced project.

As surety for Swallow Construction Corporation, the Merchants Bonding Company, at the request of Swallow Construction Corporation and subject to our normal underwriting considerations, will issue the required bid bond, and if Swallow Construction Corporation is awarded the contract a performance and payment bond will be issued on the forms provided by the owner in the full amount of the contract. It is understood that a surety relationship is strictly a matter between the surety and the principal and we cannot be held responsible to any third parties or to our principal itself if for whatever reason we elect not to execute a bond.

Merchants Bonding Company has a group rating of A/VI according to A.M. Best, is listed in the U.S. Treasury Circular as an approved surety and is licensed to transact surety business in all of the United States

Sincerely,

By:

Merchants Bonding Company aven

Robert H. Walker, Attorney-in-fact



Chicago, IL St. Louis, MO www.assuranceagency.com

April 19, 2012

Mr. Mike Stringfellow Swallow Construction Corp. 4250 Lacey Road Downers Grove, IL 60515

RE: Construction bid for Village of Downers Grove

Dear Mike:

Your current insurance policies are in compliance with the insurance requirements set forth in section 32 of the contract from the Village of Downers Grove assuming Swallow Construction Corp does not need to provide professional liability insurance. However, notice of cancellation is only provided to the first named insured on the policies. Please contact me directly any questions.

Sincerely,

Jennif K Tuayon

Jennifer Tuazon



Insurance Requirements Review

| RE: | Review for: Village of Downers Grove |
|-----|---------------------------------------|
| То: | Anthony Rendina, Swallow Construction |

We have reviewed the insurance requirements Anthony Rendina sent over via e-mail on 4/18/2012; our review determined the following:

| General Liability | Meets Requirement | Does Not Meet Requirement |
|--|---|---|
| Additional Insured Status Required | Provided via your Blanket Additional Insured Endorsement (see note below) | |
| | The additional insured status on your endorsement is triggered: When a signed contract exists between you and each of the additional insured part(ies). See important note below. | |
| Additional Requirements | Meets Requirement | Does Not Meet Requirement |
| Notice of Cancellation | | Notice of cancellation, or material change, can only be granted through language specifically on the policy. Such language or endorsements are not generally available in the insurance marketplace. Agents/brokers are not authorized to show any coverage or policy provision on the certificate that is not on the policy. |
| Indemnification or Hold Harmless or Contractual Liability to insure this contract provisions | | See important note below |

Additional Insured Endorsement/Waiver of Subrogation Endorsement Note: Most additional insured/waiver of subrogation forms require that a written contract be executed in order to trigger the additional insured coverage under the policy. The requirement sometimes can be as specific as to require that the additional insured must be a direct signatory on the contract with you. Our review does not verify whether you have the appropriate contract(s) in place or not.

IMPORTANT: Many contracts or insurance requirements include hold harmless or indemnification wording that requires you to indemnify another party for claims. All General Liability policies contain exclusions that limit coverage; and thus insurance is not available in the marketplace to fully cover such broadly written contract provisions that are not in accord with policy exclusions.

Reviewed By: Jennifer Tuazon Date: 4/18/2012 9:48:05 AM



2300 South Dirksen Parkway/Room 322 Springfield, Illinois 62764

Instructions: Complete this form by either typing or using black ink. "Authorization to Bid" will not be issued unless both sides of this form are completed in detail. Use additional forms as needed to list all work.

Affidavit of Availability For the Letting of

Part I. Work Under Contract

List below all work you have under contract as either a prime contractor or a subcontractor. It is required to include all pending low bids not yet awarded or rejected. In a joint venture, list only that portion of the work which is the responsibility of your company. The uncompleted dollar value is to be based upon the most recent engineer's or owners estimate, and must include work subcontracted to others. If no work is contracted, show NONE.

| | 1 | 2 | 3 | 4 | Awards Pending | |
|--|--------------|------------|---|-------------|----------------|-----------------------|
| Contract Number | 11-082 | | | | | |
| Contract With | DUPACKE 711M | NSHIP | | | | |
| Estimated Completion Date | 6-14-2013 | <i>μ</i> 2 | | | | |
| Total Contract Price | 2,194,533 | | | | | Accumulated Totals |
| Uncompleted Dollar Value if Firm is the Prime Contractor | 1,840,529 | | | | | 1,29429 |
| Uncompleted Dollar Value if Firm is the Subcontractor | 6 | | | | 1 | Ľ IS |
| | | | | Total Value | e of All Work | 1,840,529 |

Part II. Awards Pending and Uncompleted Work to be done with your own forces.

| List below the uncompleted dollar value subcontracted to others will be listed on th company. If no work is contracted, show N | e reverse of this fo | h contract and awar orm. In a joint ventu | ds pending to be con re, list only that portion | npleted with your own on of the work to be o | n forces. All work done by your | Accumulated Totals |
|--|--|--|--|--|---|--|
| Earthwork | 73,206 | | | | | 73,206 |
| Portland Cement Concrete Paving | | | | | | |
| HMA Plant Mix | | | \ | | | Company and Company of |
| HMA Paving | and the second s | | | | | and the second se |
| Clean & Seal Cracks/Joints | THE OWNER AND THE OWNER | | | | | and the state of the second |
| Aggregate Bases & Surfaces | Maccosson | | | | | and the second sec |
| Highway, R.R. and Waterway Structures | ENVIRED ADDRESS ADDRESS | | | | | anathread and a second |
| Drainage | 1,435,878 | | | | | 1,435878 |
| Electrical | - | | | | | - Contraction of the second |
| Cover and Seal Coats | | | | | | frails and the arrange and the second |
| Concrete Construction | and the second state of the | | | | | attention that that the loss of the |
| Landscaping | and the second formation of the second se | | | | | and the second second |
| Fencing | Consultaneous and | | | | | Construction and a second |
| Guardrail | Property and a second second | | | | | STREET FROM FOR |
| Painting | A CONTRACTOR OF THE OWNER | | | | | JANIMANTI TRANSFORMENT |
| Signing | State of the second sec | | | | | |
| Cold Milling, Planning & Rotomilling | - and the second | | | | | Participation in the second |
| Demolition | a second and the second se | | | | | and and the second second second |
| Pavement Markings (Paint) | | | | | | Alter Alter and a second and a second |
| Other Construction (List) | and the second s | | | | | Construction and the construction of the const |
| | | | _ | | and Second Se | \$ 0.00 |
| Totals | 1,509084 | - particular - | and the second s | and the second sec | Surface and a second second | 1.509,084 |

Disclosure of this information is REQUIRED to accomplish the statutory purpose as outlined in the "Illinois Procurement Code." Failure to comply will result in non-issuance of an "Authorization To Bid." This form has been approved by the State Forms Management Center.

Part III. Work Subcontracted to Others.

For each contract described in Part I, list all the work you have subcontracted to others.

| | 1 | 2 | 3 | 4 | Awards Pending |
|-----------------------|--|---|--|--|--|
| Subcontractor | TRA FAC CON | 7201 | / | | and the second second |
| Type of Work | TRAFFIC W | per / | | | |
| Subcontract Price | 18,250. | | | | |
| Amount Uncompleted | 10,125 | | | | |
| Subcontractor | GENEVA | | | and the second second | and the second |
| Type of Work | HMA - CON | CRF7E/ | and a start of the | And and the second second | and the second second second |
| Subcontract Price | 166320 | | 1. The state of th | | A STATE OF THE OWNER |
| Amount Uncompleted | 166,320 | | / . | | ۶۹ ۱ |
| Subcontractor | R3 UNABRE | phound / | and the second se | ADV-Starten Part | and the second se |
| Type of Work | DIRECTIONA | FC / | and the second second | and the second second | and the second se |
| Subcontract Price | 160,203,00 | and the second se | and the second second second | | and the second se |
| Amount Uncompleted | 1'SO, UOU_ " | | Constant of the second s | | Ľ |
| Subcontractor | LAND TECH | | | | |
| Type of Work | LAYNY 7. | | and the second second | and the second se | and the second second |
| Subcontract Price | 8501, 25 | | - Televine and the second | No. of Concerns and Concerns | and the second s |
| Amount Uncompleted | 5,000 60 | | Carline C. | and the second s | |
| Subcontractor | a start of the sta | for the second | | and the second | |
| Type of Work | and the second second | and the second se | and the second se | and the second se | and the second second |
| Subcontract Price | | 15 Martin Carlos | NUT STORE STORE STORE STORE | and the second sec | |
| Amount Uncompleted | | 1 | and a second second | | 6 |
| Total Uncompleted | 331,445.4 | and the second se | and the second sec | and the second se | |

I, being duly sworn, do hereby declare that this affidavit is a true and correct statement relating to ALL uncompleted contracts of the undersigned for Federal, State, County, City and private work, including ALL subcontract work, ALL pending low bids not yet awarded or rejected and ALL estimated completion dates.

Subscribed and sworn to before me 20 411 エレ this day of Type or ht Name icer birecto Signed Notary Public a o My commission expires ONT Company (Notary Seal) Address OFFICIAL MICHAEL J. STRINGFELLOW SEAL NOTARY PUBLIC, STATE OF ILLINOIS MY COMMISSION EXPIRES 9-16-2015

MATA® Document A310[™] – 2010

Bid Bond

CONTRACTOR:

(Name, legal status and address)

Swallow Construction Corporation 4250 Lacev Road Downers Grove, IL 60515

OWNER:

(Name, legal status and address) Village of Downers Grove 5101 Walnut Avenue Downers Grove, IL 60515

SURETY:

(Name, legal status and principal place of business) Merchants Bonding Company 2100 Fleur Drive Des Moines, Iowa 50321-1158

BOND AMOUNT: \$ -- Five Percent of Accompanying Bid--- 5% of Bid--

PROJECT:

(Name, location or address, and Project number, if any) Oakwood Ave. Storm Sewer Replacement Village of Downers Grove, IL

The Contractor and Surety are bound to the Owner in the amount set forth above, for the payment of which the Contractor and Surety bind themselves, their heirs, executors, administrators, successors and assigns, jointly and severally, as provided herein. The conditions of this Bond are such that if the Owner accepts the bid of the Contractor within the time specified in the bid documents, or within such time period as may be agreed to by the Owner and Contractor, and the Contractor either (1) enters into a contract with the Owner in accordance with the terms of such bid, and gives such bond or bonds as may be specified in the bidding or Contract Documents, with a surety admitted in the jurisdiction of the Project and otherwise acceptable to the Owner, for the faithful performance of such Contract and for the prompt payment of labor and material furnished in the prosecution thereof; or (2) pays to the Owner the difference, not to exceed the amount of this Bond, between the amount specified in said bid and such larger amount for which the Owner may in good faith contract with another party to perform the work covered by said bid, then this obligation shall be null and void, otherwise to remain in full force and effect. The Surety hereby waives any notice of an agreement between the Owner and Contractor to extend the time in which the Owner may accept the bid. Waiver of notice by the Surety shall not apply to any extension exceeding sixty (60) days in the aggregate beyond the time for acceptance of bids specified in the bid documents, and the Owner and Contractor shall obtain the Surety's consent for an extension beyond sixty (60) days.

If this Bond is issued in connection with a subcontractor's bid to a Contractor, the term Contractor in this Bond shall be deemed to be Subcontractor and the term Owner shall be deemed to be Contractor.

When this Bond has been furnished to comply with a statutory or other legal requirement in the location of the Project, any provision in this Bond conflicting with said statutory or legal requirement shall be deemed deleted herefrom and provisions conforming to such statutory or other legal requirement shall be deemed incorporated herein. When so

ADDITIONS AND DELETIONS:

The author of this document has added information needed for its completion. The author may also have revised the text of the original AIA standard form. An Additions and Deletions Report that notes added information as well as revisions to the standard form text is available from the author and should be reviewed. A vertical line in the left margin of this document indicates where the author has added necessary information and where the author has added to or deleted from the original AIA text.

This document has important legal consequences. Consultation with an attorney is encouraged with respect to its completion or modification.

Any singular reference to Contractor, Surety, Owner or other party shall be considered plural where applicable.

AIA Document A310™ – 2010. Copyright © 1963, 1970 and 2010 by The American Institute of Architects. All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it. 1 may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law. This document was produced by AIA software at 13:30:56 on 04/19/2012 under Order No.5894142554_1 which expires on 06/25/2012, and is not for resale. (961037134) User Notes:

furnished, the intent is that this Bond shall be construed as a statutory bond and not as a common law bond.

Signed and sealed this 20th day of April, 2012

(Witness)

| Swallow Construction Corporation | |
|----------------------------------|--------|
| (Contractor as Principat) | (Seal) |
| Altrong Karlin | ~ |
| White PRIDIDIN' | |
| Merchants Bonding Company | |
| (Surety) The AD (1.2. A | (Seal) |

(Title)Robert H. Walker, Attorney-in-fact

AIA Document A310™ – 2010. Copyright © 1963, 1970 and 2010 by The American Institute of Architects. All rights reserved. WARNING: This AIA® Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA® Document, or any portion of it. may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law. This document was produced by AIA software at 13:30:56 on 04/19/2012 under Order No.5894142554_1 which expires on 06/25/2012, and is not for resale. User Notes:

2

lnit. I

| STATE OF <u>Illinois</u> | | | |
|--|--------------------|-------------------|--|
| COUNTY OF Will | | ss.: | |
| On this <u>20th</u> personally appeared | | ** ** | , before me |
| | | thathe | , to me known, who, _ reside(s) at |
| of <u>Merchants Bonding</u> | Company | | is/are the <u>Attorney-in-fact</u> , the corporation described |
| in and which executed the an | nexed instrumer | it; thathe_ | _ know(s) the corporate seal of such corporate seal; that it was |
| so affixed by order of the Boa | ard of Directors | of said corpo | ration; that <u>he</u> he signed the |
| same name(s) thereto by like | order; and 'that ' | the liabilities o | of said corporation do not ex- |
| ceed its assets as ascertained in | the manner pr | ovided by law | |

"OFFICIAL SEAL"
 KIMBERLY GORMAN
 Notary Public, State of Illinois
 My Commission Expires 08/04/15

BOND-3768-A

Surety Company Acknowledgment

(Notary Public in and for the above County and State)

· 물건물건 전 2011년 - 2011년

My commission expires 08/04/15



Know All Persons By These Presents, that the MERCHANTS BONDING COMPANY (MUTUAL), a corporation duly organized under the laws of the State of Iowa, and having its principal office in the City of Des Moines, County of Polk, State of Iowa, hath made, constituted and appointed, and does by these presents make, constitute and appoint

Rob W. Kegley, Jr., Richard L. McWethy, Kevin J. Scanlon, Robert H. Walker, Gary A. Eaton

of New Lenox and State of Illinois its true and lawful Attorney-in-Fact, with full power and authority hereby conferred in its name, place and stead, to sign, execute, acknowledge and deliver in its behalf as surety any and all bonds, undertakings, recognizances or other written obligations in the nature thereof, subject to the limitation that any such instrument shall not exceed the amount of:

TEN MILLION (\$10,000,000.00) DOLLARS

and to bind the MERCHANTS BONDING COMPANY (MUTUAL) thereby as fully and to the same extent as if such bond or undertaking was signed by the duly authorized officers of the MERCHANTS BONDING COMPANY (MUTUAL), and all the acts of said Attorney-in-Fact, pursuant to the authority herein given, are hereby ratified and confirmed.

This Power-of-Attorney is made and executed pursuant to and by authority of the following Amended Substituted and Restated By-Laws adopted by the Board of Directors of the MERCHANTS BONDING COMPANY (MUTUAL) on November 16, 2002.

ARTICLE II, SECTION 8 - The Chairman of the Board or President or any Vice President or Secretary shall have power and authority to appoint Attorneys-in-Fact, and to authorize them to execute on behalf of the Company, and attach the Seal of the Company thereto, bonds and undertakings, recognizances, contracts of indemnity and other writings obligatory in the nature thereof.

ARTICLE II, SECTION 9 - The signature of any authorized officer and the Seal of the Company may be affixed by facsimile to any Power of Attorney or Certification thereof authorizing the execution and delivery of any bond, undertaking, recognizance, or other suretyship obligations of the Company, and such signature and seal when so used shall have the same force and effect as though manually fixed.

In Witness Whereof, MERCHANTS BONDING COMPANY (MUTUAL) has caused these presents to be signed by its President and its corporate seal to be hereto affixed, this 23rd day of Sept., 2011.



MERCHANTS BONDING COMPANY (MUTUAL)

arry Taylo

President

STATE OF IOWA COUNTY OF POLK ss.

On this 23rdday of Sept., 2011, before me appeared Larry Taylor, to me personally known, who being by me duly sworn did say that he is President of the MERCHANTS BONDING COMPANY (MUTUAL), the corporation described in the foregoing instrument, and that the Seal affixed to the said instrument is the Corporate Seal of the said Corporation and that the said instrument was signed and sealed in behalf of said Corporation by authority of its Board of Directors.

In Testimony Whereof, I have hereunto set my hand and affixed my Official Seal at the City of Des Moines, Iowa, the day and year first above written.



endy Am

Notary Public, Polk County, Iowa

STATE OF IOWA COUNTY OF POLK ss.

I, William Warner, Jr., Secretary of the MERCHANTS BONDING COMPANY (MUTUAL), do hereby certify that the above and foregoing is a true and correct copy of the POWER-OF-ATTORNEY executed by said MERCHANTS BONDING COMPANY (MUTUAL), which is still in full force and effect and has not been amended or revolved.

In Witness Whereof, I have hereunto set my hand and affixed the seal of the Company on this 20th day of April 2012



William Harner Jo, Secretary

V. BID and CONTRACT FORM (Village)

***THIS BID WHEN ACCEPTED AND SIGNED BY AN AUTHORIZED SIGNATORY OF THE VILLAGE OF DOWNERS GROVE SHALL BECOME A CONTRACT BINDING UPON BOTH PARTIES.

Entire Form Must Be Completed If a Submitted Bid Is To Be Considered For Award BIDDER:

| SWALDW WNJTHICTION Company Name | <u> </u> |
|--|---|
| <u>42SO LACET PD</u> Street Address of Company | ANTHING SWALLOW CUNSTRUCTION, NAT |
| DOWNERS GROVE ZL 60515 City, State, Zip | ANTHONY RENSINA Contact Name (Print) |
| $\frac{(30-S)2-9900}{\text{Business Phone}}$ | 630-417-7883 24-Hour Telephone |
| 630-512-9902 Business Fax | Signature of Officer, Partner or Sole Proprietor |
| ATTEST: if a Corporation | ANDNIO PLONDINA, PRESIDENT Print Name & Title |
| Signature of Corporation Secretary We hereby agree to furnish the Village of Down | ners Grove all necessary materials, equipment, labor, etc. to |
| | om the date of the Notice to Proceed in accordance with the |
| VILLAGE OF DOWNERS GROVE: | ATTEST: |
| Authorized Signature | Village Clerk |
| Title | |
| Date | Date |

In compliance with the specifications, the above-signed offers and agrees, if this Bid is accepted within 90 calendar days from the date of opening, to furnish any or all of the services upon which prices are quoted, at the price set opposite each item, delivered at the designated point within the time specified above.

V. BID and CONTRACT FORM (Contractor)

***THIS BID WHEN ACCEPTED AND SIGNED BY AN AUTHORIZED SIGNATORY OF THE VILLAGE OF DOWNERS GROVE SHALL BECOME A CONTRACT BINDING UPON BOTH PARTIES.

Entire Form Must Be Completed If a Submitted Bid Is To Be Considered For Award BIDDER:

| SWALLOW CONSTRUCTION | 4-19-12 |
|---|---|
| Company Name | Date |
| <u>4250 LACEY P</u> Street Address of Company | AW7HONY OS WALLOW CONSTRUCTION NET E-mail Address |
| Downth's GROVEFIL 60518 City, State, Zip | <u>ANTHONY</u> <u>RENS/MA</u> Contact Name (Print) |
| $\frac{(3) - 512 - 9900}{\text{Business Phone}}$ | (3U-477-7883) 24-Hour Telephone |
| | |
| Business Fax | Signature of Officer, Partner or Sole Proprietor |
| ATTEST: if a Corporation | AWZUNIO RENSINA, PREDSENT Print Name & Title |
| X Hellowy Kerchi | Plini Name & liue |
| Signature of Corporation Secretary | |
| We hereby agree to furnish the Village of Downer complete the project within <u>60</u> calendar days from provisions, instructions and specifications for the | rs Grove all necessary materials, equipment, labor, etc. to n the date of the Notice to Proceed in accordance with the unit prices shown on the Schedule of Prices. |
| | |

VILLAGE OF DOWNERS GROVE:

ATTEST:

Authorized Signature

Village Clerk

| Τ | ì | tl | e |
|---|---|----|---|
| | | | |

Date

Date

In compliance with the specifications, the above-signed offers and agrees, if this Bid is accepted within **90** calendar days from the date of opening, to furnish any or all of the services upon which prices are quoted, at the price set opposite each item, delivered at the designated point within the time specified above.

CAMPAIGN DISCLOSURE CERTIFICATE

Any contractor, proposer, bidder or vendor who responds by submitting a bid or proposal to the Village of Downers Grove shall be required to submit with its bid submission, an executed Campaign Disclosure Certificate.

The Campaign Disclosure Certificate is required pursuant to the Village of Downers Grove Council Policy on Ethical Standards and is applicable to those campaign contributions made to any member of the Village Council.

Said Campaign Disclosure Certificate requires any individual or entity bidding to disclose campaign contributions, as defined in Section 9-1.4 of the Election Code (10 ILCS 5/9-1.4), made to current members of the Village Council within the five (5) year period preceding the date of the bid or proposal release.

By signing the bid documents, contractor/proposer/bidder/vendor agrees to refrain from making any campaign contributions as defined in Section 9-1.4 of the Election Code (10 ILCS 5/9-1.4) to any Village Council member and any challengers seeking to serve as a member of the Downers Grove Village Council.

Under penalty of perjury, I declare:

Bidder/vendor has not contributed to any elected Village position within the last five wears. ME ANTONIO PENDINA

Signature

Bidder/vendor has contributed a campaign contribution to a current member of the Village Council within the last five (5) years.

Print the following information: Name of Contributor: _____

(company or individual)

To whom contribution was made: _____

Year contribution made: _____ Amount: \$ _____

Signature

Print Name

2012-2016 Capital Project Sheet


Project Description

Storm Sewer Replacement, Annual Element

Project summary, justification and alignment to Strategic Plan

This project accounts for future annual replacement of existing storm sewers, which have reached the end of their useful life. As individual projects are identified, project sheets are created and the amounts herein are reduced accordingly.

| Cost Summary | | | | | | | | | | Future | |
|--|------|------|---------|---------|----------|---------|---------------|-----------------|--------------|--------|-----------|
| Cost Summary | Nen | Main | | FY 2012 | FY 201 | 3 | FY 2014 | FY 2015 | FY 2016 | Years | TOTAL |
| Professional Services | | | | | | | | | | | - |
| Land Acquisition | | | | | | | | | | | - |
| Infrastructure | | | Х | 500,000 | 500,0 | 000 | 500,000 | 1,000,000 | 1,500,000 | | 4,000,000 |
| Building | | | | | | | | | | | - |
| Machinery/Equipment | | | | | | | | | | | - |
| Other/Miscellaneous | | | | | | | | | | | - |
| TOTAL COST | | | | 500,000 | 500,0 | 000 | 500,000 | 1,000,000 | 1,500,000 | - | 4,000,000 |
| Funding Source(s) | | | | | | | | | | | |
| 243-Stormwater Fund | | ▼ | | 500,000 | 500,0 | 000 | 500,000 | 1,000,000 | 1,500,000 | | 4,000,000 |
| | | ▼ | | | | | | | | | - |
| | | ▼ | | | | | | | | | - |
| | | ▼ | | | | | | | | | - |
| TOTAL FUNDING SOURCES | | | | 500,000 | 500,0 | 000 | 500,000 | 1,000,000 | 1,500,000 | - | 4,000,000 |
| Project status and completed | work | ¢ | | | Grants (| fund | ed or applied | for) related to | the project. | | |
| On-going Program. | | | | | | | None. | | | | |
| Impact-annual operating expenses | | | FY 2012 | FY 201 | 3 | FY 2014 | FY 2015 | FY 2016 | Future Yrs | TOTAL | |
| Projected Operating Expense Impact: | | | | | | | | | | - | |
| Impact on the operating budget will be determined after the project is designed. | | | | | | | | | | | |





| Priority Score | А | | Pro | oject Manager: | Andy Sikich |
|----------------|---|----------|-----|----------------|--------------|
| | | Program: | 347 | Department: | Public Works |

| and the second |
|--|
| |
| |
| Village of |
| I DOWNEDQ 🖬 🕴 |
| DOWNERS |
| |
| GROVE |
| FOUNDED IN 1832 |
| LAL BLA BALL |
| () |
| |

Village of Downers Grove Consultant Evaluation

| Contractor:Swallow Construction |
|--|
| Project: Rogers Street Water Main |
| Primary Contact: Anthony Rendina Phone: 630-512-9900 |
| Time Period: _ <u>June 2009 - May 2009</u> |
| On Schedule (allowing for uncontrollable circumstances) 🛛 🖂 yes 🗌 no |
| Provide details if early or late completion: |
| Change Orders (attach information if needed): <u>Contractor had many additional items</u> to be paid. After work was completed had additional items he wanted to be paid for that in the Village's opinion were not warranted. Difficulties / Positives: <u>Contractor at times hard to work with</u> . Started project on the wrong street and had to repair street. Damage to sanitary sewer system when installing water services. At the time of review the contractor has still not repaired sanitary sewer. |
| Interaction with public: |
| 🗌 excellent 🔲 good 🖂 average 🖂 poor |
| (Attach information on any complaints or compliments) |
| General Level of Satisfaction with work: |
| □ Well Satisfied □ Satisfied ⊠ Not Satisfied |
| Should the Village contract with this vendor in the future? \Box Yes $oxtimes$ No |
| Reviewers: <u>Scott A Vasko</u> |
| Date: <u>12/21/09</u> |

Village of DOWNERS GROVE FOUNDED IN 1832

Village of Downers Grove Contractor Evaluation

Contractor: H. Linden and Sons Sewer and Water, Inc.

Project: Pershing Ave Storm Sewer Improvements - SW-064

Primary Contact: Steve Linden Phone: 630-553-6591

Time Period: <u>August 2011 – October 2011</u>

On Schedule (allowing for uncontrollable circumstances) \Box yes \boxtimes no

Provide details if early or late completion: <u>Storm sewer improvements were completed</u> on time. Restoration was completed roughly one week past the completion date.

Change Orders (attach information if needed): N/A

| Difficulties / Positives: | Crew was very respectful of residents' needs, maintained site |
|---------------------------|--|
| cleanliness and dust co | ontrol very well; performed quality work and was very responsive |
| to Engineer. | |

Interaction with public:

| | \square | excellent | | good | | average | | poor |
|--|-----------|-----------|--|------|--|---------|--|------|
|--|-----------|-----------|--|------|--|---------|--|------|

(Attach information on any complaints or compliments)

General Level of Satisfaction with work:

| Well Satisfied | \square | Satisfied | Not Satisfied |
|----------------|-----------|-----------|---------------|
|----------------|-----------|-----------|---------------|

| Should the Village contract | with this vendor in the | 🛿 future? 🖂 Yes 🗌 No |
|-----------------------------|-------------------------|----------------------|
|-----------------------------|-------------------------|----------------------|

Reviewers: Jim Tock

Date: <u>11/22/11</u>