

VILLAGE OF DOWNERS GROVE
Report for the Village Council Meeting
5/10/2016

| | |
|---|--|
| SUBJECT: | SUBMITTED BY: |
| Lacey Road Reconstruction – ST-052/SW-070 | Nan Newlon Director of Public Works |

SYNOPSIS

A motion is requested to award a contract for the Lacey Road Reconstruction to Chicagoland Paving Contractors, Inc. of Lake Zurich, Illinois in the amount of \$549,900.00.

STRATEGIC PLAN ALIGNMENT

The strategic goals for 2015-2017 identified *Top Quality Infrastructure*.

FISCAL IMPACT

The FY16 budget includes \$550,000 for this project (\$400,000 in the Capital Projects Fund for roadway improvements and \$150,000 in the Stormwater Fund for storm sewer improvements).

RECOMMENDATION

Approval on the May 17, 2016 consent agenda.

BACKGROUND

The scope of the project includes the replacement of asphalt pavement, sidewalk repair, installation of new ribbon curb to facilitate drainage, and storm sewer replacements and improvements within the right of way of Lacey Road, between Ogden Avenue and Virginia Street. A call for bids (CFB) was issued and published in accordance with the Village's Purchasing Policy. Six bids were received on April 20, 2016. A synopsis of the bids is as follows:

| Contractor | Total Bid |
|-----------------------------|------------------|
| Chicagoland Paving | \$549,900.00 |
| A Lamp Concrete Contractors | \$595,869.00 |
| Alliance Contractors | \$655,711.05 |
| Geneva Construction | \$730,740.79 |
| G&M Cement | \$754,363.20 |
| Swallow Construction | \$808,033.95 |

Staff recommends award of the contract to Chicagoland Paving Contractors, Inc. Chicagoland has successfully completed projects for the Village of Downers Grove, such as the 2014 Patching Program and

the 2014 Parking Lot Reconstruction projects. Chicagoland Paving has also satisfactorily completed various projects for other local municipalities, including road replacement for the communities of Buffalo Grove, Libertyville, Fox Lake and Barrington.

ATTACHMENTS

Contract Document

Contractor Evaluations



CALL FOR BIDS – FIXED WORKS PROJECT

- I. Name of Company Bidding: _____ **Chicagoland Paving Contractors Inc.**
225 Telser Road
Lake Zurich, IL 60047
- II. Instructions and Specifications:
- A. Bid No.: ST-052/SW-070
 - B. For: LACEY ROAD RECONSTRUCTION
 - C. Bid Opening Date/Time: WEDNESDAY, APRIL 20, 2016 @ 10:00AM
 - D. Pre-Bid Conference Date/Time: NONE
 - E. Pre-Bid Conference Location: NONE
 - F. CONTRACT DOCUMENTS FOR PICKUP AT THE PUBLIC WORKS BUILDING, 5101 WALNUT AVE, DOWNERS GROVE, IL 60515
- III. Required of All Bidders:
- A. Bid Deposit: 5%
 - B. Letter of Capability of Acquiring Performance Bond: YES
- IV. Required of Awarded Contractor(s)
- A. Performance Bond or Letter of Credit: YES
 - B. Certificate of Insurance: YES

Legal Advertisement Published: WEDNESDAY, APRIL 6, 2016

This document comprises 69 pages

RETURN ORIGINAL BID IN SEALED ENVELOPE MARKED WITH THE BID NUMBER AS NOTED ABOVE TO:

DANIEL J. KMIECIK, PE
 STAFF ENGINEER II
 VILLAGE OF DOWNERS GROVE
 5101 WALNUT AVENUE
 DOWNERS GROVE, IL 60515
 PHONE: 630/434-6875
 FAX: 630/434-5495
www.downers.us

16-198
 BID DATE 4-20-16
 BID TIME 10:00
 WITH PRINTS LG SM NO
 COMPLETE DATE/DAYS:
540

dar
CO

Village of Downers Grove

CALL FOR BIDS – FIXED WORKS PROJECT**Bid No.:** ST-052/SW-070

The VILLAGE OF DOWNERS GROVE will receive bids Monday thru Friday, 8:00 A.M. to 5:00 P.M. at the Public Works Building, 5101 Walnut Avenue, Downers Grove, IL 60515.

The Village Council reserves the right to accept or reject any and all bids, to waive technicalities and to accept or reject any item of any Bid.

The documents constituting component parts of this contract are the following:

- I. CALL FOR BIDS
- II. TERMS & CONDITIONS
- III. GENERAL PROVISIONS
- IV. SPECIAL PROVISIONS
- V. BID & CONTRACT FORM

All Bidders MUST submit the entire bid package, with one original Bid Form. Upon formal Award, the successful Bid will automatically convert to a Contract, and the successful Bidder will receive a copy of the executed contract upon formal award of the Bid with the Notice of Award.

DO NOT DETACH ANY PORTION OF THIS DOCUMENT. INVALIDATION COULD RESULT.

Village of Downers Grove

I. CALL FOR BIDS and INSTRUCTIONS TO BIDDERS**1. GENERAL**

- 1.1 Notice is hereby given that Village of Downers Grove will receive sealed bids up to:
WEDNESDAY, APRIL 20, 2016 @ 10:00AM.
- 1.2 Defined Terms:
 - 1.2.1 Village – the Village of Downers Grove acting through its officers or agents.
 - 1.2.2 Contract Documents – this document plus any drawings issued therewith, any addenda and the Bidder's completed proposal, bonds and all required certifications.
 - 1.2.3 Bid – this document completed by an individual or entity and submitted to the Village.
 - 1.2.4 Bidder – the individual or entity who submits or intends to submit a bid proposal to the Village.
 - 1.2.5 Contractor – the individual or entity whose bid is selected by the Village and who enters into a contract with the Village.
 - 1.2.6 Work – the construction or service defined herein.
 - 1.2.7 Day – unless otherwise stated all references to day "Day" "Days", "day" or "days" shall refer to calendar days.
 - 1.2.8 Proposal Guaranty – the required bid deposit.
- 1.3 Bids must be received at the Village by the time and date specified. Bids received after the specified time and date will not be accepted and will be returned unopened to the Bidder.
- 1.4 Bids shall be sent to the Village of Downers Grove, ATTN: Daniel J. Kmiecik, PE, in a sealed envelope marked "SEALED BID". The envelope shall be marked with the name of the project, date, and time set for receipt of Bids. The bid package may be submitted any time prior to the time set for receipt of Bids.
- 1.5 All Bids must be submitted on the forms supplied by the Village and signed by a proper official of the company submitting Bid. Telephone, e-mail and fax Bids will not be accepted.
- 1.6 Under penalty of perjury, the Bidder certifies by submitting this Bid that he has not acted in collusion with any other Bidder or potential Bidder.

2. BID PREPARATION

- 2.1 It is the responsibility of the Bidder to carefully examine the Contract Documents and to be familiar with all of the requirements, stipulations, provisions, and conditions surrounding the proposed Work.

Village of Downers Grove

- 2.2 The Bidder shall inspect the site of the proposed Work in detail, investigate and become familiar with all the local conditions affecting the Work and become fully acquainted with the detailed requirements of the Work. Submitting a Bid shall be a conclusive assurance and warranty that the Bidder has made these examinations and that the Bidder understands all requirements for the performance of the Work. If the Bid is accepted, the Bidder will be responsible for all errors in the Bid resulting from his willing or neglectful failure to comply with these instructions. IN NO CASE WILL THE VILLAGE BE RESPONSIBLE FOR ANY COSTS, EXPENSES, LOSSES OR CHANGES IN ANTICIPATED MARGINS OF PROFIT RESULTING FROM THE WILLING OR NEGLECTFUL FAILURE OF THE BIDDER TO MAKE THESE EXAMINATIONS. THE VILLAGE WILL NOT BE RESPONSIBLE FOR ANY COSTS, EXPENSES, LOSSES OR CHANGES IN ANTICIPATED MARGINS OF PROFIT RESULTING FROM THE WILLING OR NEGLECTFUL FAILURE OF THE CONTRACTOR TO PROVIDE THE KNOWLEDGE, EXPERIENCE AND ABILITY TO PERFORM THE WORK REQUIRED BY THIS CONTRACT. No changes in the prices, quantities or contract provisions shall be made to accommodate the inadequacies of the Bidder, which might be discovered subsequent to award of contract. The Bidder shall take no advantage of any error or omission in the Contract Documents nor shall any error or omission in the Contract Documents serve as the basis for an adjustment of the amounts paid to the Bidder.
- 2.3 When the Contract Documents include information pertaining to subsurface explorations, borings, test pits, and other preliminary investigations, such information is included solely for the convenience of the Bidder. *The Village assumes no responsibility whatsoever with respect to the sufficiency of the information, and does not warrant, neither expressly nor by implication, that the conditions indicated represent those existing throughout the Work, or that unanticipated developments may not occur.*
- 2.4 Any information shown in the Contract Documents regarding the locations of underground utility facilities is included solely for the convenience of the Bidder. The Village assumes no responsibility whatsoever with respect to the sufficiency, accuracy or inadequacy of such information. It shall be the Bidder's responsibility to obtain detailed information from the respective utility companies relating to the location of their facilities and the work schedules of the utility companies for removing or adjusting them. Utilities whose facilities may be affected by the work include, but may not be limited to, the following: Nicor, ComEd, SBC, Comcast Cable, Downers Grove Sanitary District, and Village water, storm sewer, and street lighting systems.
- 2.5 No oral or telephone interpretations of specifications shall be binding upon the Village. All requests for interpretations or clarifications shall be made in writing and received by the Village at least five (5) business days prior to the date set for receipt of Bids or the pre-bid conference, if offered. The Village shall make all changes or interpretations of the Contract Documents in a written addendum and shall provide an addendum to any Bidder of record. Any and all changes to the Contract Documents are valid only if they are included by written addendum to all Bidders. Each Bidder must acknowledge receipt of any addenda by indicating same on the Bid Form. Each Bidder, by acknowledging receipt of any addenda, is responsible for the contents of the addenda and any changes to the Bid therein. Failure to acknowledge any addenda may cause the Bid to be rejected. The Village will not assume responsibility for receipt of any addenda. In all cases, it will be the Bidder's responsibility to obtain all addenda issued. Bidders will provide written acknowledgement of receipt of each addendum issued with the bid submission.

Village of Downers Grove

- 2.6 An estimate of the quantities of Work to be performed and the materials to be furnished is shown in the Bid Form. It is given as a basis for comparing the properly submitted Bids, and shall be used by the Village in awarding the Contract. The Village does not expressly warrant nor imply that the estimated quantities shown will correspond with those quantities required to perform the Work. No Bidder shall plead misunderstanding or deception because of such an estimate of quantities, or because of the character, location or other conditions pertaining to the Work. Payment shall be based on the actual quantities of work properly performed in accordance with the Contract, at the Contract unit prices specified. The Village reserves the right to increase, decrease or omit entirely, any or all items. No allowance will be made for any change in anticipated profits due to an increase or decrease in the original estimate of quantities.
- 2.7 The Bidder must submit his bid on the form furnished by the Village. The Bid shall be executed properly, and bids shall be made for all items indicated in the Bid Form. The Bidder shall indicate, in figures, a unit price or lump sum price for each of the separate items called for in the Bid Form. The Bidder shall show the products of the respective quantities and unit prices in the column provided for that purpose. The gross sum shown in the place indicated in the Bid Form shall be the summation of said products. All writing shall be with ink or typewriter, except the signature of the Bidder, which shall be written with ink.
- 2.8 In case of error in the extension of prices in the Bid, the hourly rate or unit price will govern. In case of discrepancy in the price between the written and numerical amounts, the written amount will govern.
- 2.9 All costs incurred in the preparation, submission, and/or presentation of any Bid including the Bidder's travel or personal expenses shall be the sole responsibility of the Bidder and will not be reimbursed by the Village.
- 2.10 The Bidder hereby affirms and states that the prices quoted herein constitute the total cost to the Village for all work involved in the respective items, as well as the materials to be furnished in accordance with the collective requirements of the Contract Documents. The Bidder also affirms that this cost includes all insurance, royalties, transportation charges, use of all tools and equipment, superintendence, overhead expense, profits and other work, services and conditions necessarily involved in the work to be done.
- 2.11 The Bidder shall complete and submit with the Bid an "Affidavit" (IDOT Form BC-57, or similar) listing all uncompleted contracts, including subcontract work; all pending low bids not yet awarded or rejected, and equipment available.
- 2.12 The Bidder shall complete and submit with the Bid a "Municipal Reference List" indicating other municipalities for which the Bidder has successfully performed similar work.
- 3. PRE-BID CONFERENCE**
- 3.1 A pre-bid conference may be offered to provide additional information, inspection or review of current facilities or equipment, and to provide an open forum for questions from Bidders. This pre-bid conference is not mandatory (unless stated "Mandatory" on the cover of this document), but attendance by Bidders is strongly advised as this will be the last opportunity to ask questions concerning the Bid.

Village of Downers Grove

3.2 Questions may be posed in writing to the Village (faxed and emailed questions are acceptable), but must be received by the Village prior to the scheduled time for the pre-bid conference. Questions received will be considered at the conference. An addendum may be issued as a result of the pre-bid conference. Such an addendum is subject to the provisions for issuance of an addendum as set forth in Section 2.5 above.

3.3 No Contract Documents will be issued after the pre-bid conference except to attendees.

4. BID SUBMISSION

4.1 An original copy of the sealed bid marked as indicated in Section 1 shall be submitted to the Village.

4.2 A bid deposit will be required, which shall not exceed ten percent (10%) of the estimated cost of the work to be furnished. Such bid deposit shall be in the form of a bid bond, certified check, cash or money order. Checks shall be drawn upon a bank of good standing payable to the order of the Village and said deposit shall be forfeited to the Village in the event the Bidder neglects or refuses to enter into a contract and bond when required, with approved sureties, to execute the Work or furnish the material for the price mentioned in his Bid and according to the plans and specifications in case the contract shall be awarded to him.

4.3 Bids shall be publicly opened at the hour and place indicated above.

5. BID MODIFICATION OR WITHDRAWAL

5.1 A Bid that is in the possession of the Village may be altered by a letter bearing the signature or name of the person authorized for submitting a Bid, provided that it is received prior to the time and date set for the bid opening. Telephone, email or verbal alterations of a Bid will not be accepted.

5.2 A Bid that is in the possession of the Village may be withdrawn by the Bidder, up to the time set for the bid opening, by a letter bearing the signature or name of the person authorized for submitting Bids. Bids may not be withdrawn after the bid opening and shall remain valid for a period of ninety (90) days from the date set for the bid opening, unless otherwise specified.

5.3 Any Bidder who does not submit a Bid is requested to return the enclosed Statement of "No Bid" postcard. Bidders not submitting Bids or "No Bid Statement" may otherwise be removed from the Village's bid mailing list.

6. BID REJECTION

6.1 Bids that contain omissions, erasures, alterations, additions not called for, conditional bids or alternate bids not called for, or irregularities of any kind, shall be rejected as informal or insufficient. Bids otherwise acceptable, which are not accompanied by the proper Proposal Guaranty, shall also be rejected as informal or insufficient. The Village reserves the right however, to reject any or all Bids and to waive such technical error as may be deemed best for the interest of the Village.

Village of Downers Grove

7. BIDDER COMPETENCY

- 7.1 No Bid will be accepted from or contract awarded to any person, firm or corporation that is in arrears or is in default upon any debt or contract. The Bidder, if requested, must present evidence to the Village of ability and possession of necessary facilities, and financial resources to comply with the terms of the Contract Documents. Evidence must be presented within three (3) business days.

8. BIDDER DISQUALIFICATION

- 8.1 Any one or more of the following causes may be considered as sufficient for the disqualification of a Bidder and the rejection of their Bid.

8.1.1 More than one Bid for the same Work from an individual, firm partnership, or corporation under the same or different names.

8.1.2 Evidence of collusion among Bidders.

8.1.3 Unbalanced Bids in which the prices for some items are substantially out of proportion to the prices for other items.

8.1.4 Failure to submit a unit price for each item of Work listed in the Bid Form.

8.1.5 Lack of competency as revealed by financial statement or experience questionnaire.

8.1.6 Unsatisfactory performance record as shown by past work, judged from the standpoint of workmanship and progress.

8.1.7 Uncompleted work which, in the judgment of the Village, might hinder or prevent the prompt completion of this Work.

8.1.8 Failure to submit a signed Bidder's Certificate stating the following:

8.1.8.1 That the Bidder is not barred from bidding on this Contract as a result of a violation of Sections 720 ILCS 5/33-E3 and 720 ILCS 5/33-E4 of the Illinois Compiled Statutes; and

8.1.8.2 The Bidder is not delinquent in the payment of any tax administered by the Illinois Department of Revenue; and

8.1.8.3 The Bidder will maintain the types and levels of insurance required by the terms of this contract; and

8.1.8.4 The Bidder will comply with the Illinois Prevailing Wage Act, 820 ILCS 130/1 *et seq.*

9. BASIS OF AWARD

- 9.1 The Village reserves the exclusive right to accept or reject any and all Bids or to waive sections, technicalities and irregularities, or to accept or reject any Bid or any item of any Bid.

Village of Downers Grove

10. AWARD OF CONTRACT

- 10.1 Unless the Village exercises its right to reject all Bids, the Contract will be awarded to that responsible Bidder whose Bid, conforming to the Contract Documents, will be most advantageous to the Village, price and other factors considered. (the credentials, financial information, bonding capacity, insurance protection, qualifications of the labor and management of the firm, past experience and ability to complete the project within time frame required - lowest responsible bidder)
- 10.2 Unless otherwise specified, if a Contract is not awarded within ninety (90) days after the opening of Bids, a Bidder may file a written request with the Village for the withdrawal of their Bid. The Village will have a maximum of ten (10) days after the receipt of such request to award the Contract or release the Bidder from further obligation by return of the Bidder's bid deposit. Any attempt or actual withdrawal or cancellation of a Bid by the awarded contractor who has been notified by the Village of the acceptance of said Bid shall be considered a breach of contract.

11. RETURN OF BID DEPOSIT

- 11.1 The bid deposit of all except the three (3) lowest responsive bidders on each contract will be returned within fifteen (15) days after the opening of Bids. The remaining bid deposits of each contractor will be returned within fifteen (15) days after the Village Council has awarded the contract and the required appurtenances to the contract have been received.

12. FAILURE TO ENTER INTO CONTRACT

- 12.1 Failure on the part of the successful Bidder to execute a Contract and provide acceptable bonds, as provided herein, within ten (10) days from the date of receipt of the Contract and Notice of Award from the Village, will be considered as just cause for the revocation of the award. The Bidder's bid security shall then be forfeited to the Village, not as a penalty but in payment of liquidated damages sustained as a result of such failure.
- 12.2 The Bidder shall not be allowed to claim lack of receipt where the Contract and Notice of Award was mailed by U.S. Postal Services certified mail to the business address listed in his Bid. In case the Village does not receive evidence of receipt within ten (10) days of the date of Notice of Award, the Village may revoke the award. The Bidder shall then forfeit the bid security to the Village, not as a penalty but in payment of liquidated damages sustained as the result of such failure to execute the Contract.
- 12.3 By submitting a Bid, the Bidder understands and agrees that, if his Bid is accepted, and he fails to enter into a contract forthwith, he shall be liable to the Village for any damages the Village may thereby suffer.

13. SECURITY FOR PERFORMANCE

- 13.1 The successful Bidder shall, within ten (10) days after acceptance of the Bidder's Bid by the Village, furnish a Performance Bond and a Materials and Labor Payment Bond acceptable to the Village in the full amount of the Bid. Said bonds shall guarantee the Bidder's performance under the Contract Documents and shall guarantee payment of all subcontractors and material suppliers. Any bond shall include a provision as will guarantee faithful performance of the Illinois Prevailing Wage Act, 820 ILCS 130/1 et seq.

Village of Downers Grove

14. TAX EXEMPTION

- 14.1 The Village is exempt from Illinois sales or use tax for direct purchases of materials and supplies. A copy of the Illinois Sales Tax Exemption Form will be issued upon request. The Village's federal identification number will also be provided to the selected Bidder.

15. RESERVED RIGHTS

- 15.1 The Village reserves the right to waive sections, irregularities, technicalities and informalities to this Contract and to accept any Bid and to reject any and all Bids and to disapprove of any and all subcontractors as may be in the best interest of the Village. Time and date requirements for receipt of Bids, however, will not be waived.

16. CATALOGS AND SHOP DRAWINGS

- 16.1 Each Bidder shall submit catalogs, descriptive literature, and detailed drawings, where applicable, to fully illustrate and describe the work or material he proposes to furnish.

17. TRADE NAMES AND SUBSTITUTIONS

- 17.1 Certain materials and equipment are specified by a manufacturer or trade name to establish standards or quality and performance and not for the purpose of limiting competition. Products of other manufacturers may be substituted, if, in the opinion of the Village, they are equal to those specified in quality, performance, design, and suitability for intended use. If the Bidder proposes to furnish an "equal", the proposed "equal" item must be so indicated in the written Bid. Where two or more items are specified, the selection among those specified is the Bidder's option, or he may submit his Bid on all such items. Detail specification sheets shall be provided by Bidder for all substituted items.

Village of Downers Grove

II. TERMS AND CONDITIONS**18. VILLAGE ORDINANCES**

18.1 The successful bidder, now the Contractor, will strictly comply with all ordinances of the Village of Downers Grove and laws of the State of Illinois.

19. USE OF VILLAGE'S NAME

19.1 The Contractor is specifically denied the right of using in any form or medium the name of the Village for public advertising unless the Village grants express permission.

20. HOURS OF WORK

20.1 The Contractor shall do no work between the hours of 7:00 p.m. and 7:00 a.m., nor on Saturdays, Sundays or legal holidays, unless otherwise approved in writing by the Village. However, such work may be performed at any time if necessary, for the proper care and protection of work already performed, or in case of an emergency. All after-hour work is still subject to the permission of the Village. Any work, including the starting and/or idling of vehicles or machinery, or a congregation of workers prior to starting work, which may cause any noise level that can be heard by adjacent residents, performed outside of these hours of work and not authorized by the Village shall be subject to a fine of \$250 per day, per violation.

21. PERMITS AND LICENSES

21.1 The Contractor shall obtain all necessary permits and licenses required to complete the Work. The cost of acquisition of all necessary permits, bonds, insurance and services as specified herein shall be considered INCLUDED IN THE TOTAL COST, and no additional compensation will be allowed the Contractor.

22. INSPECTION

22.1 The Village shall have a right to inspect, by its authorized representative, any material, components or workmanship as herein specified. Materials, components or workmanship that have been rejected by the Village as not in accordance with the terms of the contract specifications shall be replaced by the Contractor at no cost to the Village.

23. DELIVERIES

23.1 All materials shipped to the Village must be shipped F.O.B. designated location, Downers Grove, Illinois.

24. SPECIAL HANDLING

24.1 Prior to delivery of any product that is caustic, corrosive, flammable or dangerous to handle, the Contractor will provide written directions as to methods of handling such products, as well as the antidote or neutralizing material required for its first aid before delivery. Contractor shall also notify the Village and provide material safety data sheets for all substances used in connection with this Contract which are defined as toxic under the Illinois Toxic Substances Disclosure to Employees Act.

25. NONDISCRIMINATION

25.1 Contractor shall, as a party to a public contract:

25.1.1 Refrain from unlawful discrimination in employment and undertake affirmative action to

Village of Downers Grove

assure equality of employment opportunity and eliminate the effects of past discrimination;

25.1.2 By submission of this Bid, the Contractor certifies that he is an "equal opportunity employer" as defined by Section 2000(e) of Chapter 21, Title 42, U.S. Code Annotated and Executive Orders #11246 and #11375, which are incorporated herein by reference. The Equal Opportunity clause, Section 6.1 of the Rules and Regulations of the Department of Human Rights of the State of Illinois, is a material part of any contract awarded on the basis of this Bid.

25.2 It is unlawful to discriminate on the basis of race, color, sex, national origin, ancestry, age, marital status, physical or mental handicap or unfavorable discharge for military service. Contractor shall comply with standards set forth in Title VII of the Civil Rights Act of 1964, 42 U.S.C. Secs. 2000 et seq., The Human Rights Act of the State of Illinois, 775 ILCS 5/1-101 et. seq, and The Americans With Disabilities Act, 42 U.S.C. Secs. 12101 et. seq.

26. SEXUAL HARASSMENT POLICY

26.1 The bidder, as a party to a public contract, shall have a written sexual harassment policy that:

26.1.1 Notes the illegality of sexual harassment;

26.1.2 Sets forth the State law definition of sexual harassment;

26.1.3 Describes sexual harassment utilizing examples;

26.1.4 Describes the bidder's internal complaint process including penalties;

26.1.5 Describes the legal recourse, investigative and complaint process available through the Illinois Department of Human Rights and the Human Rights Commission and how to contact these entities; and

26.1.6 Describes the protection against retaliation afforded under the Illinois Human Rights Act.

27. EQUAL EMPLOYMENT OPPORTUNITY

27.1 In the event of the Contractor's non-compliance with the provisions of this Equal Employment Opportunity Clause, the Illinois Human Rights Act or the Rules and Regulations of the Illinois Department of Human Rights ("Department"), the Contractor may be declared ineligible for future contracts or subcontracts with the State of Illinois or any of its political subdivisions or municipal corporations, and the contract may be canceled or voided in whole or in part, and such other sanctions or penalties may be imposed or remedies invoked as provided by statute or regulation. During the performance of this contract, the Contractor agrees as follows:

27.1.1 That it will not discriminate against any employee or applicant for employment because of race, color, religion, sex, marital status, national origin or ancestry, age, physical or mental disability unrelated to ability, military status, order of protection status, sexual orientation, sexual identity, or an unfavorable discharge from military service; and further that it will examine all job classifications to determine if minority persons or women are underutilized and will take appropriate affirmative action to rectify any such underutilization.

Village of Downers Grove

- 27.1.2 That, if it hires additional employees in order to perform this Contract or any portion thereof, it will determine the availability (in accordance with the Department's Rules and Regulations) of minorities and women in the area(s) from which it may reasonably recruit and it will hire for each job classification for which employees are hired in such a way that minorities and women are not underutilized.
- 27.1.3 That, in all solicitations or advertisements for employees placed by it or on its behalf, it will state that all applicants will be afforded equal opportunity without discrimination because of race, color, religion, sex, marital status, national origin or ancestry, age, physical or mental disability unrelated to ability, military status, order of protection status, sexual orientation, or an unfavorable discharge from military services.
- 27.1.4 That it will send to each labor organization or representative of workers with which it has or is bound by a collective bargaining or other agreement or understanding, a notice advising such labor organization or representative of the Contractor's obligations under the Illinois Human Rights Act and the Department's Rules and Regulations. If any such labor organization or representative fails or refuses to cooperate with the Contractor in its efforts to comply with such Act and Rules and Regulations, the Contractor will promptly so notify the Department and the contracting agency and will recruit employees from other sources when necessary to fulfill its obligations thereunder.
- 27.1.5 That it will submit reports as required by the Department's Rules and Regulations, furnish all relevant information as may from time to time be requested by the Department or the contracting agency, and in all respects comply with the Illinois Human Rights Act and the Department's Rules and Regulations.
- 27.1.6 That it will permit access to all relevant books, records, accounts and work sites by personnel of the contracting agency and the Department for purpose of investigation to ascertain compliance with the Illinois Human Rights Act and the Department's Rules and Regulations.
- 27.1.7 That it will include verbatim or by reference the provisions of this clause in every subcontract it awards under which any portion of the contract obligations are undertaken or assumed, so that such provisions will be binding upon such subcontractor. In the same manner as with other provisions of this Contract, the Contractor will be liable for compliance with applicable provisions of this clause by such subcontractors; and further it will promptly notify the contracting agency and the Department in the event any subcontractor fails or refuses to comply therewith. In addition, the Contractor will not utilize any subcontractor declared by the Illinois Human Rights Commission to be ineligible for contracts or subcontracts with the State of Illinois or any of its political subdivision or municipal corporations.

28. DRUG FREE WORK PLACE

28.1 Bidder, as a party to a public contract, certifies and agrees that it will provide a drug free workplace by:

28.1.1 Publishing a statement:

- (1) Notifying employees that the unlawful manufacture, distribution, dispensation, possession

Village of Downers Grove

or use of a controlled substance, including cannabis, is prohibited in the Village's or Contractor's workplace.

(2) Specifying the actions that will be taken against employees for violations of such prohibition.

(3) Notifying the employee that, as a condition of employment on such contract or grant, the employee will:

(A) abide by the terms of the statement; and

(B) notify the employer of any criminal drug statute conviction for a violation occurring in the workplace no later than five (5) days after such conviction.

28.1.2 Establishing a drug free awareness program to inform employee's about:

(1) the dangers of drug abuse in the workplace;

(2) the Village's or Contractor's policy of maintaining a drug free workplace;

(3) any available drug counseling, rehabilitation and employee assistance programs;

(4) the penalties that may be imposed upon employees for drug violations.

28.1.3 Providing a copy of the statement required by subparagraph 11.1 to each employee engaged in the performance of the contract or grant and to post the statement in a prominent place in the workplace.

28.1.4 Notifying the contracting or granting agency within ten (10) days after receiving notice under part (3)(B) of paragraph 11.1 above from an employee or otherwise receiving actual notice of such conviction.

28.1.5 Imposing a sanction on, or requiring the satisfactory participation in a drug abuse assistance or rehabilitation program by any employee who is so convicted as required by section 5 of the Drug Free Workplace Act.

28.1.6 Assisting employees in selecting a course of action in the event drug counseling, treatment and rehabilitation is required and indicating that a trained referral team is in place.

28.1.7 Making a good faith effort to continue to maintain a drug free workplace through implementation of the Drug Free Workplace Act.

29. SUBSTANCE ABUSE PREVENTION ON PUBLIC WORKS PROJECTS ACT

29.1 In the event this is a public works project as defined under the Prevailing Wage Act, 820 ILCS 130/2, Contractor agrees to comply with the Substance Abuse Prevention on Public Works Projects Act, 820 ILCS 265/1 *et seq.*, and further agrees that all of its subcontractors shall comply with such Act. As required by the Act, Contractor agrees that it will file with the Village prior to commencing work its written substance abuse prevention program and/or that of its subcontractor(s) which meet or exceed the requirements of the Act.

30. PREVAILING WAGE ACT

30.1 Contractor agrees to comply with the Illinois Prevailing Wage Act, 820 ILCS 130/1 *et seq.*, for all work completed under this Contract. Contractor agrees to pay the prevailing wage and require that all of its subcontractors pay prevailing wage to any laborers, workers or mechanics who perform work pursuant to this Contract or related subcontract. For applicable rates, go to the State of Illinois – Department of Labor website (www.state.il.us/agency/idol/rates/rates.HTM) and use the

Village of Downers Grove

most current DuPage County rate. The Department revises the prevailing wage rates and the Contractor or subcontractor has an obligation to check the Department's website for revisions to prevailing wage rates throughout the duration of this Contract.

- 30.2 Contractor and each subcontractor shall keep or cause to be kept accurate records of all laborers, mechanics and other workers employed by them on the public works project, which records must include each worker's name, address, telephone number when available, social security number, classification, hourly wage paid (including itemized hourly cash and fringe benefits paid in each pay period), number of hours worked each day, and the starting and ending times of work each day. These records shall be open to inspection at all reasonable hours by any representative of the Village or the Illinois Department of Labor and must be preserved for five (5) years from the date of the last payment on the public work.
- 30.3 Since this is a contract for a public works project, as defined in 820 ILCS 130/2, Contractor agrees to post at the job site in an easily accessible place, the prevailing wages for each craft or type of worker or mechanic needed to execute the contract or work to be performed.
- 30.4 Because this is a public works project as defined under the Prevailing Wage Act, 820 ILCS 130/2, any and all contractors and subcontractors shall submit certified payroll records to the Village no later than the tenth (10th) day of each calendar month for the immediately preceding month in which construction on a public works project has occurred. **WITHOUT THIS PAPERWORK, NO INVOICE SHALL BE PAID BY THE VILLAGE.** Contractors and subcontractors must also submit a statement affirming that the records are true and accurate, that the wages paid to each worker are not less than the prevailing rate, and that the contractor and subcontractor are aware that filing false records is a Class A misdemeanor. The records must include the name, address, telephone number, social security number, job classification, hours of work, hourly rate, and start and end time of work each day for every worker employed on the public work. The Village reserves the right to check the pay stubs of the workers on the job. The Village further cautions that payment for any services rendered pursuant to this Contract may be predicated upon receipt of said records.
- 30.5 In the event that this is a construction project where Motor Fuel tax monies or state grant monies are used in the construction, maintenance and extension of municipal streets, traffic control signals, street lighting systems, storm sewers, pedestrian subways or overhead crossings, sidewalks and off-street parking facilities, and the like, the Village will require an Apprenticeship and Training Certification, attached after the Bidder's Certification.
- 30.6 Any bond furnished as security for performance shall include a provision as will guarantee faithful performance of the Illinois Prevailing Wage Act, 820 ILCS 130/1 et seq.

31. PATRIOT ACT COMPLIANCE

- 31.1 The Contractor represents and warrants to the Village that neither it nor any of its principals, shareholders, members, partners, or affiliates, as applicable, is a person or entity named as a Specially Designated National and Blocked Person (as defined in Presidential Executive Order 13224) and that it is not acting, directly or indirectly, for or on behalf of a Specially Designated National and Blocked Person. The Contractor further represents and warrants to the Village that the it and its principals, shareholders, members, partners, or affiliates, as applicable are not, directly or indirectly, engaged in, and are not facilitating, the transactions contemplated by this Contract on behalf of any person or entity named as a Specially Designated National and Blocked Person. The

Village of Downers Grove

Contractor hereby agrees to defend, indemnify and hold harmless the Village, and its elected or appointed officers, employees, agents, representatives, engineers and attorneys, from and against any and all claims, damages, losses, risks, liabilities and expenses (including reasonable attorney's fees and costs) arising from or related to any breach of the foregoing representations and warranties.

32. INSURANCE REQUIREMENTS

32.1 Prior to starting the Work, Contractor and any Subcontractors shall procure, maintain and pay for such insurance as will protect against claims for bodily injury or death, or for damage to property, including loss of use, which may arise out of operations by the Contractor or Subcontractor or any Sub-Sub Contractor or by anyone employed by any of them, or by anyone for whose acts any of them may be liable. Such insurance shall not be less than the greater of coverages and limits of liability specified below or any coverages and limits of liability specified in the Contract Documents or coverages and limits required by law unless otherwise agreed to by the Village.

| | | |
|---------------------------------|--------------|--|
| Workers Compensation | \$500,000 | Statutory |
| Employers Liability | \$1,000,000 | Each Accident |
| | \$1,000,000 | Disease Policy Limit |
| | \$1,000,000 | Disease Each Employee |
| Comprehensive General Liability | \$2,000,000 | Each Occurrence |
| | \$2,000,000 | Aggregate |
| | | <i>(Applicable on a Per Project Basis)</i> |
| Commercial Automobile Liability | \$1,000,000 | Each Accident |
| Professional Errors & Omissions | \$2,000,000 | Each Claim |
| (pursuant to section.9 below) | \$2,000,000 | Annual Aggregate |
| Umbrella Liability | \$ 5,000,000 | |

32.2 Comprehensive General Liability Insurance required under this paragraph shall be written on an occurrence form and shall include coverage for Products/Completed Operations, Personal Injury with Employment Exclusion (if any) deleted, Blanket XCU and Blanket Contractual Liability insurance applicable to defense and indemnity obligations and other contractual indemnity assumed under the Contract Documents. The limit must be on a "Per Project Basis".

32.3 Commercial Automobile Liability Insurance required under this paragraph shall include coverage for all owned, hired and non-owned automobiles.

32.4 Workers Compensation coverage shall include a waiver of subrogation against the Village.

32.5 Comprehensive General Liability, Employers Liability and Commercial Automobile Liability Insurance may be arranged under single policies for full minimum limits required, or by a

Village of Downers Grove

combination of underlying policies with the balance provided by Umbrella and/or Excess Liability policies.

- 32.6 Contractor and all Subcontractors shall have their respective Comprehensive General Liability (including products/completed operations coverage), Employers Liability, Commercial Automobile Liability, and Umbrella/Excess Liability policies endorsed to add the "Village of Downers, its officers, officials, employees and volunteers" as "additional insureds" with respect to liability arising out of operations performed; claims for bodily injury or death brought against the Village by any Contractor or Subcontractor employees, or the employees of Subcontractor's subcontractors of any tier, however caused, related to the performance of operations under the Contract Documents. Such insurance afforded to the Village shall be endorsed to provide that the insurance provided under each policy shall be *Primary and Non-Contributory*.
- 32.7 Contractor and all Subcontractors shall maintain in effect all insurance coverages required by the Contract Documents at their sole expense and with insurance carriers licensed to do business in the State of Illinois and having a current A. M. Best rating of no less than A- VIII. In the event that the Contractor or any Subcontractor fails to procure or maintain any insurance required by the Contract Documents, the Village may, at its option, purchase such coverage and deduct the cost thereof from any monies due to the Contractor or Subcontractor, or withhold funds in an amount sufficient to protect the Village, or terminate this Contract pursuant to its terms.
- 32.8 All insurance policies shall contain a provision that coverages and limits afforded hereunder shall not be canceled, materially changed, non-renewed or restrictive modifications added, without thirty (30) days prior written notice to the Village. Renewal certificates shall be provided to the Village not less than five (5) days prior to the expiration date of any of the required policies. All Certificates of Insurance shall be in a form acceptable to the Village and shall provide satisfactory evidence of compliance with all insurance requirements. The Village shall not be obligated to review such certificates or other evidence of insurance, or to advise Contractor or Subcontractor of any deficiencies in such documents, and receipt thereof shall not relieve the Contractor or Subcontractor from, nor be deemed a waiver of the right to enforce the terms of the obligations hereunder. The Village shall have the right to examine any policy required and evidenced on the Certificate of Insurance.
- 32.9 If the Work under the Contract Documents includes design, consultation, or any other professional services, Contractor or the Subcontractor shall procure, maintain, and pay for Professional Errors and Omissions insurance with limits of not less than \$2,000,000 per claim and \$2,000,000 annual aggregate. If such insurance is written on a claim made basis, the retrospective date shall be prior to the start of the Work under the Contract Documents. Contractor and all Subcontractors agree to maintain such coverage for three (3) years after final acceptance of the Project by the Village or such longer period as the Contract Documents may require. Renewal policies during this period shall maintain the same retroactive date.
- 32.10 Any deductibles or self-insured retentions shall be the sole responsibility of the Insured. At the option of the Village, either: the insurer shall reduce or eliminate such deductibles or self-insured retentions as respects the Village, its officers, officials, employees and volunteers; or the Contractor shall procure a bond guaranteeing payment of losses and related investigations, claim administration and defense expenses.

Village of Downers Grove

33. INDEMNITY AND HOLD HARMLESS AGREEMENT

33.1 To the fullest extent permitted by law, the Contractor shall indemnify, keep and save harmless the Village and its agents, officers, and employees, against all injuries, deaths, strikes, losses, damages, claims, suits, liabilities, judgments, costs and expenses, which may arise directly or indirectly from any negligence or from the reckless or willful misconduct of the Contractor, its employees, or its subcontractors.

33.2 The Contractor shall at its own expense, appear, defend and pay all charges of attorneys and all costs and other expenses arising therefrom or incurred in connection therewith, and, if any judgment shall be rendered against the Village in any such action, the Contractor shall, at its own expense, satisfy and discharge the same. This agreement shall not be construed as requiring the Contractor to indemnify the Village for its own negligence. The Contractor shall indemnify, keep and save harmless the Village only where a loss was caused by the negligent, willful or reckless acts or omissions of the Contractor, its employees, or its subcontractors.

34. SUBLETTING OF CONTRACT

34.1 No contract awarded by the Village shall be assigned or any part subcontracted without the written consent of the Village. In no case shall such consent relieve the Contractor from his obligation or change the terms of this Contract.

All approved subcontracts shall contain language which incorporates the terms and conditions of this Contract.

35. TERMINATION OF CONTRACT

35.1 The Village reserves the right to terminate the whole or any part of this Contract, upon written notice to the Contractor, for any reason.

35.2 The Village further reserves the right to terminate the whole or any part of this Contract, upon written notice to the Contractor, in the event of default by the Contractor. Default is defined as failure of the Contractor to perform any of the provisions of this Contract or failure to make sufficient progress so as to endanger performance of this Contract in accordance with its terms. In the event that the Contractor fails to cure the default upon notice, and the Village declares default and termination, the Village may procure, upon such terms and in such manner as it may deem appropriate, supplies or services similar to those so terminated. The Village may also contact the issuer of the Performance Bond to complete the Work. The Contractor shall be liable for any excess costs for such similar supplies or services. Any such excess costs incurred by the Village may be set-off against any monies due and owing by the Village to the Contractor.

36. BILLING AND PAYMENT PROCEDURES

36.1 Payment will be made upon receipt of an invoice referencing Village purchase order number. Once an invoice and receipt of materials or service have been verified, the invoice will be processed for payment in accordance with the Village's payment schedule. The Village will comply with the Local Government Prompt Payment Act, 50 ILCS 505/1 et seq., in that any bill approved for payment must be paid or the payment issued to the Contractor within 60 days of receipt of a proper bill or invoice. If payment is not issued to the Contractor within this 60 day period, an interest penalty of 1.0% of any amount approved and unpaid shall be added for each month or fraction thereof after the end of this 60 day period, until final payment is made.

Village of Downers Grove

36.2 The Village shall review each bill or invoice in a timely manner after its receipt. If the Village determines that the bill or invoice contains a defect making it unable to process the payment request, the Village shall notify the Contractor as soon as possible after discovering the defect pursuant to rules promulgated under 50 ILCS 505/1 et seq. The notice shall identify the defect and any additional information necessary to correct it.

36.3 As this Contract is for work defined as a "fixed public work" project under the Illinois Prevailing Wage Act, 820 ILCS 130/2, any contractor or subcontractor is required to submit certified payroll records along with the invoice. No invoice shall be paid without said records.

36.4 Please send all invoices to the attention of: Village of Downers Grove, Accounts Payable, 801 Burlington, Downers Grove, IL 60515.

37. COMPLIANCE WITH OSHA STANDARDS

37.1 Equipment supplied to the Village must comply with all requirements and standards as specified by the Occupational Safety and Health Act. All guards and protectors as well as appropriate markings will be in place before delivery. Items not meeting any OSHA specifications will be refused.

38. CERCLA INDEMNIFICATION

38.1 The Contractor shall, to the maximum extent permitted by law, indemnify, defend, and hold harmless the Village, its officers, employees, agents, and attorneys from and against any and all liability, including without limitation, costs of response, removal, remediation, investigation, property damage, personal injury, damage to natural resources, health assessments, health settlements, attorneys' fees, and other related transaction costs arising under the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) of 1980, 42 U.S.C.A. Sec. 9601, et seq., as amended, and all other applicable statutes, regulations, ordinances, and under common law for any release or threatened release of the waste material collected by the Contractor, both before and after its disposal.

38.2 If the Contractor encounters any waste material governed by the above Act, it shall immediately notify the Village and stop working in the area until the above requirements can be met.

39. COPYRIGHT or PATENT INFRINGEMENT

39.1 The Contractor agrees to indemnify, defend, and hold harmless the Village against any suit, claim, or proceeding brought against the Village for alleged use of any equipment, systems, or services provided by the Contractor that constitutes a misuse of any proprietary or trade secret information or an infringement of any patent or copyright.

40. BUY AMERICA

40.1 The Contractor agrees to comply with 49 U.S.C.5323(j), the Federal Transportation Administration's (FTA) Buy America regulations at 49 C.F.R. Part 661, and any amendments thereto, and any implementing guidance issued by the FTA, with respect to this Contract, when financed by Federal funds (through a grant agreement or cooperative agreement).

40.2 As a condition of responsiveness, the Contractor agrees to submit with its Bid submission, an executed Buy America Certificate, attached hereto.

Village of Downers Grove

41. CAMPAIGN DISCLOSURE

- 41.1 Any contractor, proposer, bidder or vendor who responds by submitting a bid or proposal to the Village of Downers Grove shall be required to submit with its bid submission, an executed Campaign Disclosure Certificate, attached hereto.
- 41.2 The Campaign Disclosure Certificate is required pursuant to the Village of Downers Grove Council Policy on Ethical Standards and is applicable to those campaign contributions made to any member of the Village Council.
- 41.3 Said Campaign Disclosure Certificate requires any individual or entity bidding to disclose campaign contributions, as defined in Section 9-1.4 of the Election Code (10 ILCS 5/9-1.4), made to current members of the Village Council within the five (5) year period preceding the date of the bid or proposal release.
- 41.4 By signing the bid documents, contractor/proposer/bidder/vendor agrees to refrain from making any campaign contributions as defined in Section 9-1.4 of the Election Code (10 ILCS 5/9-1.4) to any Village Council member and any challengers seeking to serve as a member of the Downers Grove Village Council.

42. GUARANTEE PERIOD

- 42.1 The Contractor shall guarantee all work and provide a maintenance bond for the full amount of the contract, covering a minimum period of one (1) year after approval and acceptance of the Work. The bond shall be in such form as the Village may prescribe, unless otherwise noted in the Specifications, and shall be submitted before receiving final payment. If longer guarantee periods are required, they will be noted in the Special Provisions for this project.

43. SUCCESSORS AND ASSIGNS

- 43.1 The terms of this Contract will be binding upon and inure to the benefit of the parties and their respective successors and assigns; provided, however, that neither party will assign this Contract in whole or in part without the prior written approval of the other. The Contractor will provide a list of key staff, titles, responsibilities, and contact information to include all expected subcontractors.

44. WAIVER OF BREACH OF CONTRACT

- 44.1 The waiver by one party of any breach of this Contract or the failure of one party to enforce at any time, or for any period of time, any of the provisions hereof will be limited to the particular instance and will not operate or be deemed to waive any future breaches of this Contract and will not be construed to be a waiver of any provision except for the particular instance.

45. CHANGE ORDERS

- 45.1 The contract price is a "not-to-exceed" cost. At any time additional work is necessary or requested, and the not-to-exceed price is increased thereby, all parties must agree to any change, addition or price increase in writing.
- 45.2 Change orders for public works projects which authorize an increase in the contract price that is 50% or more of the original contract price or that authorize or necessitate any increase in the price of a subcontract under the contract that is 50% or more of the original subcontract price must be resubmitted for bidding in the same manner by which the original contract was bid. (50 ILCS 525/1)

Village of Downers Grove

46. SEVERABILITY OF INVALID PROVISIONS

- 46.1 If any provisions of this Contract are held to contravene or be invalid under the laws of any state, country or jurisdiction, contravention will not invalidate the entire Contract, but it will be construed as if not containing the invalid provision and the rights or obligations of the parties will be construed and enforced accordingly.

47. GOVERNING LAW

- 47.1 This Contract will be governed by and construed in accordance with the laws of the State of Illinois. Venue is proper only in the County of DuPage for state cases or the Northern District of Illinois for federal cases.

48. NOTICE

- 48.1 Any notice will be in writing and will be deemed to be effectively served when deposited in the mail with sufficient first class postage affixed, and addressed to the party at the party's place of business. Notices shall be addressed to the Village as follows:

**Village Manager
Village of Downers Grove
801 Burlington Ave.
Downers Grove, IL 60515**

And to the Contractor as designated on the Contract Form.

49. AMENDMENT

- 49.1 This Contract will not be subject to amendment unless made in writing and signed by all parties.

50. COOPERATION WITH FOIA COMPLIANCE

- 50.1 Contractor acknowledges that the Freedom of Information Act may apply to public records in possession of the Contractor or a subcontractor. Contractor and all of its subcontractors shall cooperate with the Village in its efforts to comply with the Freedom of Information Act. 5 ILCS 140/1 et.seq.

51. EMPLOYMENT OF ILLINOIS WORKERS ON PUBLIC WORKS ACT

- 51.1 If the work contemplated by this Contract is funded or financed in whole or in part with State Funds or funds administered by the State, Contractor agrees to comply with the terms of the Employment of Illinois Workers on Public Works Act by employing at least 90% Illinois laborers on the project. 30 ILCS 570/1 et seq. Contractor agrees further to require compliance with this Act by all of its subcontractors.

Village of Downers Grove

III. GENERAL PROVISIONS**1. STANDARD SPECIFICATIONS**

- 1.1 The following standards shall govern the construction of the proposed improvements:
- 1.1.1 Standard Specifications for Water and Sewer Main Construction in Illinois, Seventh Edition, 2014 (the Water & Sewer Specs.); and
 - 1.1.2 Standard Specifications for Road and Bridge Construction as adopted by the Illinois Department of Transportation, January 1, 2012; along with Supplemental Specifications and Recurring Special Provisions (collectively the "SSRBC") as adopted by the Illinois Department of Transportation, January 1, 2015; and
 - 1.1.3 Water Distribution Specifications, Village of Downers Grove, Illinois, revised March, 2006; and
 - 1.1.4 Standard Detail Drawings, Village of Downers Grove, Illinois revised May, 2014.
- 1.2 These Contract Documents shall take precedence whenever there are conflicts in the wording or statements made by the above specifications and these Contract Documents.
- 1.3 Unless otherwise referenced herein, Division I of the Water and Sewer Specs and Section 102 and Articles 104.02, 104.03, 104.07, 107.02, 107.27, 107.35, 108.10, 108.11, and 108.12 of the Standard Specifications are hereby suspended.

2. COOPERATION OF CONTRACTOR

- 2.1 The Contractor will be supplied with a minimum of 2 sets of approved plans and contract assemblies including Special Provisions, one set of which the Contractor shall keep available on the work site at all times. The Contractor shall give the work site constant attention necessary to facilitate the progress thereof, and shall cooperate with the Village in every way possible.
- 2.2 The Contractor shall have on the work site at all times, as the Contractor's agent, a competent English-speaking representative capable of reading and thoroughly understanding the Contract Documents, and thoroughly experienced in the type of work being performed. The representative shall also be capable of receiving instruction from the Village, and shall have full authority to promptly respond to such instruction. He shall be capable of supplying such materials, equipment, tools, labor and incidentals as may be required. The Contractor shall not replace him without prior written notification to the Village.

3. LEGAL REGULATIONS AND RESPONSIBILITY TO THE PUBLIC

- 3.1 Section 107 of the SSRBC shall govern the Contractor's legal regulations and responsibility to the public, with the following additions:
- 3.1.1 PROJECT SAFETY. Add the following to Article 107.28:
 - 3.1.1.1 The Contractor shall conduct his work in such a manner as to provide an environment consistent with the safety, health and well being of those engaged in the completion of the work specified in this contract.

Village of Downers Grove

- 3.1.1.2 The Contractor shall comply with all State and Federal Safety Regulations as outlined in the latest revisions of the Federal Construction Safety Standards (Series 1926) and with applicable provisions regulations of the Occupation Safety and Health Administration and (OSHA) Standards of the Williams-Stelger Occupational Health Safety Act of 1970 (Revised). SPECIAL ATTENTION SHALL BE PAID TO COMPLIANCE WITH OSHA'S SUBPART P – EXCAVATIONS STANDARD.
- 3.1.1.3 The Contractor and Village shall each be responsible for their own respective agents and employees.
- 3.1.1.4 The Contractor shall, prior to performing any work, request information from the Village regarding any existing confined spaces owned by the Village that may be entered in the course of the work, and shall obtain all required confined space entry permits prior to entering any confined spaces. Contractor shall follow all current laws and regulations with regard to confined space entry. Contractor shall maintain and, upon request, provide full documentation of compliance with the appropriate confined space permits for each separate confined space entered on the project.
- 3.1.2 **BACKING PRECAUTIONS.** Pursuant to Sections 14-139(b) and 14-171.1 of the Downers Grove Municipal Code, any motor vehicle which has an obstructed view to the rear and is to be operated at any time in reverse gear on the public streets of the Village by the Contractor or any subcontractor shall either be equipped with a reverse signal alarm (backup alarm) audible above and distinguishable from the surrounding noise level, or shall provide an observer to signal that it is safe to back up.
- 3.1.3 **OVERWEIGHT, OVERWIDTH AND OVERHEIGHT PERMITS.** The Village has and supports an overweight truck enforcement program. Contractors are required to comply with weight requirements and safety requirements as established by Illinois Law or Village Ordinance, for vehicles, vehicle operators and specialty equipment. In some instances, specialty equipment for road repairs or construction projects requires the movement of overweight, overwidth, or overheight loads utilizing a Village roadway. Such movement will require obtaining a permit from the Village Police Department's Traffic Supervisor.
- 3.1.4 **BARRICADES AND WARNING SIGNS.** The Contractor shall provide the Village with a telephone number of a person or company who is available 24 hours per day, seven days per week, to erect additional barricades or signs. If the Village or his representative deems it necessary for the Public's safety to erect additional barricades or signs during normal working hours, the Contractor will furnish the necessary barricades or signs, and have them in place within 30 minutes. If, after normal working hours, the requested signs are not in place within three hours after the request is made, the Village reserves the right to have the barricades and signs erected. The cost of erecting the barricades and signs shall be deducted by the Village from any payments due the Contractor.

Village of Downers Grove

4. PROSECUTION AND PROGRESS

4.1 Section 108 of the SSRBC shall govern the prosecution and progress of the work, with the following additions:

4.1.1 The Contractor shall schedule his work such that all improvements shall be substantially complete by September 2, 2016. The completion date will remain binding throughout the duration of the Contract unless revised in writing by the Village.

4.1.2 The total duration of disturbance for work related to means of public egress through the project site or access to private property (e.g. removal and replacement of curb and gutters, sidewalks, driveway entrances, etc.) must not exceed ten (10) calendar days. The Contractor may use high-early strength concrete, meeting all specifications herein, **at his own expense** to help meet this requirement.

4.1.3 The Contractor shall also make special note of the following work schedule requirements:

4.1.3.1.1 After installation of HMA base course on Lacey Road, the contractor will have two weeks to grind butt joints, prep, and install surface course throughout the entire project.

4.1.3.1.2 Please take note of SP-36 on parkway restoration that states prior to sod installation the contractor shall backfill and grade all parkways and keep them weed free and protect against erosion.

4.1.4 Should the Contractor fail to complete the work on or before the specified completion dates set forth in Sections 4.1.1, 4.1.2 or within such extended time as may be allowed, the Contractor shall be liable for liquidated damages in accordance with the applicable sections of Article 108.09 of the SSRBC.

4.1.5 Prior to commencing construction, a meeting will be held with the Contractor and the Village. Any questions concerning procedures, general conditions, special provisions, plans or specific items related to the project shall be answered and clarified. No Pre-Construction meeting shall be scheduled until submittals, performance bonds, and certificates of insurance are delivered to, and approved by, the Village.

4.1.6 Weekly progress meetings may be required by the Village. If required, the Contractor shall have a capable person, such as a site superintendent or project manager, attend such meetings and be prepared to report on the prosecution of the Work according to the progress schedule. The Village reserves the right to require adjustments to scheduling of work.

5. MEASUREMENT AND PAYMENT

5.1 Section 109 of the SSRBC shall govern measurement and payment, with the following additions:

5.1.1 Modifies Article 109.07 - Partial payments will be made per Section 34 of Part II of this document (Billing and Payment Procedures.)

5.1.2 The Village will require that partial and final affidavits for all labor, materials and equipment used on the Project, be submitted with the partial and final payment requests. Such waivers

Village of Downers Grove

shall indicate that charges for all labor, materials and equipment used on the project have been paid. Partial waivers from suppliers and subcontractors may be submitted after the first payment to the Contractor, and before the subsequent payment to that which they apply. However, partial waivers from the Contractor must accompany the invoice of the payment to which it applies. All final waivers, from all suppliers and subcontractors MUST accompany the Contractor's invoice upon submittal for final payment. A sworn statement by the Contractor shall accompany full waivers. Such requirement for full waivers is solely for the benefit of the Village and shall not be construed to benefit any other person. Partial payment for work done shall in no way imply acceptance of the work to that date.

Village of Downers Grove

IV. SPECIAL PROVISIONS

The following Special Provisions shall modify, supercede, or supplement the Standard Specifications referred to in Section III - General Provisions.

Where any section, subsection, paragraph, or subparagraph of the Standard Specifications is *supplemented* by any of the following paragraphs, the provisions of such section, subsection, paragraph, or subparagraph shall remain in effect. The Special Provisions shall govern in addition to the particular Standard Specification so supplemented, and not in lieu thereof.

Where any section, subsection, paragraph, or subparagraph of the Standard Specifications is *amended, voided, or superseded* by any of the following paragraphs, any provision of such section, subsection, paragraph, or subparagraph standing unaffected, shall remain in effect. The Special Provisions shall govern in lieu of any particular provision of the Standard Specification so amended, voided, or superseded, and not in addition to the portion changed.

SP-1: SCOPE OF WORK

The Lacey Road Reconstruction Project shall generally consist of the following:

- Removal of exiting storm pipes, structures, culverts, and other collateral items
- Construction of approximately 360 linear feet of storm sewers and drainage structures ranging in diameter from 2' to 5'.
- Reconstruction of approximately 1,300 linear feet of HMA roadway in a residential subdivision with ribbon curb.
- All other collateral work such as driveway replacements, aggregate shoulder replacement, sidewalk and sodding.

SP-2: GENERAL CONSTRUCTION REQUIREMENTS

The following general requirements are intended to govern the overall priority for the performance of the work described in this contract. As general requirements, they are not intended to dictate to the Contractor the precise method by which these tasks shall be performed.

No more than three hundred linear feet (300 LF) of pavement may be open-cut and closed to use by the motoring public, and access to all individual drives within the current work zone must be restored at the end of each workday, unless a Village-approved phasing plan shows otherwise.

The contractor is to submit a phasing plan after award of contract to the Village for review. The contractor must leave driveways to commercial businesses accessible during working hours. The contractor will not be allowed to proceed to another phase without the approval of the Engineer. **The contractor will receive no additional compensation for constructing the project in phases.**

The awarded Contractor shall schedule his work such that **all improvements shall be installed by September 2, 2016.** Failure to complete the work on time will result in assessment of liquidated damages in accordance with the applicable sections of Article 108.09 of the Standard Specifications.

The Contractor shall maintain traffic flow on ALL STREETS during the day in accordance with the applicable special provision. Adequate signing and flagging is of particular importance for safe travel of all

Village of Downers Grove

residents.

SP-3: QUALIFICATIONS OF BIDDER

In addition to those requirements set forth in Section 10.1 above, in order to be considered a responsible bidder, the bidder must have particular expertise in having successfully constructed projects of a similar size and scope, specifically including commercial/residential neighborhood street and utility removal and reconstruction. The Bidder must submit the following information for itself and for each Sub-Contractor which is proposed for earthwork, paving or underground utility work:

a. Similar Project Experience

- i. Bidder must provide detailed information regarding past similar projects performed by the submitting firm within the past five (5) years.
- ii. Bidder must submit a list of references of previous projects identifying the location of the work, the dollar value of the work, the owner or agency responsible for the work, and the name and phone number of the contact person.
- iii. Bidder must submit the Certification of Qualifications form with the Bid.

- b. Proposed Project Team - identify a project manager and full-time onsite construction supervisor (can be the same person), with qualifications. The individuals proposed must be utilized for the duration of this project unless an alternate is approved in writing by the Village.

SP-4: PRECONSTRUCTION VIDEOTAPING

This work shall consist of furnishing all materials and labor required to perform a videotape survey of the construction limits, adjacent right-of-way, and adjacent structures bordering the work. This shall include, but not be limited to, existing buildings, garages, pavements, curb and gutter, sidewalks, fences, trees and landscaping. One (1) copy of the videotape shall be furnished to the Village in DVD format. Videotaping shall be performed by a reputable company meeting the approval of the Village, in the presence of a representative of the Village, and shall be performed prior to the commencement of construction. The videotape survey shall serve as a basis for establishing damage that has occurred as a result of construction operations.

Basis of Payment: This work will be paid for at the contract **LUMP SUM** price for **PRECONSTRUCTION VIDEOTAPING**, which price shall be payment in full for the work as specified herein.

SP-5: CONSTRUCTION STAKING AND RECORD DRAWINGS

Description: Section 5-7 of the Water and Sewer Specs shall be replaced in its entirety by the following:

The Contractor shall furnish and place all construction layout stakes for this project. Competent personnel with suitable equipment shall conduct this work, supervised by a licensed Illinois Land Surveyor. The Contractor shall be responsible for having the finished work conform substantially to the lines, grades, elevations and dimensions shown on the plans.

The Contractor shall provide adequate control points to construct the individual Project elements, and shall provide the Engineer with adequate control in close proximity to check the compliance of the elements constructed.

Village of Downers Grove

The Contractor shall record all field notes in standard survey field notebooks and those books shall become the property of the Village at the completion of the Project. All notes shall be neat, orderly and in an accepted format.

Prior to final payment and within 28 calendar days of substantial completion, as determined in section III.4.1.1, the Contractor shall provide the Village with record drawings showing the elevations of all constructed storm and sanitary sewer manholes, catch basins, inlets, clean-outs, and any other structures defined by the Engineer as part of the project, including all rim elevations, and invert elevations of all pipes. Rim elevation of all curb structures shall be taken at the flowline of the gutter. Significant changes to the design plans shall also be depicted. Red-lined plans or electronically-generated as-built plans are acceptable. Digital copies of as-built drawings must also be provided (PDF files or approved equal), along with one full-sized paper copy. All work related to generating the as-built drawings shall be supervised by a licensed Illinois Land Surveyor.

Basis of Payment: This work will be paid for at the contract **LUMP SUM** price for **CONSTRUCTION STAKING AND RECORD DRAWINGS**, which price shall be payment in full for the work as specified herein.

SP-6: TREE PROTECTION


Municipal Codes regarding trees, including tree protection requirements for public parkway trees, are located in Chapter 24 of the Downers Grove Municipal Code. Specifically, Municipal Codes 24-7 and 24-8 detail the public parkway tree protection sizes and fines for violations. The Village Forester shall approve all tree protection measures and any deviations. All tree protection measures and any deviations shall be noted in the contract specifications and on approved project plan sheets and permits using the guidelines listed below.

Tree protection shall include avoiding damage to the above ground tree branches and trunk, and the below ground root system and surrounding soil. Tree crowns and trunks shall not suffer any branch or bark loss. Roots shall be protected from compaction, storage of materials, severing, regrading of the parkway or excavation unless specifically noted on the project plan sheets.

The Critical Root Zone, or CRZ, is the area immediately surrounding a tree that must be protected from damage. In a municipal parkway setting with utilities and paved or concrete surfaces, the size of the CRZ has been adjusted to form a rectangle around the parkway tree trunk with minimum dimensions listed in the following table. The depth of the CRZ extends to 4 feet below the natural ground surface level.

| <u>Parkway</u> | <u>Width street to property</u> | <u>Length along street</u> | <u>Depth</u> |
|------------------------------|---------------------------------|----------------------------|--------------|
| <u>Tree diameter at 4.5'</u> | <u>(min. curb to sidewalk)</u> | <u>street(minimum)</u> | |
| 0 – 12.0 inches | 10.0 feet | 10 feet | 4 feet |
| 12.1 – 24.0 inches | 10.0 feet | 20 feet | 4 feet |
| 24.1 or more inches | 10.0 feet | 30 feet | 4 feet |

Village of Downers Grove



For projects that involve excavations of less than one (1) foot in depth in the parkway or street and are replacing structures in the same location, fencing of the public parkway trees shall not be required. Example projects include, but are not limited to, street pavement resurfacing, curb removal/replacement, driveway removal/replacement, or sidewalk removal/repairs or new sidewalk installations. Contractors shall be mindful of the CRZ dimensions and potential for fines if any parkway trees suffer any unauthorized damage as determined by the Village Forester.

For projects that involve excavations of one (1) foot or more in depth in the parkway or street or both, fencing of the public parkway trees shall be required. Example projects include, but are not limited to, watermain replacements with new roadway keystops and domestic service box installations, sanitary line replacements and new service connections, new or replacement natural gas services, new or replacement phone or fiber optic lines, or new or replacement storm sewers, or projects that widen roads which in turn decreases the parkway soil volume around public parkway trees.

Projects that require fencing (listed above) shall fence the public parkway trees with six (6) foot high chain link construction fence secured to metal posts driven in the ground which are spaced no further than ten (10) feet apart. The dimensions of the fence shall depend on the tree diameter size and shall follow the table listed for the CRZ above, or as large as practical dependent on driveways and other field conditions. The fenced rectangle shall have three (3) sides with the opening facing the adjacent residences for easy access for mowing or tree care. Under no circumstances shall any items be stored within the fence. All fencing shall be maintained daily in an upright good condition. The size and location of all fencing shall be shown on the project plan sheets.

To avoid damage to the CRZ, utilities must be augered underneath the public parkway trees. Excavation pits for augering equipment are to be outside the fenced area and are to be shown on the project plan sheets. Excavation pits for roadway keystops and domestic service boxes are to be as small as practical with excavation occurring in a direction away from the adjacent public parkway tree.

In cases when severing of roots within a portion of the CRZ may be unavoidable (ex. sidewalk installation, curb replacement, water or sanitary service replacement), subject to the approval of the Village Forester, sharp clean cuts shall be made on root ends to promote wound closure and root regeneration. Root pruning and excavation activities shall occur such that the smallest volume of soil and roots is disturbed, and the locations shall be shown on the project plan sheets.

Village of Downers Grove

In addition to fines and citations that may be assessed for violations of any Chapter 24 of the Municipal Code (such as not maintaining fencing around the CRZ or unauthorized removal of protected trees), the contractor may be subject to the following provisions:

- issuance of an invoice for the value or partial value of the tree lost due to damage to either the above ground or below ground portions of the parkway tree, or unauthorized tree removal.
- costs of repairs, such as pruning or cabling, or costs for removal of the damaged parkway tree along with the stump if the tree cannot remain in the right-of-way.
- fines of \$500 for the 1st offense; \$1,000 for the 2nd offense; \$2,500 for the 3rd and subsequent offenses.
- each day during which a violation continues shall be construed as a separate and distinct offense.

The value or partial value of the tree lost shall be determined by the Village Forester using the most current edition of the Guide for Plant Appraisal (prepared by the Council of Tree & Landscape Appraisers and the International Society of Arboriculture) and the most current edition of the Species Ratings & Appraisal Factors for Illinois (prepared by the Illinois Arborist Association). The total cost determined for the damage shall be deducted from the payments made to the Contractor for the project. Should the Village hire another Contractor or tree service to complete pruning work, these costs shall also be deducted from the payments made to the Contractor.

Basis of Payment: This work shall be paid for at the contract unit price per **FOOT** for **TREE PROTECTION**, which price shall be payment in full for the work as specified herein, except tree removal as defined by the standard specifications, which will be paid for separately.

SP-7: TREE ROOT PRUNING

Description: All trees, public or private, affected by new sidewalk installation within its root protection zone, shall be root pruned prior to any excavation taking place. Root pruning shall be performed in accordance with the Tree Protection Zone detail of the Plans, and shall be done only to the depth of the excavation necessary for installing the new sidewalk. Root pruning shall start and proceed uninterrupted for the length of travel through the root protection zone. Root pruning shall be made no more than 10 inches from the tree-side edge of the proposed sidewalk.

Approval by the Village Forester of the equipment to be used for root pruning, as well as the proposed path of the root pruning work, is required prior to the work being performed. The Engineer or his representative shall permit no excavation until written approval is obtained by the Contractor from the Village Forester. No materials or equipment may be stored or kept in the Tree Protection Zone. Tree damage, as determined by the Village Forester, shall be assessed to the Contractor using the most recent edition of the Guide for Plant Appraisal, published by the International Society of Arboriculture.

Basis of Payment: This work shall be paid for at the contract unit price per **FOOT** for **TREE ROOT PRUNING**, which price shall be payment in full for the work as specified herein and as measured in place.

Village of Downers Grove

SP-8: ACCESS AND WATER SHUT-OFF NOTIFICATION

If access to a driveway will be blocked, or water will be turned off, the Contractor shall give that resident or business proper written notification at least 24 hours in advance. The Contractor must provide them the opportunity to remove their cars from the drive or make other arrangements, and prepare for any shutdown of the water system. Samples of written notices shall be submitted to the Engineer for approval.

In addition, the Contractor shall be responsible for notifying the resident or business verbally on the morning of any driveway closure, to ensure awareness of the lack of access.

SP-9: TRAFFIC CONTROL, MAINTENANCE OF TRAFFIC, DETOURS

This item shall include the furnishing, installing, maintaining, relocating and removing of all traffic control devices and personnel used for the purpose of regulating, warning, or directing traffic during the construction of this project. All traffic control devices used on this project shall conform to the Standard Specifications for Traffic Control Devices and the Illinois Manual on Uniform Traffic Control Devices. No waiving of these requirements will be allowed without prior written approval of the Engineer.

The Contractor shall protect all workers engaged in the project, and shall provide for safe and convenient public travel by providing adequate traffic control under all circumstances. Such circumstances may include, but not be limited to work performed along the route under construction, road closures for construction operations of any type, or when any section of the road is opened to traffic prior to completion of all work. The Contractor shall ensure that the work zone in question is properly signed, barricaded and otherwise marked.

The Contractor will be responsible for the proper location, installation, and arrangement of all traffic control devices during the period of construction. All open excavations shall be protected by Type I barricades equipped with bi-directional flashing lights at each end of the excavation, as well as at 50-foot intervals between ends for excavations greater than 50 feet in length and weighted down by **two sandbags per each barricade**. All street closures shall be protected by Type III barricades equipped with bi-directional flashing lights and weighted down by **eight sandbags per each barricade**.

The Contractor shall plan his work so that there will be no open holes during non-working hours and that all barricades have been removed from the pavement during non-working hours.

In the event that one direction of travel must be closed, the Contractor has the option of setting up a detour route or using flaggers (minimum of two). The Engineer shall approve proper signing and barricading of the detour route and lane closures, and shall issue written authorization prior to closure.

The Contractor shall maintain his operations in a manner such that traffic flow shall not be substantially impeded during the construction of the proposed improvements. Where traffic must cross open trenches during a given work day, the Contractor shall provide steel plates at street intersections and driveways. Prior to the end of a given work day, the pavement surface shall be temporarily restored. No open excavation may be left overnight or on the weekend without the express written permission of the Engineer.

As the condition and location of the work changes, the Contractor shall maintain all traffic control devices and personnel engaged in traffic control, in a manner that will accommodate the changing particulars of the work at any given time. Advance warnings, detour and directional information and other controls or

Village of Downers Grove

directions necessary for safe passage of traffic around the work site shall be reviewed and changed, if necessary, to meet the needs of the situation. Signage erected, but not necessary or proper for the situation ahead shall be covered or taken down. Barricading and signage shall be monitored on a daily basis to ensure that it meets the requirements for work zone safety for the conditions of the particular work being performed.

The Contractor shall provide a name and phone number for a responsible party capable of providing emergency service, 24 hours per day, for the duration of the Project.

Basis of Payment: This work shall be paid for at the contract **LUMP SUM** price for **TRAFFIC CONTROL, MAINTENANCE OF TRAFFIC, DETOURS**, which price shall be payment in full for the installation and maintenance of proper traffic control to protect the work and the public for the duration of the Project.

SP-10: STREET SWEEPING

All roadway surfaces shall be kept free of dirt, mud, dust and debris of any kind throughout every phase of the Project. Dirt, mud, dust and debris of any kind shall be removed from the roadway surface to the satisfaction of the Engineer by any one or combination of the following: approved mechanical sweeping equipment, manual labor, or other approved techniques.

Whenever ordered by the Engineer, especially for locations subject to a particularly high volume of traffic, the Contractor shall mechanically sweep the work site.

Basis of Payment: This work will be paid for at the contract unit price per **HOURLY** for **STREET SWEEPING**, which price shall be payment in full for the work as specified herein.

SP-11: EROSION AND SEDIMENTATION CONTROL

Throughout each and every phase of the project, all downstream ditches and storm sewers shall be protected from the run-off of roadway surfaces, excavations, and other construction activities generating the movement of dirt, mud, dust and debris. This work shall consist of constructing temporary erosion and sedimentation control systems as shown on the plans or as directed by the Engineer. The work shall be placed by methods and with materials in accordance with Sections 280, 1080 and 1081 of the Standard Specifications, except as amended herein.

All downstream ditches shall be protected from erosion and sedimentation by the installation of silt fence or ditch checks; straw bales shall not be used. Piles of excavated material are not allowed to be stored onsite. Storm sewer inlet structures or manholes shall be protected by temporary placement of filter baskets, or solid lids, as authorized in the field by the Engineer.

Erosion and sedimentation control measures as indicated in the Erosion Control Plan, or as directed by the Engineer shall be installed on the project site prior to beginning any construction activities which will potentially create conditions subject to erosion. Erosion control devices shall be in place and approved by the Engineer as to proper placement and installation prior to beginning other work. Erosion control protection for Contractor equipment storage sites, plant sites, and other sites shall be installed by the Contractor and approved by the Engineer prior to beginning construction activities at each site. All erosion and sedimentation control items must reference and be in accordance with the SWPPP standards and documentation. All contractors will be required to sign a document acknowledging this procedure. Any specific work done by each Contractor must comply with any SWPPP regulations. If erosion control items are needed to be replaced or repaired due to

Village of Downers Grove

construction activities of each Contractor following the installation of initial erosion and sediment control items, these items shall be incidental to each Contractor's overall contract work.

Silt Fence Installation. Placement and maintenance of silt fence at areas designated by the Engineer. The work shall be placed by methods and materials in accordance with Sections 280 and 1080 of the Standard Specifications, except as amended herein.

Silt Fence Removal. Removal and disposal of silt fence immediately prior to final restoration work.

Inlet Filter Baskets. Installation, maintenance and removal (after final stabilization) of inlet filter baskets as depicted on the plans.

Ditch Check/Silt Dike. Installation and maintenance of ditch checks as depicted on the plans and as designated by the Engineer.

Ditch Check/Silt Dike Removal. Removal and disposal of ditch checks immediately prior to final restoration work.

Concrete Washout. This shall be INCIDENTAL to the project.

Basis of Payment: This work shall be paid for at the contract unit price per EACH for INLET FILTER BASKETS, per EACH for SILT DIKE, per EACH for SILT DIKE REMOVAL, per FOOT for SILT FENCE INSTALLATION, and per FOOT for SILT FENCE REMOVAL.

SP-12: STORM SEWER REMOVAL

This work shall consist of the removal of existing storm sewer as shown on the plans and in accordance with Section 551 of the Standard Specifications. The existing sewer may be salvaged by the Contractor for whatever use he sees fit, except not to be reused as permanent installation on this project. Trenches falling under or within 2' of proposed pavement or driveways shall be backfilled with TRENCH BACKFILL in accordance with section 208.

Basis of Payment: The cost for the removal, backfilling and disposal of the materials will be paid for at the contract unit price per FOOT for STORM SEWER REMOVAL of the size indicated.

SP-13: HMA DRIVEWAY REMOVAL

This work shall consist of the excavation, transportation and disposal of HMA Driveway Pavement sub-base and sub-grade material as required to meet the proposed lines and subgrades of the project in accordance with Section 440 of the Standard Specifications.

Method of Measurement: This work will not be measured for payment. Payment will be based on Contract Quantities. By submission of a bid, Contractor agrees on Contract Quantity.

Basis of Payment: This work shall be paid for at the contract unit price per SQUARE YARD for HMA DRIVEWAY REMOVAL.

Village of Downers Grove

SP-14: PCC DRIVEWAY REMOVAL

This work shall consist of the excavation, transportation and disposal of PCC Driveway Pavement sub-base and sub-grade material as required to meet the proposed lines and subgrades of the project in accordance with Section 440 of the Standard Specifications.

Method of Measurement: This work will not be measured for payment. Payment will be based on Contract Quantities. By submission of a bid, Contractor agrees on Contract Quantity.

Basis of Payment: This work shall be paid for at the contract unit price per **SQUARE YARD** for **PCC DRIVEWAY REMOVAL**.

SP-15 : EARTH EXCAVATION, SPECIAL

This work shall consist of the excavation, removal and disposal of all pavement, sub-base and subgrade materials as required to meet the lines and subgrades to the depth of all proposed items including but not limited to proposed roadways, curb and gutter, ditching, roadway shoulders, commercial driveway aprons, concrete sidewalks, and asphalt pathways in accordance with Section 202 of the Standard Specifications and as specified herein. Any other earthwork shown on the plans in the roadway or parkway but not specifically called out shall be INCIDENTAL. Piles of excavated material are not allowed to be stored onsite.

This item shall include all full depth straight joints that shall be sawn at the ends and all edges of portions to be removed.

Method of Measurement: This work will not be measured for payment. Payment will be based on Contract Quantities. By submission of a bid, Contractor agrees on Contract Quantity.

The removal and disposal of unsuitable materials (undercut) to allow POROUS GRANULAR EMBANKMENT SPECIAL to be installed below proposed sub-base granular as necessary and as directed by the Engineer will be paid for separately at the contract unit price per CUBIC YARD of REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL.

Basis of Payment: This work shall be paid for at the contract unit price per **CUBIC YARD** for **EXCAVATION, SPECIAL**, which shall include all labor, materials and equipment necessary to do the work.

SP-16: REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL

Subgrade preparation shall include the removal of unsuitable surface conditions including pavement materials, vegetation, high organic content topsoil, root matter and other deleterious conditions which may be encountered. The subgrade soils (including soils in the conduit trenches) shall be proof-rolled and the soils compacted to a minimum of 95% compaction based on the standard proctor, AASHTO T-99 or ASTM D-698, within 1.0 foot of the surface. Proof-rolling and compaction will not be paid for separately, but will be considered as an incidental expense.

When proof-rolling reveals unstable soil conditions, these soils shall be removed. Removal and disposal of all surplus, unstable and unsuitable materials and organic waste below the design sub-grade shall be performed in such a manner that public or private property will not be damaged or endangered. Removal and Disposal of Unsuitable Material shall conform to applicable portions of Section 202 of the IDOT

Village of Downers Grove

Standard Specifications. The quantity is provided for estimated purposes only, and adjustments to unit prices will not be allowed based on actual quantities.

Basis of Payment: This work shall be paid for at the contract unit price per **CUBIC YARD** for **REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL**, and shall include all labor, equipment and materials necessary to perform the work as specified.

SP-17: POROUS GRANULAR EMBANKMENT, SUB-GRADE

This work shall consist of placing and compacting porous granular material installed on geotextile fabric to the lines and grades shown on the plans or as directed by the Engineer in accordance with the applicable portions of Section 207 of the IDOT Standard Specifications. The material shall be used as a bridging layer over soft, unstable or loose soil areas and for placement under water.

The geotextile fabric shall be in accordance with the specifications contained in Article 1080.02 of the IDOT Standard Specifications. The PGE material shall conform to Article 1004.05 of the IDOT Standard Specifications except the gradation shall be as follows:

1. Crushed Stone, Crushed Blast Furnace Slag, and Crushed Concrete

| Sieve Size | Percent Passing |
|------------|-----------------|
| *6" | 97 ± 03 |
| *4" | 90 ± 10 |
| 2" | 45 ± 25 |
| #200 | 5 ± 5 |

2. Gravel, Crushed Gravel and Pit Run Gravel

| Sieve Size | Percent Passing |
|------------|-----------------|
| *6" | 97 ± 03 |
| *4" | 90 ± 10 |
| 2" | 45 ± 25 |
| #4 | 30 ± 20 |
| #200 | 5 ± 5 |

*For undercut greater than eighteen inches (18"), the percent passing the 6" sieve may be 90 ± 10, and the 4" sieve requirements eliminated.

The porous granular material shall be placed in one lift when the total thickness to be placed is 6" or less or as directed by the Engineer. Each lift of the porous granular material shall be rolled with a vibratory roller meeting the requirements of Article 1101.01 of the IDOT Standard Specifications to obtain the desired keying or interlock and compaction. The Engineer shall verify that adequate keying has been obtained.

A 3" nominal thickness top lift of capping aggregate having a gradation of CA-6 will be required when Sub-base Granular Material is not specified in the contract and Porous Granular Embankment, Sub-Grade will be

Village of Downers Grove

used under the pavement and shoulders. Capping aggregate will not be required when embankment meeting the requirements of Section 207 of the Standard Specifications or granular sub-base is placed on top of the porous granular material.

Unnecessary construction equipment for the completion of the replacement material will not be allowed on the undercut areas until compaction of the recommended thickness of the porous granular sub-grade.

Full-depth sub-grade undercut should occur at limits determined by the Engineer. A transition slope to the full depth of undercut shall be made outside of the undercut limits at a taper of 1 foot longitudinal per 1 inch depth below the proposed sub-grade or bottom of the proposed aggregate sub-grade when included in the contract.

This work shall be measured for payment in accordance with Article 207.04 of the IDOT Standard Specifications. When specified on the contract, the theoretical elevation of the bottom of the aggregate sub-grade shall be used to determine the upper limit of Porous Granular Embankment, Sub-Grade. The volume will be computed by method of average end areas.

Basis of Payment: This work will be paid for at the contract unit price per **CUBIC YARD** for **POROUS GRANULAR EMBANKMENT, SUB-GRADE**, which price shall include all equipment, labor and materials required to complete this work as specified, including capping aggregate.

PGE shall be used as field conditions warrant at the time of construction. No adjustment in unit price will be allowed for an increase or decrease in quantities from the estimated quantities.

SP-18: IEPA CLEAN CONSTRUCTION OR DEMOLITION DEBRIS

If construction activities will result in removal and disposal of excavation spoils, per Illinois Public Act 96-1416 and the Illinois Environmental Protection Agency, soil sampling and analysis, along with certification from a licensed professional engineer (PE) or licensed professional geologist (PG) that the soil is uncontaminated, will be required prior to clean construction and demolition debris (CCDD) facility acceptance. However, if the subject property has never been used for industrial or commercial purposes, and is not adjacent to Potentially Impacted Properties (PIP's), then the site owner or operator may certify that the soil is uncontaminated by use of IEPA form LPC-662.

To facilitate meeting the above requirements, the Village will supply a signed LPC-663 or LPC-662 form. Neither the LPC-663/662, nor the report shall be considered a guarantee that excavated material shall meet the requirements of Illinois Public Act 96-1416, and the Contractor shall be responsible for satisfactory removal and disposal of all material as specified herein. No additional environmental testing of the existing on-site material may be performed without prior written permission from the Engineer. In the event that Contractor performs any additional testing without the written permission of the Engineer, Contractor will be required to properly and legally dispose of all material from the project site, regardless of its suitability for disposal in a CCDD facility, at his own expense, without any additional payment for testing, hauling and disposal as specified below.

The Village anticipates that one or more of the following CCDD facilities will accept material from this project:

- Reliable Lyons CCDD, 4226 Lawndale Ave, Lyons, IL 60534
- Hanson Material Service, 125 N Independence Blvd Romeoville, IL 60446
- Bluff City Materials, 1245 Gifford Rd, Elgin, IL 60120
- Vulcan Materials, 5500 Joliet Rd, McCook, IL 60525
- Heartland Recycling Aurora CCDD, Mettel Rd, Aurora, IL 60505

Village of Downers Grove

Contractor shall consult with these facilities prior to submitting a bid for this project. Contractor shall base his bid on hauling all CCDD generated by this project to these facilities. No additional compensation will be allowed for hauling to any other facilities, for any reason, unless none of the above listed facilities will accept the material. If an alternate facility was approved by the Village prior to bid submittal, and that facility will no longer accept the material, the facilities listed above shall be used by the Contractor at no additional cost to the Village, unless none of the above facilities will accept the material. In the case where neither any of the above listed facilities, nor a pre-approved alternate facility, will accept the material, the Village and Contractor shall attempt to locate an alternate facility, unless the material is classified as unsuitable for disposal in a CCDD facility, in which case it shall be hauled to a landfill and paid for as specified below. Should the Contractor wish to haul material to an alternate facility, the name, location and contact information for the proposed facility shall be submitted to the Village for evaluation, a minimum of five (5) calendar days prior to submission of a bid. Any costs associated with additional sampling, analysis, and/or reporting to meet the acceptance requirements of the alternate facility shall be borne by the bidding Contractor and included within the Contractor's bid. By submitting a bid, Contractor agrees that at least one (1) of the above listed facilities, or an alternate facility approved by the Village in writing prior to the submission of the bid, will accept the material and shall be used for disposal of all CCDD from this project, unless otherwise determined to be non-hazardous special waste as specified below. In the event that the Contractor needs to alter the CCDD facility used for placement of excavated material, the Contractor shall notify the Engineer no later than three (3) days in advance of the planned alteration. In no event shall material be hauled to an alternate facility without the written permission of the Engineer.

Construction Requirements: The Contractor shall be responsible for satisfactory removal and disposal of all waste material, asphalt, concrete, stone, dirt, and debris generated or discovered in the course of the work. Removal and disposal of excavation items being disposed of at a clean construction and demolition debris (CCDD) facility shall meet the requirements of Public Act 96-1416. This work shall be incidental and shall not be paid for separately, with the exception of the **ADDITIONAL HAULING SURCHARGE, NON-HAZARDOUS SPECIAL WASTE** as specified below.

The temporary storing of excavated materials within the public right-of-way or project limits shall not be allowed unless approved by the Engineer. It shall be the Contractor's responsibility to find an approved dumpsite for debris and any excavated materials. The Village will not provide one.

The Contractor shall employ a licensed testing firm, as approved by Engineer, to screen each truck-load of material on-site, using a PID or FID field screen or other acceptable method. The PID shall be calibrated on a daily basis. The Contractor shall enter all truck-loads leaving the site into an on-site screening log including, but not limited to, project name, date, time, weather conditions, name of screener, hauling company, truck number, screening method, background PID reading, calibrated PID reading, truck/bucket PID reading, and description of materials screened. Each day prior to the first truck leaving the site, Engineer and Contractor's testing consultant shall agree on the allowable PID reading in accordance with the receiving CCDD facility procedures (typically 0.0 or daily background levels). The receiving CCDD facility may be consulted daily, or periodically, as needed to verify that the appropriate value is being used. If said screen indicates levels that will be unacceptable for disposal at the CCDD facility, the material shall be quarantined on-site for further evaluation. If material is rejected at the CCDD facility, it shall be returned to the project site and quarantined for further evaluation. No additional compensation shall be allowed for returning a rejected load back to the project site, or any other additional hauling, loading, unloading, etc, as may be required. Should it be determined by the Village or Village's agent that the material is not suitable for disposal in a CCDD facility, the Contractor shall be responsible for properly disposing of the material at

Village of Downers Grove

an acceptable landfill, and providing the Village with all of the proper paperwork to document the material disposal with the IEPA. This work shall be paid for as specified below. If a truck-load is rejected by a CCDD facility after leaving the project site, and said truck-load is not identified in the on-site screening log, the Contractor shall still be required to properly dispose of the material and provide the Village with the necessary documentation, but shall not be additionally compensated as specified below.

All additional work to satisfy these requirements shall be the responsibility of the Contractor. All costs associated with meeting these requirements shall be paid for as specified herein. These costs shall include but are not limited to all required testing, lab analysis, and certification by a licensed professional engineer (PE) or licensed professional geologist (PG), if required, in addition to the cost of additional hauling, dump fees, etc. Payment for this work shall be in addition to payment for EARTH EXCAVATION per the contract unit price. No adjustment to the contract unit price will be allowed due to changes to quantities based on actual field conditions.

Basis of Payment: This work shall be paid for at the contract unit price per **LOAD** for **ADDITIONAL HAULING SURCHARGE, NON-HAZARDOUS SPECIAL WASTE**, which price shall be payment in full for the work as specified herein.

SP-19: EXPLORATORY TRENCH, SPECIAL

This item shall consist of excavating an area for the purpose of locating existing utilities within the construction limits of the proposed improvement. This work shall be performed as directed by the Engineer.

A nominal quantity of exploratory excavation has been included in the schedule of prices for the purpose of establishing a unit price for this item of work.

After the excavation has been inspected, it shall be backfilled as directed by the Engineer. If it is located in a paved area (existing or proposed), the excavation shall be backfilled with Trench Backfill as specified herein.

Otherwise, the excavation shall be backfilled with excavated material compacted to the satisfaction of the Engineer. Any excess material shall be disposed of in accordance with Article 202.03 of the IDOT Standard Specifications.

Trench Backfill will not be measured for payment.

This work will be paid for at the contract unit price per **EACH** for **EXPLORATORY TRENCH, SPECIAL**, measured as specified, which price shall include excavation, backfill and legal disposal of excess material.

SP-20: MAILBOX RELOCATION

The item shall include the removal and the reinstallation of all curbside mailboxes within the work area, regardless of type and size.

Construction Requirements. All work shall be in accordance with Post Office standards and requirements. Before demolition begins the contractor will be required to coordinate the installation and location of any temporary or new mailboxes with the Post Office and Engineer. No existing mailboxes shall be removed and demolition may not begin until the Post Office and Engineer have approved any temporary installation.

Once pavement is restored up to the top of binder course for that particular phase the original mailboxes shall be reinstalled at the proposed locations on the plans.

Village of Downers Grove

At the appropriate time, the Engineer will document the condition of the existing mailboxes and supports prior to removal by the Contractor. The Contractor shall exercise care not to damage the mailboxes during removal and re-installation. Any materials damaged by the Contractor shall be replaced to the satisfaction of the Engineer at no additional cost to the Village.

Every mailbox shall be re-installed with, at a minimum, a foundation approximately 12 inches in diameter and 18 inches deep consisting of a 3 inch gravel base below a rapid setting concrete mix. The concrete shall be manufactured by Sakrete. The mix shall be: Fast-Setting Ultra High Strength (product # 11050). An approved equal can be used; however it shall meet ASTM C 387. Finishing shall comply with ACI 302 and curing shall comply with ACI 308. In cases where standard installation will not suffice, the contractor shall submit proposed installation details to the Engineer for approval

The Contractor shall provide all materials, labor and equipment required to perform this work. The Engineer and the Post Office shall approve all materials. The Contractor will be required to coordinate all work with the Post Office and the Engineer in order to ensure no interruption of service.

Basis of Payment. This work shall be paid for at the contract unit price per **EACH** for **MAILBOX RELOCATION**. The Contractor shall temporarily install mailboxes as directed by the Engineer and per the proposed plans. Contractor will be compensated after the removal of the mailboxes, restoration and acceptance of the re-installed mailboxes.

SP-21: AGGREGATE SHOULDERS, TYPE B, 4"

Description: This item shall be done in accordance with Sec. 481 of the SSRBC and shall consist of the construction of approximate two (2) foot wide, four (4) inch deep shoulders or as directed by the Engineer in the area designated by the Engineer.

Unless otherwise directed by the Engineer, existing shoulders with elevations that are too high to accept the proposed aggregate shoulder shall be scraped or excavated as necessary prior to placement of new aggregate. This provision shall also apply to existing shoulders that contain too much vegetation or topsoil. Unnecessary damage or debris outside the designated shoulder area shall be removed and repaired and will not be paid for separately but shall be considered incidental to the cost of Aggregate Shoulders, Type B.

The contractor shall install the aggregate shoulders such that the surface of the shoulder shall be one eighth inch (1/8") below the line of the cross slope of the finished road surface as it extends through the shoulder. The contractor will be required to place a straight-edged tool on the finished surface of the road and extend it at least 2' beyond the edge of pavement to ensure the aggregate shoulder is not placed above the line created by the road cross-slope. Installation of the aggregate shoulder in this manner may require hand placement and compaction, of which all labor and material required shall be included in the unit price for this item.

Basis of Payment: This work will be paid for at the contract unit price per **SQUARE YARD** for **AGGREGATE SHOULDERS, TYPE B**, which price shall be payment in full for the work as specified herein.

SP-22: CONCRETE RIBBON CURB

Village of Downers Grove

This work shall consist of the placement of P.C.C. Ribbon or V-Curb, of the type, size and location shown on the plans. All P.C.C. Curbs shall be placed by methods and materials as specified in Articles 606 and 1020 of the SSRBC, except as amended herein.

Placement of P.C.C. Curb shall include the following:

- a) The use of Class SI Portland cement concrete, 6.05 cwt/cy mix, with 6% air entrainment, 3" slump;
- b) The saw cutting of 2 inch deep joints at not more than 15-foot intervals, within 24 hours after being placed;
- c) The placement of 2 dowel bars into the gutter portion of existing concrete curb, and at expansion joints, in accordance with the detail shown on the plans;
- d) The placement of 3/4 inch pre-molded expansion joint filler perpendicular to the centerline of the roadway for the full depth of the curb and gutter, where abutting existing concrete curb and gutter, at 10 feet either side of a utility structure, at construction joints at the ends of pours, at not more than 90 foot intervals;
- e) The proper curing of all concrete work utilizing the methods and materials outlined in Articles 424 and 1022.01 of the SSRBC (Type 2 membrane curing with red dye is preferred);
- f) The backfilling of all curb work with materials approved by the Engineer.

At locations shown on the plans or where directed by the Engineer the contractor will use High-early strength concrete. The desired concrete mix shall have a minimum compressive strength of 3,000 psi at 24 hours. Mix design shall be submitted to the Engineer for review and approval.

Basis for Payment: This work shall be paid for at the contract unit price per **FOOT** for **CONCRETE RIBBON CURB**, of the type specified, which price shall include all excavation, 4" aggregate base and for the work as specified herein.

SP-23: P.C.C. SIDEWALK, 5 INCH

This work shall consist of installation of new P.C.C. sidewalk as indicated by location or shown on the plans. All P.C.C. sidewalks shall be removed and replaced by methods and with materials in accordance with Articles 424 and 1020.04 of the SSRBC, except as amended herein.

Excavation for new sidewalk shall be performed with a Gradall. Operating a Gradall on the parkways will not be allowed. All excavation shall be made from the street unless otherwise approved by the Engineer. Excavation work utilizing a skid steer loader shall not be allowed.

Placement of sidewalk shall include the following:

- a) Any necessary excavation, clearing, and proper disposal of excavated materials, removal and disposal of all obstructions such as fences, walls, foundations and buildings;
- b) The placement and compaction of four inches (4") of Subbase Granular material, Type B, CA 6 with the methods and with materials in accordance with Section 311 and of Article 1004.04 of the SSRBC;
- c) The set up of form work such that the maximum running slope of the finished walk does not exceed 5 percent (1:20) or not to exceed the general grade established for the roadway, and the cross slope is not more than 2 percent (1:50).
- d) The placement of five inch (5") thick, Class SI Portland Cement Concrete, 5.65 cwt/cy mix, with 5-8% air entrainment, 2"-4" slump, and six inch (6") thickness through or in residential driveways

Village of Downers Grove

or where subject to vehicular traffic, to the width specified on the plans or as directed by the Engineer;

- e) The tooling of contraction joints, 3/4-inch radius and 1 inch deep, 5 feet on center;
- f) The placement of 1/2 inch thick premoulded expansion joints at 50 foot intervals on center, or abutting existing concrete sidewalk, or at the end of a pour;
- g) The adjustment to proper grade of all utility structures encountered;
- h) For sidewalks passing over newly constructed utility trenches, three equally spaced epoxy coated No. 4 reinforcing bars shall be centered over all utility trenches. Bars shall extend a minimum of 5 feet (1.5 m) beyond the walls of the utility trench. Reinforcement shall be incidental to the cost of the pay item.
- i) The replacement of all traffic control devices or parking meters removed;
- j) The proper curing of all concrete work utilizing methods and materials outlined in Articles 424 and 1022.01 of the SSRBC, (Type III membrane curing compound white pigmented);
- k) The complete restoration of abutting asphalt driveways damaged as a result of installation, or where new sidewalk surface is more than 1/2 inch higher or lower than the original grade of the asphalt drive. Restoration shall consist of a minimum of one foot either side of the sidewalk; with a minimum of three inch (3") thick Hot-Mix Asphalt Surface, Mixture C, N50 (IL 9.5) surface course; and restoration of gravel drives with similar HMA restoration.
- l) Installation of ADA compliant ramps for curbed and non-curbed streets.

Except for damaged parkway areas due to rutting or not designated by the Engineer, restoration will be paid for in accordance with the specification PARKWAY RESTORATION, SPECIAL.

When sidewalks are closed to pedestrians a minimum of two barricades (one on either side of the work zone) shall be used.

Basis for Payment: This work shall be paid for at the contract unit price per **SQUARE FOOT** for **P.C.C. SIDEWALK, 5-INCH**, which price shall be payment in full for the work as specified herein.

SP-24: DETECTABLE WARNINGS

This work shall consist of the installation of new detectable warning material as shown in the plans. All detectable warnings shall be placed by methods and with materials in accordance with Article 424 and 424.09 of the SSRBC.

Each Detectable Warning shall consist of brick red 2' x 5' panels inserted into wet concrete. Detectable Warning shall be Access-Tile Cast-In-Place Replaceable or approved equivalent.

Basis of Payment: This work shall be paid for at the contract unit price per **SQUARE FOOT** for **DETECTABLE WARNINGS**, which price shall include all material, labor, and equipment necessary to complete this item.

SP-25: AGGREGATE FOR TEMPORARY ACCESS

This work shall consist of construction and maintenance of an aggregate surface course for abutting properties as part of construction operations, per the applicable portions of Article 107.09 of the SSRBC except as amended herein.

Coarse aggregate shall meet the gradation for CA-6, and meet the requirements of Article 1004.04 of the SSRBC.

Village of Downers Grove

The temporary aggregate shall be used as ramping between the new aggregate base and all side streets, abutting properties, and crosswalks where vehicle and pedestrian traffic is to be maintained. Removal and disposal of the temporary aggregate shall be considered incidental to this item. The Engineer may require that some or all of the temporary aggregate be reused within the project limits.

When temporary access is no longer required, the aggregate placed for its construction and maintenance shall be removed and utilized in the permanent construction or otherwise disposed of as specified in Article 202.03 of the SSRBC. The Engineer reserves the right to determine suitability for utilization of reclaimed asphalt pavement used in the construction of temporary access in the permanent construction.

This work will be measured in place in tons. The contractor shall submit the load ticket to the Engineer at the work site when the truck arrives.

This work will be paid for at the contract unit price per **TON** for **AGGREGATE FOR TEMPORARY ACCESS**, which price shall include all costs of furnishing, placing, maintaining, removing and reusing, and removing and disposing of aggregate used in the construction of temporary access.

SP-26: DRIVEWAYS

This work shall consist of the installation of new HMA and PCC driveways at locations shown on the plans.

The driveways shall be constructed as shown in the details and as specified herein:

The subgrade shall be prepared at all locations, and the slopes adjacent to the driveways shall be shaped accordingly. The maximum grade for the side slopes shall not exceed 33 percent.

PCC Driveways: The base course shall consist of 6 inches of Type CA-6 aggregate base, measured after placement and compaction. The surface course shall consist of 6 inches of Class PV Portland Cement Concrete. The Driveway shall be placed by methods and materials outlined in Articles 423 and 1020.04 of the Standard Specifications.

All concrete work shall be properly cured utilizing the materials and methods outlined in Section 1022 of the Standard Specifications; except that Type II curing compound with red dye shall be used.

HMA Driveways: The asphalt shall be placed upon a minimum of 6 inches of Type CA-6 aggregate base course, and shall consist of 3 inches of compacted HMA Surface Course. The asphalt shall also be placed by methods and materials outlined in Articles 406 and 1009 of the Standard Specifications.

Basis of Payment: This work will be paid for at the unit price per **SQUARE YARD** for **P.C.C. DRIVEWAY PAVEMENT, SPECIAL**, of the thickness specified, **HOT-MIX ASPHALT DRIVEWAY PAVEMENT, SPECIAL**, which price shall be payment in full for the work as specified herein.

All POROUS GRANULAR EMBANKMENT required to establish driveway elevations and sizes will not be paid for separately but shall be included in the cost of the driveway replacement.

SP-27: STORM SEWER

Village of Downers Grove

Description: This item shall consist of the construction of Storm Sewer. Storm sewer shall be constructed with new Reinforced Concrete Pipe (RCP) per the SSRBC (AASHTO M315), and Ductile Iron Pipe with gasket (DIP), AWWA C -1 Class 52 with SuperCoat interior lining, asphalt exterior coating, and rubber-gasketed joints AWWA C - 111 of the diameter shown, or High Density Polyethylene (HDPE), or Polyvinyl Chloride (PVC) Pipe SDR 26 with gasketed, bell and spigot, push on type joints conforming to ASTM D3212 of the diameter shown on the Drawings.

The pipe shall be placed so that the entire length of the pipe will have full bearing. No blocking of any kind shall be used to adjust the pipe to grade except when used with concrete encasement.

Laying of sewer pipe shall be accomplished to line and grade in the trench only after it has been de-watered and the foundation and/or bedding has been prepared. Mud, silt, gravel, and other foreign material shall be kept out of the pipe and off the jointing surface.

All pipe laid shall be retained in position so as to maintain alignment and joint closure until sufficient backfill has been completed to adequately hold the pipe in place. All pipes shall be laid to conform to be prescribed line and grade shown on the Plans.

The sewer pipe, unless otherwise approved by the Engineer, shall be laid up grade from point of connection on the existing sewer or from a designated starting point. The sewer pipe shall be installed with the bell end forward or upgrade, unless approved otherwise. When pipe laying is not in progress, the forward end of the pipe shall be kept tightly closed with an approved temporary plug.

If deemed necessary by the Engineer, all pipe and manholes shall pass an ex-filtration test in accordance with ASTM C-969-02 prior to acceptance. All testing shall be done under supervision of the Engineer, who shall be notified 48 hours prior to testing.

The following specific items shall be considered incidental to storm sewer pipe construction and their costs shall be merged into the contract unit price per **FOOT** of the storm sewer pipe.

1. Removal of all surplus trench excavation from site.
2. Excavation for and placement of bedding material.
3. Support of trenches, including any necessary bracing or shoring.
4. De-watering of trench or excavation.
5. Placement and compaction of backfill by vibratory plate or other approved mechanical device.
6. Coring into existing drainage structures where connections are called for on the plans.
7. Sawcutting of pavement and/or curb and gutter.

Basis of Payment: This work shall be paid for at the contract unit price per **FOOT** for:

STORM SEWERS (CLASS, MATERIAL, SIZE SPECIFIED),

which price shall include all labor, material, and equipment and incidental work herein specified, except **TRENCH BACKFILL** used as Final Backfill as defined by the Standard Specifications, which will be paid for separately.

SP-28: MANHOLES, CATCH BASINS, AND INLETS (SIZE AND TYPE SPECIFIED)

Village of Downers Grove

This work shall consist of the installation of precast concrete drainage structures with a cast-in, clamp-on type flexible boot meeting ASTM C923 requirements, of the size and type shown on the plans or specified by the Engineer. Included in the contract unit price shall be all excavation, removal and disposal of existing storm structures, bedding, supplying and compacting of backfill materials. Backfill materials for new structures shall be CA-6 aggregate mechanically compacted. Unless otherwise specified, all manholes, catch basins, and inlets and shall be their respective Type A design with cast-in-place, clamp-on type, flexible rubber boot(s).

All structures in excess of four feet in depth shall be equipped with cast iron steps meeting the standards of ASTM A48.

Precast sections shall conform with ASTM C 478 and shall be substantially free from fractures, large or deep cracks and surface roughness. Slabs shall be sound and free from gravel pockets. Joints between precast sections shall be designed for rubber gaskets or bituminous mastic material.

Adequate foundation for all structures shall be obtained by removal and replacement of unsuitable materials with well graded granular material; or by tightening with coarse ballast rock, or by such other means as provided for foundation preparation of the connected sewers.

Precast base sections shall be placed on a well graded granular bedding of not less than two (2) inches in thickness. The bedding course shall be firmly tamped and made smooth and level to assure uniform contact and support of the precast element.

All lift holes shall be completely filled with mortar to ensure water tightness.

Castings shall be set in mortar or bituminous mastic beds. The adjustment of the casting to the required final grade shall be made with precast concrete adjusting rings. Maximum adjustment with rings shall be twelve inches (12"). Brick, concrete block, or wooden shims will not be permitted. Pre-cast concrete adjusting rings shall be set in mortar or bituminous mastic beds.

In pavements, frames shall be heavy duty Type 1 with either Type B closed lids or Type 11 frame and grates.

This work will be paid for at the contract unit price per **EACH** for **MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME OPEN LID; MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME CLOSED LID; MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME OPEN LID; INLETS, TYPE A, TYPE 1 FRAME OPEN LID**

which price shall include all material, labor, and equipment necessary to complete the work.

SP-29: TRENCH BACKFILL

Description: All trenches and excavations beneath pavements and driveways, as shown on plans or as directed by the Engineer in the field, will require Case III SELECTED GRANULAR BACKFILL meeting the gradation of Type A of Sec. 20-5.03 of the Water and Sewer Specs.

Trench Backfill, CA-6 shall meet the requirements of Section 1004 of the SSRBC, gradation to be "CA-6", except that GR-7 gravel will not be allowed. Select Granular Backfill, CA-6 should be used when under or within 2' of paved areas or structures, and shall extend from 1' above the pipe to at least 9" below the street

Village of Downers Grove

surface.

Backfill shall be compacted by vibrating plate or other mechanical compacting device in a manner consistent with the Standard Specifications, to ensure that no future settlement occurs.

Backfilling Method 2 as listed in Article 550.07 of the SSRBC will not be allowed.

Backfilling Method 3 as listed in Article 550.07 of the SSRBC will only be allowed with prior approval from the Engineer.

All backfilling shall be done in accordance with Section 20-4.06 of the Water and Sewer Specs. Specifically, all trenches and excavations other than those shown on the plans or designated by the Engineer to receive **SELECTED GRANULAR BACKFILL, CA-6** shall be backfilled by any acceptable method which will not dislodge or damage the pipe, or cause bridging action in the trench. Spoil material may be used as backfill in turf areas. In turf areas, **SELECTED GRANULAR BACKFILL, CA-11** shall be used to a height of one (1) foot above the top of the storm sewer pipe, and the balance of the backfill may be approved excavated material.

Placement of SELECTED GRANULAR BACKFILL, CA-11, as Granular bedding, Haunching, and Initial Backfill, as defined in the Water and Sewer Specs., shall be considered incidental to the contract price for pipe installation.

Payment shall be made only for the placement of SELECTED GRANULAR BACKFILL, CA-6, as Final Backfill, as defined in the Water and Sewer Specs. Backfill of approved excavated material shall be considered incidental to the contract price.

Where granular bedding as encasement material is not specified, selected excavation material free from clods or stones shall be used between the bottom of the trench and a point six inches above the top of the pipe.

Selected granular backfill shall be furnished for backfilling to the full width of the trench. It will be measured in cubic yards in place, except that the quantity for which payment will be made shall not exceed the volume of the trench as computed by using the maximum width of trench permitted by the SSRBC. Any selected granular material required in excess of the maximum quantity herein specified shall be furnished by the Contractor at his own expense.

This item also includes the disposal of the surplus excavated material that is replaced by selected granular backfill. Any material meeting the aforementioned gradation that has been excavated from the trenches may be used for backfilling the trenches. However, no compensation will be allowed as selected granular backfill for the portion of the trench backfilled with excavated material.

Basis of Payment: This work will be paid for at the contract unit price per **CUBIC YARD** for **TRENCH BACKFILL** which price shall be payment in full for the work as specified herein and as measured in place.

SP-30: CONNECT EXISTING STORM SEWER TO PROPOSED DRAINAGE STRUCTURE

This work shall consist of the connection of existing storm sewer to proposed manholes, catch basins or inlets. Removed or extended pipes shall be replaced with new pipe of the same size and type and connected to the proposed structure. Connections to existing pipes shall be made using a band seal, concrete collar or other approved method.

Village of Downers Grove

Basis of Payment: This work will be paid for at the contract unit price **EACH** for **CONNECT EXISTING STORM SEWER TO PROPOSED DRAINAGE STRUCTURE**.

SP-31: STORM SEWER CONNECTION TO EXISTING DRAINAGE STRUCTURE

This work includes the connection of the proposed storm sewers to the existing manholes at locations shown on the plans. The proposed connection shall be neatly cut and the area between the cut out and sewer filled with brick and mortar in accordance with Section 1042 of the Standard Specifications.

Basis of Payment: This work will be paid for at the contract unit price per **EACH** for **STORM SEWER CONNECTION TO EXISTING MANHOLE** which includes all work specified herein.

SP-32: CONFLICT MANHOLE (SIZE, TYPE, FRAME)

Description: This work shall consist of constructing a storm sewer manhole together with frames and the conflict manhole detail on the Drawings and as specified herein.

Construction Requirements: Drainage structures shall be precast reinforced concrete in accordance with Article 602.07 of the Standard Specifications. The section of sanitary sewer to pass through the conflict manhole shall be encased in ductile iron or steel casing (coated on both interior and exterior) with spacers. The casing for the sanitary sewer running through the conflict manhole shall be installed in two pieces and tack welded back together. The casing pipe shall be wrapped with "Canusa" pipe wrap and the casing ends shall be sealed with brick and mortar. Manholes shall be provided with epoxy-coated cast iron steps on 16" centers from frame to invert.

Basis of Payment: This work shall be paid for at the contract unit price per **EACH** for **CONFLICT MANHOLE (SIZE, TYPE, FRAME)**, which unit prices shall include all sewer pipe, casing pipe, couplings, frame and lids, backfilling, sand cushion, flat slab tops and all labor, material and equipment necessary to complete work.

SP-33: FIRE HYDRANT EXTENSION

This work shall consist of raising existing fire hydrants as directed by the Engineer. All work will be done in accordance with Village standards and as described herein.

When existing fire hydrants are to be raised, the work shall be accomplished through the use of extension kits manufactured by Waterous for Village of Downers Grove hydrants.

Basis of Payment: This work will be paid for at the contract unit price for **EACH** for **FIRE HYDRANT EXTENSION**, which price shall include all labor, material, backfill, and equipment necessary to complete the work.

SP-34: VALVE BOXES TO BE ADJUSTED

This work shall consist of the adjustment of any valve boxes throughout the project to the proper elevation as determined by the construction of the new roadway, curb and gutter and/or sidewalk in the area.

If the valve box is located in the sidewalk or concrete drive area, it shall be boxed out and expansion material shall be placed around the perimeter of the box-out. In addition, in a sidewalk area, expansion materials shall

Village of Downers Grove

be placed across the sidewalk on the joints on both sides of the valve box.

This work shall be paid for at the contract unit price EACH for **VALVE BOXES TO BE ADJUSTED**, which price shall be payment in full for all labor, equipment and materials required to complete the work in accordance with the plans and specifications.

SP-35: EXISTING STRUCTURES TO BE ADJUSTED

Although the cost of adjusting and/or reconstructing structures per this specification will be paid for under this contract, the contractor shall be aware that many of the structures are not the property of the Village of Downers Grove, and that such work may require inspections and/or permits from other governmental agencies.

A. DRAINAGE, WATER, AND UTILITY STRUCTURES

This work shall consist of the removal and disposal of the existing frame and lid/grate; installation of the applicable new frame and lid/grate; all labor, equipment and material required to adjust or reconstruct manholes, catch basins and inlets, and valve vaults in accordance with Section 602 of the SSRBC. This item will include all excavation, concrete and trench backfill.

B. SANITARY MANHOLES

This method shall be used for all manholes which will have less than seven and one-half (7 ½") inches of adjustment between the top of the cone and the bottom of the frame when set at finished grade. To raise the frame, adjustment shall be made using precast reinforced concrete rings. Concrete blocks or bricks shall not be used. The spaces between the cone, rings and frame shall be completely sealed with preformed bituminous mastic (Easy Stik or approved equal). Mortar shall not be used. To lower the frame, existing adjustments shall be removed and the space between the frame and the cone shall be removed and the space between the frame and the cone shall be completely sealed with preformed bituminous mastic gasket. If the manhole would have seven and one-half (7 ½") inches or more of adjustments when set at the finished grade or if the frame must be lowered by more than the amount of existing adjustment, the manhole shall be reconstructed. Refer to Downers Grove Sanitary District specifications for manhole reconstruction. The Downers Grove Sanitary District shall be notified of manholes to be adjusted prior to beginning construction. Once completed, no such adjustment shall be backfilled without inspection by the Downers Grove Sanitary District.

This work shall be paid for at the contract unit price per EACH for **STRUCTURE TO BE ADJUSTED**.

SP-36: PARKWAY RESTORATION, SPECIAL

This item shall be done in accordance with the applicable portions of Sec. 252 of the Standard Specifications and the following provisions.

As contract work progresses through the Village, parkway restoration work shall commence in a timely manner in areas where permanent placement of new curb and gutter, driveways, sidewalks, etc., has been completed. Under no circumstances shall the Contractor prolong final grading, shaping and sod placement so that the entire project can be permanently restored at the same time.

This work shall consist of the excavation, topsoiling and sodding of the entire parkway between the back of curb and the right-of-way and adjacent to all curbs, sidewalks and driveways removed and replaced during the

Village of Downers Grove

course of construction or as directed by the Engineer. Restoration will also be performed on areas disturbed by storm sewer or culvert construction.

All topsoil to be used for parkway restoration shall be obtained from outside the limits of this improvement, transported to the site and placed at required locations to a minimum depth of 4". All materials shall meet the requirements of Art. 1081.05 of the Standard Specifications. All placement of topsoil shall meet the requirements of Sec. 211 of the Standard Specifications.

All sod shall meet the requirements of Art. 1081.03 of the Standard Specifications. All placement of sod shall meet the requirements of Sec. 252 of the Standard Specifications.

For that period prior to full parkway restoration, the Contractor shall backfill and grade all disturbed areas so as to insure the safety of the general public. Parkways shall be left in a safe, clean and usable condition conducive to foot traffic and to the satisfaction of the Village. The Contractor shall protect these unfinished areas against erosion and work to keep them weed free.

Basis of Payment: This work will be paid for at the contract unit price per **SQUARE YARD** for **PARKWAY RESTORATION, SPECIAL**, which price shall be payment in full for any excavation and grading necessary, the furnishing, transporting and placement of all topsoil and sod and the full watering of sod. Unless otherwise directed by the Engineer restoration of disturbed parkways outside the limits of improvement will not be paid for separately but shall be considered incidental to the contract.

Supplemental watering shall be paid for at the contract unit price per unit for **SUPPLEMENTAL WATERING**.

Pollution Prevention Plan

Village of Downers Grove

| SITE DESCRIPTION | | | |
|--|--|---|--|
| Project Name and Location: (Latitude, Longitude, or Address) | Lacey Road Roadway Reconstruction 41° 48' 30"N, 88° 01' 22"W | Owner Name and Address: | Village of Downers Grove Public Works Department 5101 Walnut Ave. Downers Grove, IL 60515 |
| Description: (Purpose and Types of Soil Disturbing Activities) | The proposed improvements are along Lacey Road located in the Village of Downers Grove, DuPage County, Illinois. | | |
| <p>The following summarizes the improvements as part of the project:</p> <ul style="list-style-type: none"> • Removal of exiting storm pipes, structures, culverts, and other collateral items • Construction of approximately 360 linear feet of storm sewers and drainage structures ranging in diameter from 2' to 5'. • Reconstruction of approximately 1,300 linear feet of HMA roadway in a residential subdivision with ribbon curb. • All other collateral work such as driveway replacements, aggregate shoulder replacement, sidewalk and sodding. | | | |
| Runoff Coefficient: | 0.60 – Residential/Commercial | | |
| Site Area: | Area of disturbance = 1.98 acres Tributary area to project = 42 acres | | |
| Sequence of Major Activities | | | |
| The order of activities will be as follows: | | | |
| <ol style="list-style-type: none"> 1. Video Tape Project Limits 2. Tree Fence and Traffic Control 3. Sediment & Erosion Control 4. Exploratory Trenches and utility adjustments 5. Demolition and installation of proposed storm sewer 6. Roadway removal Lacey Road 7. Construct new Lacey Road Roadway | | <ol style="list-style-type: none"> 8. Install new sidewalk and replace disturbed sidewalk 9. Replace disturbed driveway aprons 10. Grading and parkway restoration 11. Install surface course | |
| Name of Receiving Waters: | East Branch of the DuPage River | | |
| CONTROLS | | | |
| | | Erosion and Sediment Controls | |

Village of Downers Grove

Stabilization Practices

Temporary Stabilization: Inlet filter baskets shall be installed under open lid drainage structures to prevent siltation from entering downstream receiving systems. Inlet filter baskets consist of a reinforced sediment bag with a frame that is inserted between the existing/proposed frame and grate.

Permanent Stabilization: Disturbed portions of the site where construction has permanently ceased shall be stabilized with permanent sod. The permanent sodding shall conform to the standards set forth in the project specification book.

Structural Practices

N/A

Storm Water Management

Stormwater drainage will be provided by new storm sewer.

Downers Grove is a full waiver community and no detention is required.

OTHER CONTROLS

Waste Disposal:

No hazardous or any other kind of waste should be stored onsite. If any waste is found then it is the contractor's responsibility to remove it.

Offsite Vehicle Tracking:

This is an existing residential and commercial area. As such, construction vehicles will access the site along existing roads. Roads will be swept when needed.

TIMING OF CONTROL/MEASURES

All sediment and erosion control measures shall be in place prior to earth disturbance. All other areas will be sodded.

CERTIFICATION OF COMPLIANCE WITH FEDERAL, STATE, AND LOCAL REGULATIONS

The storm water pollution prevention plan reflects Downers Grove requirements for storm water management and erosion control requirements as established within the DuPage County Countywide Stormwater and Flood Plain Ordinance.

MAINTENANCE/INSPECTION PROCEDURES

Erosion and Sediment Control Inspection and Maintenance Practices

These are the inspection and maintenance practices that will be used to maintain sediment and erosion

Village of Downers Grove

controls:

- All control measures will be inspected at least once each week and following any storm event of 0.5 inches or greater.
- All measures will be maintained in good working order; if a repair is necessary, it will be initiated within 24 hours of report.
- Built up sediment will be removed from silt fence when it has reached one-third the height of the fence.
- Silt fence will be inspected for depth of sediment, tears and to see if the fabric is securely attached to the fence posts.
- Temporary and permanent sodding will be inspected for bare spots, washouts and healthy growth.
- A maintenance inspection report will be made after each inspection. A copy of the report form to be completed by the inspector is attached.

Non-Storm Water Discharges

It is expected that the following non-storm water discharge will occur from the site during construction periods:

- Water from water line flushing.
- Pavement wash water (where no spills or leaks of toxic materials will have occurred)
- Uncontaminated groundwater (from dewatering excavation)

Material:

The materials or substances listed below are expected to be present onsite during construction:

- Concrete
- Reinforced Concrete Pipe
- Tar
- Petroleum Based Products
- Fertilizers

SPILL PREVENTION

Material Management Practices

Village of Downers Grove

The following are the material management practices that will be used to reduce the risk of spills or other accidental exposure of materials and substances to storm water runoff.

Good Housekeeping:

The following good housekeeping practices will be followed onsite during the construction project:

- An effort will be made to store only enough product required to do the job
- All materials stored onsite will be stored in a neat, orderly manner in their appropriate containers and, if possible, under a roof or other enclosure
- Products will be kept in their original containers with the original manufacturer's label
- Substances will not be mixed with one another unless recommended by the manufacturer
- Whenever possible, all of a product will be used up before disposing of the container
- Manufacturers' recommendations for proper use and disposal will be followed
- The site superintendent will inspect daily to ensure proper use and disposal of materials onsite.

Hazardous Products:

These practices are used to reduce the risks associated with hazardous materials.

- Products will be kept in original containers unless they are not resealable
- Original labels and material safety data will be retained; they contain important product information
- If surplus product must be disposed of, manufacturers' or local and State recommended methods for proper disposal will be followed.

Product Specific Practices

The following product specific practices will be followed onsite:

Petroleum Products:

All onsite vehicles will be monitored for leaks and receive regular preventive maintenance to reduce the chance of leakage. Petroleum products will be stored in tightly sealed containers, which are clearly labeled.

Fertilizers:

Fertilizers used will be applied only in the minimum amounts recommended by the manufacturer. Once applied, fertilizer will be worked into the soil to limit exposure to storm water. The contents of any partially used bags of fertilizer will be transferred to a sealable plastic bin to avoid spills.

Concrete Truck:

Concrete trucks will not be allowed to wash out or discharge surplus concrete or drum wash water on the site.

Village of Downers Grove

POLLUTION PREVENTION PLAN CERTIFICATION

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine or imprisonment for knowing violations.

Signed: _____

Date: _____

Village of Downers Grove

CONTRACTOR'S CERTIFICATION

I certify under penalty of law that I understand the terms and conditions of the general National Pollutant Discharge Elimination System (NPDES) permit that authorizes the storm water discharges associated with industrial activity from the construction site identified as part of this certification.

| Signature | For | Responsible For |
|-------------|-----|-----------------|
| _____ | | |
| _____ | | |
| Date: _____ | | |
| _____ | | |
| Date: _____ | | |
| _____ | | |
| Date: _____ | | |

Village of Downers Grove

V. BID and CONTRACT FORM (Village)

*****THIS BID WHEN ACCEPTED AND SIGNED BY AN AUTHORIZED SIGNATORY OF THE VILLAGE OF DOWNERS GROVE SHALL BECOME A CONTRACT BINDING UPON BOTH PARTIES.**

Entire Form Must Be Completed If a Submitted Bid Is To Be Considered For Award

BIDDER:

| | |
|---|--|
| <p>_____</p> <p>Chicagoland Paving Contractors Inc. 225 Telser Road Lake Zurich, IL 60047</p> <p>_____</p> <p>City, State, Zip</p> <p>_____</p> <p>847 550 9681</p> <p>Business Phone</p> <p>_____</p> <p>847 550 9684</p> <p>Business Fax</p> <p>ATTEST: if a Corporation</p> <p>_____</p> <p><i>[Signature]</i></p> <p>Signature of Corporation Secretary</p> | <p>_____</p> <p>4/20/16</p> <p>Date</p> <p>_____</p> <p>chicagoland1esbcglobal.net</p> <p>E-mail Address</p> <p>_____</p> <p>Bill Bowers</p> <p>Contact Name (Print)</p> <p>_____</p> <p>847 417-1133</p> <p>24-Hour Telephone</p> <p>_____</p> <p><i>[Signature]</i></p> <p>Signature of Officer, Partner or Sole Proprietor</p> <p>_____</p> <p>William R. Bowers VP</p> <p>Print Name & Title</p> |
|---|--|

We hereby agree to furnish the Village of Downers Grove all necessary materials, equipment, labor, etc. to complete the project by September 2, 2016 in accordance with the provisions, instructions and specifications for the unit prices shown on the Schedule of Prices.

VILLAGE OF DOWNERS GROVE:

ATTEST:

Authorized Signature

Title

Date

Village Clerk

Date

In compliance with the specifications, the above-signed offers and agrees, if this Bid is accepted within 90 calendar days from the date of opening, to furnish any or all of the services upon which prices are quoted, at the price set opposite each item, delivered at the designated point within the time specified above.

Village of Downers Grove

V. BID and CONTRACT FORM (Contractor)

***THIS BID WHEN ACCEPTED AND SIGNED BY AN AUTHORIZED SIGNATORY OF THE VILLAGE OF DOWNERS GROVE SHALL BECOME A CONTRACT BINDING UPON BOTH PARTIES.

Entire Form Must Be Completed If a Submitted Bid Is To Be Considered For Award

BIDDER:

Company Name

Chicagoland Paving Contractors Inc.
225 Telsor Road
Lake Zurich, IL 60047

Date

4/20/16

E-mail Address

chicagoland11esb@global.net

City, State, Zip

Contact Name (Print)

Bill Bowes

Business Phone

847 550 9681

24-Hour Telephone

847-417-1133

Business Fax

847 550 9684

Signature of Officer, Partner or Sole Proprietor

[Handwritten Signature]

ATTEST: if a Corporation

Print Name & Title

William R. Bowes VP

Signature of Corporation Secretary

[Handwritten Signature]

We hereby agree to furnish the Village of Downers Grove all necessary materials, equipment, labor, etc. to complete the project by September 2, 2016 in accordance with the provisions, instructions and specifications for the unit prices shown on the Schedule of Prices.

VILLAGE OF DOWNERS GROVE:

ATTEST:

Authorized Signature

Village Clerk

Title

Date

Date

In compliance with the specifications, the above-signed offers and agrees, if this Bid is accepted within 90 calendar days from the date of opening, to furnish any or all of the services upon which prices are quoted, at the price set opposite each item, delivered at the designated point within the time specified above.

Village of Downers Grove

SCHEDULE OF PRICES:

BASE BID

| ITEM NO. | PAY ITEM | BID QUANTITY | UNIT | UNIT PRICE | TOTAL ITEM COST |
|----------|---|--------------|-------|--------------------|----------------------|
| 67100100 | Mobilization | 1 | LS | 5,000 ⁻ | 5,000 ⁻ |
| SP-4 | Preconstruction Video Taping | 1 | LS | 500 ⁻ | 500 ⁻ |
| SP-5 | Construction Staking and Record Drawings | 1 | LS | 4,500 ⁻ | 4,500 ⁻ |
| SP-6 | Tree Protection | 120 | LF | 5 ⁻ | 600 ⁻ |
| SP-7 | Tree Root Pruning | 40 | EA | 100 ⁻ | 4,000 ⁻ |
| SP-9 | Traffic Control | 1 | LS | 8,519.70 | 8,519.70 |
| SP-10 | Street Sweeping | 24 | HOURL | 125 ⁻ | 3,000 ⁻ |
| SP-11 | Silt Fence Installation and Removal | 721 | LF | 3 ⁻ | 2,163 ⁻ |
| SP-11 | Inlet Filter Baskets | 25 | EA | 125 ⁻ | 3,125 ⁻ |
| SP-11 | Silt Dike Installation and Removal | 10 | EA | 250 ⁻ | 2,500 ⁻ |
| 44000500 | Combination Curb & Gutter Removal | 133 | LF | 10 ⁻ | 1,330 ⁻ |
| 44000600 | Sidewalk Removal | 943 | SF | 1 ⁻ | 943 ⁻ |
| SP-12 | Storm Sewer Removal, 12" | 141 | LF | 10.35 | 1,459.35 |
| SP-12 | Storm Sewer Removal, 15" | 67 | LF | 10.35 | 693.45 |
| SP-12 | Storm Sewer Removal, 18" | 29 | LF | 10.35 | 300.15 |
| 44000161 | HMA Surface Removal, 3" Depth | 106 | SY | 10 ⁻ | 1,060 ⁻ |
| SP-13 | HMA Driveway Removal | 76 | SY | 15 ⁻ | 1,140 ⁻ |
| SP-14 | Concrete Driveway Removal | 49 | SY | 15 ⁻ | 735 ⁻ |
| SP-15 | Earth Excavation, Special | 2,300 | CY | 25 ⁻ | 57,500 ⁻ |
| SP-16 | Removal and Disposal of Unsuitable Material | 250 | CY | 25 ⁻ | 6,250 ⁻ |
| SP-17 | Porous Granular Embankment, Special | 750 | CY | 25 ⁻ | 18,750 ⁻ |
| SP-18 | Additional Hauling Surcharge, Non-Hazardous Special Waste | 50 | LOAD | 400 ⁻ | 20,000 ⁻ |
| SP-19 | Exploratory Trench, Special | 100 | CY | 51.50 | 5,150 ⁻ |
| M6320030 | Guardrail Removal | 105 | LF | 4 ⁻ | 420 ⁻ |
| X0327008 | Sign Relocation | 6 | EA | 125 ⁻ | 750 ⁻ |
| SP-20 | Mailbox Relocation | 2 | EA | 175 ⁻ | 350 ⁻ |
| SP-21 | Aggregate Shoulders, Type B - 4" | 5 | TON | 100 ⁻ | 500 ⁻ |
| SP-22 | Concrete Ribbon Curb | 2,700 | LF | 16.15 | 43,605 ⁻ |
| 60603800 | Combination Curb and Gutter, Type B-6.12 | 75 | LF | 16.15 | 1,211.25 |
| SP-23 | Portland Cement Concrete Sidewalk - 5" | 1,060 | SF | 5.25 | 5,565 ⁻ |
| SP-24 | Detectible Warnings | 60 | SF | 42 ⁻ | 2,520 ⁻ |
| 40603335 | HMA Surface Course, Mix "D", N50 | 400 | TON | 82.50 | 33,000 ⁻ |
| 40600625 | Leveling Binder (Machine Method), 1.5" | 20 | TON | 80 ⁻ | 1,600 ⁻ |
| 40603080 | HMA Binder Course, IL-19.0, N50 | 620 | TON | 69 ⁻ | 42,780 ⁻ |
| 35501308 | HMA Base Course, 6" | 1,500 | TON | 69 ⁻ | 103,500 ⁻ |

Village of Downers Grove

| | | | | | |
|----------|---|-------|------|---------------------|---------------------|
| 40600100 | Bituminous Materials (Prime Coat) | 440 | GAL | 4 ⁻ | 1,760 ⁻ |
| 40600300 | Aggregate Prime Coat | 15 | TON | .01 | .15 ⁻ |
| 31101200 | Subbase Granular Material, Type B 4" | 4,080 | SY | 5 ⁻ | 20,400 ⁻ |
| 31101400 | Subbase Granular Material, Type B 6" | 140 | SY | 7 ⁻ | 980 ⁻ |
| M6300101 | Steel Plate Beam Guardrail, Type A, 1.83M Posts | 115 | LF | 32 ⁻ | 3,680 ⁻ |
| SP-25 | Aggregate for Temporary Access | 100 | TON | 17 ⁻ | 1,700 ⁻ |
| SP-26 | HMA Driveway Pavement, Special | 64 | SY | 35 ⁻ | 2,240 ⁻ |
| SP-26 | PCC Driveway Pavement, Special | 38 | SY | 61 ⁻ | 2,318 ⁻ |
| SP-27 | Storm Sewers, Type 1, 12", RCP | 64 | LF | 41.50 | 2,656 ⁻ |
| SP-27 | Storm Sewers, Type 1, 15", RCP | 37 | LF | 45.50 | 1,683.50 |
| SP-27 | Storm Sewers, Type 1, 18", RCP | 21 | LF | 48.50 | 1,018.50 |
| SP-27 | Storm Sewers, Type 1, 12", HDPE | 202 | LF | 53.75 | 10,857.50 |
| SP-27 | Storm Sewers, Type 1, 18", HDPE | 35 | LF | 57.75 | 2,021.25 |
| 54213660 | Precast RCP Flared End Sections, 15" | 1 | EA | 1,250 ⁻ | 1,250 ⁻ |
| SP-28 | Inlets, Type A, Type 1 Frame, Open Lid | 5 | EA | 1,050 ⁻ | 5,250 ⁻ |
| SP-28 | Manholes, Type A, 4' Diameter, Type 1 Frame Open Lid | 2 | EA | 4,125 ⁻ | 8,250 ⁻ |
| SP-28 | Manholes, Type A, 6' Diameter, Type 1 Frame Open Lid | 1 | EA | 6,200 ⁻ | 6,200 ⁻ |
| SP-28 | Manholes, Type A, 6' Diameter, Type 1 Frame Closed Lid | 1 | EA | 6,200 ⁻ | 6,200 ⁻ |
| SP-29 | Trench Backfill | 270 | CY | 31 ⁻ | 8,370 ⁻ |
| SP-30 | Connect Existing Storm Sewer to Proposed Drainage Structure | 3 | EA | 515 ⁻ | 1,545 ⁻ |
| SP-31 | Storm Sewer Connection to Existing Drainage Structure | 1 | EA | 360 ⁻ | 360 ⁻ |
| SP-32 | Conflict Manhole | 2 | EA | 12,360 ⁻ | 24,720 ⁻ |
| SP-33 | Fire Hydrant Extensions | 3 | EA | 825 ⁻ | 2,475 ⁻ |
| SP-34 | Valve Boxes to be Adjusted | 5 | EA | 360 ⁻ | 1,800 ⁻ |
| SP-35 | Existing Structures to be Adjusted | 17 | EA | 435 ⁻ | 7,395 ⁻ |
| 25200200 | Supplemental Watering | 20 | UNIT | .01 | .20 |
| SP-36 | Parkway Restoration, Special | 2,650 | SY | 15 ⁻ | 39,750 ⁻ |

TOTAL BASE BID 549,900.00

Village of Downers Grove

BIDDER'S CERTIFICATION (page 1 of 3)With regard to Lacey Road Reconstruction Project,bidder Chicagoland Paving Contractors
(Name of Bidder)

hereby certifies the following:

1. Bidder is not barred from bidding this contract as a result of violations of Section 720 ILCS 5/33E-3 (Bid Rigging) or 720 ILCS 5/33E-4 (Bid-Rotating);
2. Bidder certifies that it has a written sexual harassment policy in place and full compliance with 775 ILCS §12-105(A)(4);
3. Bidder certifies that not less than the prevailing rate of wages as determined by the Village of Downers Grove, DuPage County or the Illinois Department of Labor shall be paid to all laborers, workers and mechanics performing work for the Village of Downers Grove. All bonds shall include a provision as will guarantee the faithful performance of such prevailing wage clause. Bidder agrees to comply with the Illinois Prevailing Wage Act, 820 ILCS 130/1 *et seq.*, for all work completed. Bidder agrees to pay the prevailing wage and require that all of its subcontractors pay prevailing wage to any laborers, workers or mechanics who perform work pursuant to this contract or related subcontract. Bidder and each subcontractor shall keep or cause to be kept an accurate record of names, occupations and actual wages paid to each laborer, workman and mechanic employed by the Bidder in connection with the contract. This record shall be sent to the Village on a monthly basis along with the invoice and shall be open to inspection at all reasonable hours by any representative of the Village or the Illinois Department of Labor and must be preserved for five (5) years following completion of the contract. Bidder certifies that bidder and any subcontractors working on the project are aware that filing false payroll records is a class B misdemeanor and that the monetary penalties for violations are to be paid pursuant to law by the bidder, contractor and subcontractor. The Village shall not be liable for any underpayments. If applicable: Since this is a contract for a fixed public works project, as defined in 820 ILCS 130/2, Contractor agrees to post at the job site in an easily accessible place, the prevailing wages for each craft or type of worker or mechanic needed to execute the contract or work to be performed;
4. Bidder certifies that it is in full compliance with the Federal Highway Administrative Rules on Controlled Substances and Alcohol Use and Testing, 49 C.F.R. Parts 40 and 382 and that all employee drivers are currently participating in a drug and alcohol testing program pursuant to the Rules;
5. Bidder further certifies that it is not delinquent in the payment of any tax administered by the Department of Revenue, or that Bidder is contesting its liability for the tax delinquency or the amount of a tax delinquency in accordance with the procedures established by the appropriate Revenue Act. Bidder further certifies that if it owes any tax payment(s) to the Department of Revenue, Bidder has entered into an agreement with the Department of Revenue for the payment of all such taxes that are due, and Bidder is in compliance with the agreement.

Village of Downers Grove


BIDDER'S CERTIFICATION (page 2 of 3)

BY: [Signature]
Bidder's Authorized Agent

36-3494492

FEDERAL TAXPAYER IDENTIFICATION NUMBER

OR _____
Social Security Number



Subscribed and sworn to before me
this 20 day of aug, 2016.
[Signature]
Notary Public

(Fill Out Applicable Paragraph Below)

(a) Corporation

The Bidder is a corporation organized and existing under the laws of the State of IL, which operates under the Legal name of chicagoland Paving Contractors, and the full names of its Officers are as follows:

President: Kevin Meertz

Secretary: William R Banes

Treasurer: Kevin Meertz

and it does have a corporate seal. (In the event that this bid is executed by other than the President, attach hereto a certified copy of that section of Corporate By-Laws or other authorization by the Corporation which permits the person to execute the offer for the corporation.)

(b) Partnership

Signatures and Addresses of All Members of Partnership:

CHICAGOLAND PAVING CONTRACTORS, INC.
225 TELSER ROAD
LAKE ZURICH, IL 60047
Tel: 847-550-9681 Fax: 847-550-9684
Chicagoland1@sbcglobal.net

Certificate of Resolution

I, Kevin Meartz, President of CHICAGOLAND PAVING CONTRACTORS, Inc., an Illinois corporation (the Corporation) hereby certifies that the following resolutions were unanimously adopted by the Shareholders and Directors of the Corporation by consent of the Shareholders and Directors dated May 26, 1988:

RESOLVED, that CHICAGOLAND PAVING CONTRACTORS, INC., an Illinois Corporation (the Corporation) authorizes William R. Bowes, to have the authority to sign and enter into a contract on behalf of CHICAGOLAND PAVING CONTRACTORS, Inc.

FURTHER RESOLVED, that any one or more of the President and any Secretary or Assistant Secretary of the Corporation are authorized, empowered and directed to execute and deliver on behalf of the Corporation, such documents and agreements as they or any of them determine to be necessary or advisable to effectuate the foregoing resolutions.

Executed in Lake Zurich, IL on May 26, 1988.

By: *Kevin Meartz*
Kevin Meartz, President

Village of Downers Grove

BIDDER'S CERTIFICATION (page 3 of 3)

The partnership does business under the legal name of: _____
which name is registered with the office of _____ in the state of _____.

(c) Sole Proprietor

The Supplier is a Sole Proprietor whose full name is: _____
and if operating under a trade name, said trade name is: _____
which name is registered with the office of _____ in the state of _____.

6. Are you willing to comply with the Village's insurance requirements within 13 days of the award of the contract? yes

INSURER'S NAME: Corkill Agency

AGENT: Paul Praxmayer

Street Address: 25 NW Point Blvd


City, State, Zip Code: Elk Grove Village IL 60007

Telephone Number: 847-758-1000

I/We hereby affirm that the above certifications are true and accurate and that I/we have read and understand them.

Print Name of Company: Chicagoland Paving

Print Name and Title of Authorizing Signature: William R. Baus, V.P.

Signature: 

Date: 4.20.16

Village of Downers Grove

MUNICIPAL REFERENCE LIST

Municipality: please see attached
 Address: _____
 Contact Name: _____ Phone #: _____
 Name of Project: _____
 Contract Value: _____ Date of Completion: _____

Municipality: _____
 Address: _____
 Contact Name: _____ Phone #: _____
 Name of Project: _____
 Contract Value: _____ Date of Completion: _____

Municipality: _____
 Address: _____
 Contact Name: _____ Phone #: _____
 Name of Project: _____
 Contract Value: _____ Date of Completion: _____

Municipality: _____
 Address: _____
 Contact Name: _____ Phone #: _____
 Name of Project: _____
 Contract Value: _____ Date of Completion: _____

Municipality: _____
 Address: _____
 Contact Name: _____ Phone #: _____
 Name of Project: _____
 Contract Value: _____ Date of Completion: _____

Street Project List 2015

Village of Buffalo Grove

Auburn Lane Roadway Reconstruction
Contract Amount: \$ 859,900.00
Mr. Leo Morand
Gewalt Hamilton & Associates
847-478-9700

Village of Libertyville

2015 Pavement Reconstruction - Phase II
Contract Amount: \$ 1,099,900.00
Mr. Phillip J. Hurst
Civiltech Engineering
630-773-3900

Village of Round Lake

Forest Avenue & MacGillis Drive Pavement Rehabilitation
Contract Amount: \$ 344,900.00
Mr. Michael DeBennette
Baxter & Woodman, Inc.
847-223-5088

Village of Fox Lake

Stage III Roads
Contract Amount: \$ 739,900.00
Mr. Steven Berecz
Gewalt Hamilton Associates
847-478-9700

Village of Barrington

2015 Road Patching Program
Contract Amount: \$ 174,320.00
Mr. Jeff Ende
Village of Barrington Engineer
847-304-3400

Bloomington Township Highway Department

2015 Road Maintenance / Resurfacing Program
Contract Amount: \$ 364,900.00
Mr. David Bohac
Morris Engineering
630-271-0700

City of Countryside

2015 MFT Street Rehabilitation
Contract Amount: \$ 339,900.00
Mr. Thomas Brandstedt
Frank Novotny & Associates, Inc.
630-887-8640

Village of Berkeley

Joint Parking Lot Reconstruction
Contract Amount: \$ 214,900.00
Mr. David Bugaj
Civiltech Engineering
630-773-3900

Village of Oak Park

2015 Resurfacing of Various Streets
Contract Amount: \$ 2,339,000.00
Mr. Roman Babinski
Village of Oak Park Engineer
708-358-5127

Village of Downers Grove

SUBCONTRACTORS LIST

The Bidder hereby states the following items of work will not be performed by its organization. (List items to be subcontracted as well as the names, addresses and phone numbers of the subcontractors.)

1) Galaxy Type of Work Sewer

Addr: 9233 W. Cherry Ave City _____ State _____ Zip _____
Franklin Ave IL 60131

2) D: Natale Type of Work Concrete

Addr: 1441 Bernard City Addison State IL Zip 60101

3) Northern Contract Type of Work guard rail

Addr: 1851 Coltonville Rd City Sycamore State IL Zip 60178

4) NL Group Type of Work landscape

Addr: 9 Hillside Dr. City Lake Barrig State IL Zip 60010

5) _____ Type of Work _____

Addr: _____ City _____ State _____ Zip _____

6) _____ Type of Work _____

Addr: _____ City _____ State _____ Zip _____

7) _____ Type of Work _____

Addr: _____ City _____ State _____ Zip _____

8) _____ Type of Work _____

Addr: _____ City _____ State _____ Zip _____

Village of Downers Grove

CERTIFICATION OF QUALIFICATIONS

Project Team

Project Manager: Mike Silk

Construction Supervisor: Mike Silk

Team Member: _____

Team Member: _____

Team Member: _____

Team Member: _____

Team Member: _____

Team Member: _____



By checking this box, the bidder hereby certifies that it complies with all requirements of SP-3 including at least three (3) contracts of similar nature and scope within the last five (5) years, and has provided detailed supporting information.


Signed by: [Signature] (Corporate Seal)

Title: U.P. William R. Bowes

Name & Address: _____
of Contractor Chicagoland Paving Contractors Inc.
225 Telser Road
or Vendor Lake Zurich, IL 60047

Subscribed and sworn to before me this 20 day of April, 2016

[Signature]
Authorized Signature



Village of Downers Grove



VENDOR W-9 REQUEST FORM

The law requires that we maintain accurate taxpayer identification numbers for all individuals and partnerships to whom we make payments, because we are required to report to the I.R.S all payments of \$600 or more annually. We also follow the I.R.S. recommendation that this information be maintained for all payees including corporations.

Please complete the following substitute W-9 letter to assist us in meeting our I.R.S. reporting requirements. The information below will be used to determine whether we are required to send you a Form 1099. Please respond as soon as possible, as failure to do so will delay our payments.

BUSINESS (PLEASE PRINT OR TYPE):

NAME: _____

ADDRESS: **Chicagoland Paving Contractors Inc.** _____

225 Telser Road

CITY: **Lake Zurich, IL 60047** _____

STATE: _____

ZIP: _____

PHONE: **847 550 9681** FAX: **847 550 9684**

TAX ID #(TIN): **36-3494492** _____

(If you are supplying a social security number, please give your full name)

REMIT TO ADDRESS (IF DIFFERENT FROM ABOVE):

NAME: _____


ADDRESS: _____

CITY: _____

STATE: _____ ZIP: _____

TYPE OF ENTITY (CIRCLE ONE):

- Individual
- Sole Proprietor
- Partnership
- Medical
- Charitable/Nonprofit
- Limited Liability Company –Individual/Sole Proprietor
- Limited Liability Company-Partnership
- Limited Liability Company-Corporation
- Corporation**
- Government Agency

SIGNATURE:  DATE: 4/20/16

Village of Downers Grove

Apprenticeship and Training Certification

(Does not apply to federal aid projects. Applicable only to maintenance and construction projects that use Motor Fuel Tax funds or state grant monies)

Name of Bidder: Chicagoland Paving Contractors

In accordance with the provisions of Section 30-22 (6) of the Illinois Procurement Code, the bidder certifies that it is a participant, either as an individual or as part of a group program, in the approved apprenticeship and training programs applicable to each type of work or craft that the bidder will perform with its own forces. The bidder further certifies for work that will be performed by subcontract that each of its subcontractors submitted for approval either (a) is, at the time of such bid, participating in an approved, applicable apprenticeship and training program; or (b) will, prior to commencement of performance of work pursuant to this contract, begin participation in an approved apprenticeship and training program applicable to the work of the subcontract. The Illinois Department of Labor, at any time before or after award, may require the production of a copy of each applicable Certificate of Registration issued by the United States Department of Labor evidencing such participation by the contractor and any or all of its subcontractors. Applicable apprenticeship and training programs are those that have been approved and registered with the United States Department of Labor. The bidder shall list in the space below, the official name of the program sponsor holding the Certificate of Registration for all of the types of work or crafts in which the bidder is a participant and that will be performed with the bidder's forces. Types of work or craft work that will be subcontracted shall be included and listed as subcontract work. The list shall also indicate any type of work or craft job category that does not have an applicable apprenticeship or training program. **The bidder is responsible for making a complete report and shall make certain that each type of work or craft job category that will be utilized on the project is accounted for and listed. Return this with the bid.**

please see attached

The requirements of this certification and disclosure are a material part of the contract, and the contractor shall require this certification provision to be included in all approved subcontracts. In order to fulfill this requirement, it shall not be necessary that an applicable program sponsor be currently taking or that it will take applications for apprenticeship, training or employment during the performance of the work of this contract.

Print Name and Title of Authorizing Signature: William R. Bowes, U.P.

Signature: 

Date: 4/20/16

Chicagoland Paving Contractors, Inc.

225 Telser Road
Lake Zurich, IL 60047

Phone: 847-550-9681
Fax: 847-550-9684


APPRENTICESHIP TRAINING CERTIFICATION

International Brotherhood of Teamsters – Truck Drivers
Registration No. IL01050004

Operating Engineers Local #150 – Operating Engineers
Registration No. IL008780173

Heavy Equipment Technician Operating Engineers Local #150 – Heavy
Repairs
Registration No. IL01202003

Chicagoland Laborers' – JATC – Construction Craft Laborer
Registration No. IL01790001



Illinois Teamsters Joint Council No. 25 and Employers Apprenticeship & Training Fund

990 NE Frontage Road, Suite 4, Joliet, IL 60431
Office: (815) 773-0700 Fax: (815) 773-1122
Info@illinoisteamsterstraining.org

May 15, 2015

To Whom It May Concern:

This letter will certify that Chicagoland Paving, Inc. is currently contributing and is current with its contributions, as of April 2015, for the Trade of Construction Driver (1032), to the Illinois Teamsters Joint Council No.25 and Employers Apprenticeship & Training Fund.

Any questions, please feel free to contact me at (815) 773-0700.

Very Truly Yours,

Rose Wyler
Administrative Assistant

cc: file

The United States Department of Labor

Office of Apprenticeship Training, Employer and Labor Services

Bureau of Apprenticeship and Training

Certificate of Registration

Illinois Teamsters/Employers Apprenticeship & Training Fund Affiliated with Joint Councils 25 & 65

Joliet, Illinois

For The Trade of Construction Driver

Registered as part of the National Apprenticeship Program

in accordance with the basic standards of apprenticeship

established by the Secretary of Labor

June 28, 2005

Date Revised: January 25, 2008

IL015050004

Registration No.



R. J. Chao

Secretary of Labor

Anthony Savage

Administrator, Apprenticeship Training, Employer and Labor Services

INTERNATIONAL UNION OF OPERATING ENGINEERS

LOCAL UNION NO. 150, 150B, 150A, 150C, 150RA, 150D, 150G, 150M

AFFILIATED WITH THE AFL-CIO AND BUILDING TRADES DEPARTMENT

JAMES M. SWEENEY
PRESIDENT-BUSINESS MANAGER(708) 482-8600 - FAX (708) 482-7186
6200 JOLIET ROAD
COUNTRYSIDE, IL 60525-3992

May 8, 2014

Chicagoland Paving Contractors, Inc.
225 Telser Rd
Lake Zurich, IL 60047Re: Proof of Compliance with 30 ILCS 500/30-22(6)
Our File No. MI-00321

Dear Sir or Madam:

At the request of Chicagoland Paving Contractors, Inc., I am providing you with evidence of the Company's compliance with the apprenticeship requirements in 30 ILCS 500/30-22(6) of the Illinois Procurement Code. I am submitting this letter along with apprenticeship certificates (Nos. IL012020003 and IL008780173).

As a signatory contractor with the International Union of Operating Engineers, Local 150, AFL-CIO, Brothers Chicagoland Paving Contractors, Inc., is required by Collective Bargaining Agreement to participate in an applicable apprenticeship and training program approved by and registered with the United States Department of Labor's Bureau of Apprenticeship and Training. The attached certificates are evidence of compliance with the U.S. Department of Labor's apprenticeship requirements.

Thank you for your cooperation in this matter. If you have any questions or concerns, please do not hesitate to contact me.

Very truly yours,

IUOE, Local 150, AFL-CIO
District 1 dispatch office

Pauline Leitzell

PL/jm

Enclosures: Certificates

02/20/2006 10:24 P.M.

003

U.S. DEPARTMENT OF LABOR

Office of Apprenticeship Training, Employer and Labor Services

Bureau of Apprenticeship and Training

Certificate of Registration

Operating Engineers Local #150

Plainfield, Illinois

For the Trade of Operating Engineer

Registered as part of the National Apprenticeship Program

in accordance with the basic standards of apprenticeship

established by the Secretary of Labor

November 5, 2002

Date

IL 008780173

Registration No.



Scott Chao
Secretary of Labor

Anthony Swope
Administrator, Apprenticeship Training, Employer and Labor Services

Printed and Registered States Department of Labor

Office of Apprenticeship Training, Employer and Labor Services


Bureau of Apprenticeship and Training

Certificate of Registration

Heavy Equipment Technician Operating Engineers Local #150
Plainfield, Illinois

For the Trade of Repairer (Heavy)

Registered as part of the National Apprenticeship Program
in accordance with the basic standards of apprenticeship
established by the Secretary of Labor



May 5, 2002

Date

IL012020003

Registration No.

Loi. Chao
Secretary of Labor

Anthony Duran
Administrator

Chicagoland
LABORERS'
District Council Training & Apprentices Fund

www.chicagolaborers.org

CCCB 42-L

19 May 2015

Executive Director

Thomas Nordeen

Labor Trustees

James P. Connolly
Martin Flanagan
Joseph V. Healy
Charles V. LoVerde III
Joe Riley

Ms. Julie Heiderman
Chicagoland Paving Contractors, Inc.
225 Telser Road
Lake Zurich, Illinois 60047

Dear Ms. Heiderman:

Management Trustees


Seth Gudeman
Lawrence Keefe
Joseph Koppers
Robert G. Krug
David Lorig
William Vignocchi

Enclosed you will please find a copy of the Department of Labor certification that you requested recently.

You may also use this letter as verification that Chicagoland Paving Contractors, Inc. is indeed signatory to the Chicago Laborers District Council and contributes to the Laborers Apprenticeship Fund.

Should you require anything further, please do not hesitate to contact me.

Yours very truly,



Robbin L. Blakely
Office Manager

RLB
ENC

Carol Stream Location

1200 Old Gary Avenue
Carol Stream IL 60188
630.653.0006

LiUNA!

Feel the Power

Chicago Location

5700 West Homer Street
Chicago IL 60639
773.413.3315

United States Department of Labor

Office of Apprenticeship Training, Employer and Labor Services
Bureau of Apprenticeship and Training

Certificate of Registration

Chicago and Laborers' J.A.T.C.
Carol Stream, Illinois

For the Trade - Construction Craft Laborer

Registered as part of the National Apprenticeship Program
in accordance with the basic standards of apprenticeship
established by the Secretary of Labor

April 12, 1999
Date REVISED August 13, 2004
11 017990001
Registration No.



L. J. Chao
Secretary of Labor
Anthony Dunge
Administrator, Apprenticeship Training, Employer and Labor Services

Village of Downers Grove

BUY AMERICA CERTIFICATION

Certification requirement for procurement of steel, iron, or manufactured products when Federal funds (Grant Agreement or Cooperative Agreement) are used.

Instructions:

Bidder to complete the Buy America Certification listed below. Bidder shall certify EITHER COMPLIANCE OR NON-COMPLIANCE (not both). This Certification MUST BE submitted with the Bidder's bid response.

Special Note: Make sure you have signed only one of the above statements – either Compliance OR Non-Compliance (not both).

Certificate of Compliance

The bidder or offeror hereby certifies that it **will meet** the requirements of 49 U.S.C. 5323(j)(1), as amended, and the applicable regulations in 49 CFR Part 661.

Signature _____

Company Name _____

Title _____

Date _____

Certificate of Non-Compliance

The bidder or offeror hereby certifies that it **cannot comply** with the requirements of 49 U.S.C. 5323(j)(1), as amended, and 49 C.F.R. 661, but it may qualify for an exception pursuant to 49 U.S.C. 5323(j)(2)(A), 5323(j)(2)(B), or 5323(j)(2)(D), and 49 C.F.R. 661.7.

Signature _____

Company Name _____

Title _____

Date _____

AFTER THIS CERTIFICATE HAS BEEN EXECUTED, A BIDDER MAY NOT SEEK A WAIVER.

Note: The U.S./Canadian Free Trade Agreement does not supersede the Buy America requirement.

Village of Downers Grove

Suspension or Debarment Certificate

Non-Federal entities are prohibited from contracting with or making sub-awards under covered transactions to parties that are suspended or debarred or whose principals are suspended or debarred. Covered transactions include procurement for goods or services equal to or in excess of \$100,000.00 contractors receiving individual awards for \$100,000.00 or more and all sub-recipients must certify that the organization and its principals are not suspended or debarred.

By submitting this offer and signing this certificate, the bidder certifies to the best of its knowledge and belief, that the company and its principals:

- 1. Are not presently debarred, suspended, proposed for debarment, declared ineligible or voluntarily excluded from covered transactions by any federal, state or local governmental entity, department or agency.
- 2. Have not within a three-year period preceding this proposal been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction, or convicted of or had a civil judgment against them for a violation of Federal or state antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, or receiving stolen property;
- 3. Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State, or local) with commission of any of the offenses enumerated in paragraph (2) of this certification: and
- 4. Have not within a three-year period preceding this application/proposal/contract had one or more public transactions (Federal, State or local) terminated for cause or default.

If the bidder is unable to certify to any of the statements in this certification, bidder shall attach an explanation to this certification.

Company Name: Chicagoland Paving Contractors Inc.

Address: 225 Telser Road
Lake Zurich, IL 60047

City: _____ ip Code: _____

Telephone: (847) 550 9687 Fax Number: (847) 550 9684

E-mail Address: chicagoland1@sbcglobal.net

Authorized Company Signature: [Handwritten Signature]

Print Signature Name: William R. Barnes Title of Official: VP

Date: 4/20/16

Village of Downers Grove

CAMPAIGN DISCLOSURE CERTIFICATE

Any contractor, proposer, bidder or vendor who responds by submitting a bid or proposal to the Village of Downers Grove shall be required to submit with its bid submission, an executed Campaign Disclosure Certificate, attached hereto.


The Campaign Disclosure Certificate is required pursuant to the Village of Downers Grove Council Policy on Ethical Standards and is applicable to those campaign contributions made to any member of the Village Council.

Said Campaign Disclosure Certificate requires any individual or entity bidding to disclose campaign contributions, as defined in Section 9-1.4 of the Election Code (10 ILCS 5/9-1.4), made to current members of the Village Council within the five (5) year period preceding the date of the bid or proposal release.

By signing the bid documents, contractor/proposer/bidder/vendor agrees to refrain from making any campaign contributions as defined in Section 9-1.4 of the Election Code (10 ILCS 5/9-1.4) to any Village Council member and any challengers seeking to serve as a member of the Downers Grove Village Council.

Under penalty of perjury, I declare:

Bidder/vendor has not contributed to any elected Village position within the last five (5) years.


Signature William R. Bowes
Print Name

Bidder/vendor has contributed a campaign contribution to a current member of the Village Council within the last five (5) years.

Print the following information:

Name of Contributor: _____
(company or individual)

To whom contribution was made: _____

Year contribution made: _____ Amount: \$ _____

Signature Print Name

Village of Downers Grove

BID SUBMITTAL CHECKLIST

Each Bidder's Bid Package must be submitted with all requisite forms properly completed, and all documentation included. The following list is not all-inclusive, but is designed to facilitate a good, competitive bidding environment.

1. Instructions to Bidders read and understood. Any questions must be asked according to the instructions.
2. Cover sheet filled-in
3. Bid Form copies filled-in. All copies must have original signatures and seals on them.
4. Bid Bond or cashier's check enclosed with bid package.
5. Schedule of Prices completed. Check your math!
6. Bidder Certifications signed and sealed.
7. Letter from Surety ensuring issuance of Performance and Labor Bonds.
8. Letter from Insurance Agent or Carrier ensuring issuance of required job coverage.
9. Municipal Reference List completed.
10. Certification of Qualifications
11. Vendor request form W-9 completed.
12. Affidavit (IDOT Form BC-57, or similar).
13. Bid package properly sealed and labeled before delivery. If sending by mail or messenger, enclose in a second outer envelope or container. Project plan sheets do not have to be included with the bid package.



25 Northwest Point Blvd., Ste 625
Elk Grove Village, IL 60007
Phone: (847) 758-1000
Fax: (847) 758-1200

April 20, 2016

Village of Downers Grove
5101 Walnut Avenue
Downers Grove, IL 60515

Re: Letter of Bond Ability for Bid #ST-052/SW-070
Lacey Road Resconstruction
Chicagoland Paving Contractors, Inc.
225 Telser Road
Lake Zurich, IL 6004

To Whom It May Concern:

We are the bonding Agent for Chicagoland Paving Contractors, Inc. This letter is to acknowledge the capability of acquiring a payment and/or performance bond on behalf of Chicagoland Paving Contractors, Inc. for the bid opening on April 20, 2016 under Bid No.: ST-052/SW-070 for the project known as "Lacey Road Reconstruction", should they be the low bidder and are required to secure such final bond(s).

Should you have any questions or concerns, please do not hesitate to contact us.

Sincerely,

A handwritten signature in black ink, appearing to read "Luke F. Praxmarer". The signature is written in a cursive, somewhat stylized font.

Luke F. Praxmarer
(Attorney-in-Fact)



Corkill Insurance Agency, Inc.
25 Northwest Point Blvd., Suite 625
Elk Grove Village, IL 60007

Phone 847-758-1000
Fax 847-758-1200

April 19, 2016

Daniel J. Kmiecik, PE
Village of Downers Grove
5101 Walnut Avenue
Downers Grove IL 60515

Re: Chicagoland Paving Contractors, Inc.
225 Telser Rd
Lake Zurich, IL 60047

Bid/Project: ST-052/SW-070
Lacey Road Reconstruction

To Whom It May Concern:

This letter is to certify that we have read the insurance requirements set forth in the Bid/Contract and will issue the required certificates and policies of insurance upon award of the contract to *Chicagoland Paving Contractors, Inc.*

Please contact me personally should you have any questions.

Thank you,

Paul F. Praxmarer

Paul F. Praxmarer
Vice President
847.437.2656



AIA[®] Document A310[™] – 2010

Bid Bond

Bond Number: 2320798

CONTRACTOR:

(Name, legal status and address)

Chicagoland Paving Contractors, Inc.
225 Telser Rd.
Lake Zurich, IL 60047

SURETY:

(Name, legal status and principal place of business)

West Bend Mutual Insurance Company
8401 Greenway Blvd, Suite 1100
Middleton, WI 53562

OWNER:

(Name, legal status and address)

Village of Downers Grove
5101 Walnut Ave.
Downers Grove, IL 60515

BOND AMOUNT: \$ 5% of Total Bid Amount (Five Percent of Total Bid Amount)

PROJECT:

(Name, location or address, and Project number, if any)

Lacey Road Reconstruction

ADDITIONS AND DELETIONS:

The author of this document has added information needed for its completion. The author may also have revised the text of the original AIA standard form. An *Additions and Deletions Report* that notes added information as well as revisions to the standard form text is available from the author and should be reviewed. A vertical line in the left margin of this document indicates where the author has added necessary information and where the author has added to or deleted from the original AIA text.

This document has important legal consequences. Consultation with an attorney is encouraged with respect to its completion or modification.

Any singular reference to Contractor, Surety, Owner or other party shall be considered plural where applicable.

The Contractor and Surety are bound to the Owner in the amount set forth above, for the payment of which the Contractor and Surety bind themselves, their heirs, executors, administrators, successors and assigns, jointly and severally, as provided herein. The conditions of this Bond are such that if the Owner accepts the bid of the Contractor within the time specified in the bid documents, or within such time period as may be agreed to by the Owner and Contractor, and the Contractor either (1) enters into a contract with the Owner in accordance with the terms of such bid, and gives such bond or bonds as may be specified in the bidding or Contract Documents, with a surety admitted in the jurisdiction of the Project and otherwise acceptable to the Owner, for the faithful performance of such Contract and for the prompt payment of labor and material furnished in the prosecution thereof; or (2) pays to the Owner the difference, not to exceed the amount of this Bond, between the amount specified in said bid and such larger amount for which the Owner may in good faith contract with another party to perform the work covered by said bid, then this obligation shall be null and void, otherwise to remain in full force and effect. The Surety hereby waives any notice of an agreement between the Owner and Contractor to extend the time in which the Owner may accept the bid. Waiver of notice by the Surety shall not apply to any extension exceeding sixty (60) days in the aggregate beyond the time for acceptance of bids specified in the bid documents, and the Owner and Contractor shall obtain the Surety's consent for an extension beyond sixty (60) days.

If this Bond is issued in connection with a subcontractor's bid to a Contractor, the term Contractor in this Bond shall be deemed to be Subcontractor and the term Owner shall be deemed to be Contractor.

When this Bond has been furnished to comply with a statutory or other legal requirement in the location of the Project, any provision in this Bond conflicting with said statutory or legal requirement shall be deemed deleted herefrom and provisions conforming to such statutory or other legal requirement shall be deemed incorporated herein. When so furnished, the intent is that this Bond shall be construed as a statutory bond and not as a common law bond.


Init.

AIA Document A310[™] – 2010. Copyright © 1963, 1970 and 2010 by The American Institute of Architects. All rights reserved. **WARNING:** This AIA[®] Document is protected by U.S. Copyright Law and International Treaties. Unauthorized reproduction or distribution of this AIA[®] Document, or any portion of it, may result in severe civil and criminal penalties, and will be prosecuted to the maximum extent possible under the law. This document was produced by AIA software at 12:05:38 on 04/11/2011 under Order No.0544169414_1 which expires on 02/16/2012, and is not for resale.

User Notes:

(1481917559)

Signed and sealed this 20 day of April, 2016




(Witness)



(Witness)

Chicagoland Paving Contractors, Inc.

(Contractor as Principal) (Seal)

 UP.

(Title) William R. Banes

West Bend Mutual Insurance Company

(Surety) (Seal)



(Title) Paul F. Praxmarer (Attorney-In-Fact)

Init.



2320798

Power of Attorney

Know all men by these Presents, That West Bend Mutual Insurance Company, a corporation having its principal office in the City of West Bend, Wisconsin does make, constitute and appoint:

PAUL PRAXMARER

lawful Attorney(s)-in-fact, to make, execute, seal and deliver for and on its behalf as surety and as its act and deed any and all bonds, undertakings and contracts of suretyship, provided that no bond or undertaking or contract of suretyship executed under this authority shall exceed in amount the sum of: Seven Million Five Hundred Thousand Dollars (\$7,500,000)

This Power of Attorney is granted and is signed and sealed by facsimile under and by the authority of the following Resolution adopted by the Board of Directors of West Bend Mutual Insurance Company at a meeting duly called and held on the 21st day of December, 1999.

Appointment of Attorney-In-Fact. The president or any vice president, or any other officer of West Bend Mutual Insurance Company may appoint by written certificate Attorneys-in-Fact to act on behalf of the company in the execution of and attesting of bonds and undertakings and other written obligatory instruments of like nature. The signature of any officer authorized hereby and the corporate seal may be affixed by facsimile to any such power of attorney or to any certificate relating therefore and any such power of attorney or certificate bearing such facsimile signatures or facsimile seal shall be valid and binding upon the company, and any such power so executed and certified by facsimile signatures and facsimile seal shall be valid and binding upon the company in the future with respect to any bond or undertaking or other writing obligatory in nature to which it is attached. Any such appointment may be revoked, for cause, or without cause, by any said officer at any time.

In witness whereof, the West Bend Mutual Insurance Company has caused these presents to be signed by its president undersigned and its corporate seal to be hereto duly attested by its secretary this 1st day of March, 2009.

Attest


James J. Pauly
James J. Pauly
Secretary



Kevin A. Steiner
Kevin A. Steiner
Chief Executive Officer / President

State of Wisconsin
County of Washington

On the 1st day of March, 2009 before me personally came Kevin A. Steiner, to me known being by duly sworn, did depose and say that he resides in the County of Washington, State of Wisconsin; that he is the President of West Bend Mutual Insurance Company, the corporation described in and which executed the above instrument; that he knows the seal of the said corporation; that the seal affixed to said instrument is such corporate seal; that it was so affixed by order of the board of directors of said corporation and that he signed his name thereto by like order.



John F. Duwell
John F. Duwell
Executive Vice President - Chief Legal Officer
Notary Public, Washington Co. WI
My Commission is Permanent

The undersigned, duly elected to the office stated below, now the incumbent in West Bend Mutual Insurance Company, a Wisconsin corporation authorized to make this certificate, Do Hereby Certify that the foregoing attached Power of Attorney remains in full force effect and has not been revoked and that the Resolution of the Board of Directors, set forth in the Power of Attorney is now in force.

Signed and sealed at West Bend, Wisconsin this 20 day of April, 2016



Daie J. Kent
Daie J. Kent
Executive Vice President -
Chief Financial Officer



ACKNOWLEDGMENT OF CORPORATE SURETY


STATE OF Illinois)

ss

County of Cook)

On this 20 day of April, 20 16, before me appeared Paul F. Praxmarer

to me personally known, who being by me duly sworn, did say that he/she is the aforesaid officer or attorney in fact of the WEST BEND MUTUAL INSURANCE COMPANY, a corporation; that the seal affixed to the foregoing instrument is the corporate seal of said corporation, and that said instrument was signed and sealed on behalf of said corporation by the aforesaid officer (or Attorney-in-Fact), by authority of its Board of Directors; and the aforesaid officer (or Attorney-in-Fact), acknowledged said instrument to be the free act and deed of said corporation.



Rebecca Spees

 Notary Public

My Commission Expires

July 30, 20 17

County of Cook, State of Illinois

MICHIGAN ONLY: This policy is exempt from the filing requirements of Section 2236 of the Insurance Code of 1956, 1956 PA 218 and MCL 500.2236.



Illinois Department of Transportation

Bureau of Construction
2300 South Dirksen Parkway/Room 322
Springfield, Illinois 62764

**Affidavit of Availability
For the Letting of _____**

(Letting date)

Instructions: Complete this form by either typing or using black ink. "Authorization to Bid" will not be issued unless both sides of this form are completed in detail. Use additional forms as needed to list all work.

Part I. Work Under Contract

List below all work you have under contract as either a prime contractor or a subcontractor. It is required to include all pending low bids not yet awarded or rejected. In a joint venture, list only that portion of the work which is the responsibility of your company. The uncompleted dollar value is to be based upon the most recent engineer's or owners estimate, and must include work subcontracted to others. If no work is contracted, show NONE.

| | 1 | 2 | 3 | 4 | Awards Pending | |
|--|-----------|--------------|--------------|------------|----------------|---------------------|
| Contract Number | | | | | | |
| Contract With | Gurnee PD | METRA | IDOT | Hanover Pk | | |
| Estimated Completion Date | 6/1/16 | 9/30/16 | 11/2016 | 1/28/16 | | |
| Total Contract Price | 64,800.00 | 2,000,000.00 | 1,039,907.80 | 897,967.93 | | Accumulated Totals |
| Uncompleted Dollar Value if Firm is the Prime Contractor | 64,800.00 | 1,000,000.00 | 1,039,907.80 | 897,967.93 | | 3,002,675.73 |
| Uncompleted Dollar Value if Firm is the Subcontractor | | | | | | 0.00 |
| Total Value of All Work | | | | | | 3,002,675.73 |

Part II. Awards Pending and Uncompleted Work to be done with your own forces.

List below the uncompleted dollar value of work for each contract and awards pending to be completed with your own forces. All work subcontracted to others will be listed on the reverse of this form. In a joint venture, list only that portion of the work to be done by your company. If no work is contracted, show NONE.

| | | | | | Accumulated Totals |
|--------------------------------------|------------------|---------------------|-------------------|-------------------|---------------------|
| Earthwork | 28,450.00 | | 355,500.00 | 201,552.28 | 585,502.28 |
| Portland Cement Concrete Paving | | | | | 0.00 |
| HMA Plant Mix | | 250,000.00 | 108,500.00 | 187,500.00 | 546,000.00 |
| HMA Paving | | 750,000.00 | 140,946.30 | 210,500.00 | 1,101,446.30 |
| Clean & Seal Cracks/Joints | | | | | 0.00 |
| Aggregate Bases & Surfaces | 25,000.00 | | 185,000.00 | 100,000.00 | 310,000.00 |
| Highway,R.R. and Waterway Structures | | | | | 0.00 |
| Drainage | | | | | 0.00 |
| Electrical | | | | | 0.00 |
| Cover and Seal Coats | | | | | 0.00 |
| Concrete Construction | | | | | 0.00 |
| Landscaping | 10,000.00 | | 50,000.00 | | 60,000.00 |
| Fencing | | | | | 0.00 |
| Guardrail | | | | | 0.00 |
| Painting | | | | | 0.00 |
| Signing | | | | | 0.00 |
| Cold Milling, Planning & Rotomilling | | | | 6,000.00 | 6,000.00 |
| Demolition | | | | | 0.00 |
| Pavement Markings (Paint) | | | | | 0.00 |
| Other Construction (List) | | | | | 0.00 |
| | | | | | 0.00 |
| | | | | | 0.00 |
| Totals | 63,450.00 | 1,000,000.00 | 839,946.30 | 705,552.28 | 0.00 |
| | | | | | 2,608,948.58 |

Disclosure of this information is **REQUIRED** to accomplish the statutory purpose as outlined in the "Illinois Procurement Code". Failure to comply will result in non-issuance of an "Authorization To Bid." This form has been approved by the State Forms Management Center.

Part III. Work Subcontracted to Others

For each contract described in Part I, list all the work you have subcontracted to others.

| | 1 | 2 | 3 | 4 | Awards Pending |
|--------------------------|-----------------|-------------|-------------------|-------------------|----------------|
| Subcontractor | Garelli | | Precision | Precision | |
| Type of Work | striping | | striping | striping | |
| Subcontract Price | 1,350.00 | | 4,078.50 | 1,715.00 | |
| Amount Uncompleted | 1,350.00 | | 4,078.50 | 1,715.00 | |
| Subcontractor | | | Fence Connect | Suburban Con. | |
| Type of Work | | | fencing | concrete | |
| Subcontract Price | | | 23,615.00 | 79,896.70 | |
| Amount Uncompleted | | | 23,615.00 | 79,896.70 | |
| Subcontractor | | | Utility Dynamics | Galaxy Under | |
| Type of Work | | | electrical | sewer | |
| Subcontract Price | | | 101,980.00 | 71,044.00 | |
| Amount Uncompleted | | | 101,980.00 | 71,044.00 | |
| Subcontractor | | | McGinty | KD Staples | |
| Type of Work | | | landscape | landscape | |
| Subcontract Price | | | 10,615.00 | 39,759.95 | |
| Amount Uncompleted | | | 10,615.00 | 39,759.95 | |
| Subcontractor | | | Kreative Scape | | |
| Type of Work | | | concrete | | |
| Subcontract Price | | | 41,991.00 | | |
| Amount Uncompleted | | | 41,991.00 | | |
| Subcontractor | | | Galaxy Under. | | |
| Type of Work | | | sewer | | |
| Subcontract Price | | | 7,000.00 | | |
| Amount Uncompleted | | | 7,000.00 | | |
| Subcontractor | | | Homer | | |
| Type of Work | | | tree remove | | |
| Subcontract Price | | | 10,682.00 | | |
| Amount Uncompleted | | | 10,682.00 | | |
| Total Uncompleted | 1,350.00 | 0.00 | 199,961.50 | 192,415.65 | 0.00 |


I, being duly sworn, do hereby declare this affidavit is a true and correct statement relating to ALL uncompleted contracts of the undersigned for Federal, State, County, City and private work, including ALL subcontract work, ALL pending low bids not yet awarded or rejected and ALL estimated completion dates

Subscribed and sworn to before me

this 20 day of April, 2016.

Julie C Heiderman
Notary Public

My commission expires: 10/18/18




Type or Print Name William R. Bowes, V.P.
Officer or Director Title

Signed [Signature]

Company Chicagoland Paving Contractors, Inc.

Address 225 Telser Road
Lake Zurich, IL 60047



Village of Downers Grove

Contractor Evaluation

Contractor: Chicagoland Paving

Project: 2014 Fall Pavement Patching

Primary Contact: Bill Bowes Phone: 847-550-96814

Time Period: October 2014

On Schedule (allowing for uncontrollable circumstances) Yes No

Provide details if early or late completion: Completed Class D patches on time.

Change Orders (attach information if needed): None

Difficulties / Positives: None

Interaction with public:

Excellent Good Average Poor


(Attach information on any complaints or compliments)

General Level of Satisfaction with work:

Well Satisfied Satisfied Not Satisfied

Reviewers: Nate Hawk

Date: 2/3/15



Village of Downers Grove

Contractor Evaluation

Contractor: Chicagoland Paving

Project: Parking Lot Improvements for Fire Stations 1 & 3 and School District 58

Primary Contact: Bill Bowes Phone: 847-550-9681

Time Period: June 2014 to November 2014

On Schedule (allowing for uncontrollable circumstances) Yes No

Provide details if early or late completion: Completed School District 58 improvements on time; delays of Fire Station 3 improvements caused by pavement removal work during rainy weather and placing new asphalt on stone base that was not prepared correctly causing the need for removal

Change Orders (attach information if needed): None

Difficulties / Positives: Worked well with School District 58 to complete District 58 improvement satisfactorily; good subcontractor control; lack of communication with Village staff on scheduling; delays due to performing improvements during rainy weather conditions that caused construction problems

Interaction with public:

Excellent Good Average Poor

(Attach information on any complaints or compliments)

General Level of Satisfaction with work:

Well Satisfied Satisfied Not Satisfied

Reviewers: Nate Hawk

Date: 2/3/15