

**VILLAGE OF DOWNERS GROVE**  
**Report for the Village**  
**6/5/2018**

<b>SUBJECT:</b>	<b>SUBMITTED BY:</b>
Storm Sewer Repairs on Curtiss Street	Nan Newlon Director of Public Works

**SYNOPSIS**

A motion is requested to authorize payment in an amount not to exceed \$41,071.66 and authorize the Village Manager to enter into an agreement with LA Sites Sewer & Water of Joliet, Illinois to repair a section of Village storm sewer at 2400 Curtiss Street.

**STRATEGIC PLAN ALIGNMENT**

The goals for 2017-2019 include *Top Quality Infrastructure*.

**FISCAL IMPACT**

There are sufficient funds in the Stormwater Fund for this project.

**RECOMMENDATION**

Approval on the June 5, 2018 consent agenda.

**BACKGROUND**

Rexnord is in the process of constructing a new facility at 2400 Curtiss Street and during that work significant deterioration of a Village storm sewer was discovered that crosses their proposed driveway. This storm sewer needs to be replaced before the new driveway is constructed, which is anticipated within the next two weeks. To facilitate this repair the Village requested a proposal from Rexnord's contractor, LA Sites Sewer & Water, which is attached.

**ATTACHMENTS**

Quote

VILLAGE OF DOWNERS GROVE  
COUNCIL ACTION SUMMARY

INITIATED: Village Attorney DATE: June 5, 2018  
(Name)

RECOMMENDATION FROM: \_\_\_\_\_ FILE REF: \_\_\_\_\_  
(Board or Department)

**NATURE OF ACTION:**

**STEPS NEEDED TO IMPLEMENT ACTION:**

- Ordinance
- Resolution
- Motion
- Other

Motion to authorize payment in an amount not to exceed \$41,071.66 and authorize the Village Manager to enter into an agreement with LA Sites Sewer & Water for emergency repairs to a section of storm sewer at 2400 Curtiss.



**SUMMARY OF ITEM:**

Approval of this motion shall authorize payment in an amount not to exceed \$41,071.66 and authorize the Village Manager to enter into an agreement with LA Sites Sewer & Water for emergency repairs to a section of storm sewer at 2400 Curtiss.

**RECORD OF ACTION TAKEN:**

---



---



---



1733 TERRY DRIVE  
 JOLIET, IL 60436  
 779.702.8071 • 779.702.8412 f  
 www.lasitesinc.com

**PROPOSAL**

**DOWNERS GROVE - 2400 CURTISS STORM SEWER  
 REMOVAL & REPLACEMENT PER 5-31-2018 RED LINE PLAN**

	QTY	UNIT	UNIT PRICE	TOTAL
<b>MOBILIZATION:</b>				
TRI-AXLE LOWBOY W/ PERMITS - 1 WAY MOVES				
-Excavator	1	LS	\$837.20	\$837.20
-Loader	1	LS	\$734.00	\$734.00
			<b>TOTAL MOB</b>	<b>\$1,571.20</b>
<b>BYPASS PUMPING OF EXISTING 42' ERCP FROM EXISTING "T" MANHOLE    WEST TO REXNORD POND:</b>				
-40K gen set (24hr) + transport & fuel	1	LS	\$534.60	\$534.60
-2" electric pump, discharge hose, silt bag	1	LS	\$150.00	\$150.00
			<b>TOTAL BYPASS</b>	<b>\$684.60</b>
<b>LABOR:</b>				
- Foreman w/ truck & tools	16	HR	\$146.60	\$2,345.60
- Operator (excavator)	16	HR	\$123.60	\$1,977.60
- Operator (excavator) over time & grease time	1	HR	\$148.90	\$148.90
- Operator	16	HR	\$123.60	\$1,977.60
- Laborer	16	HR	\$109.00	\$1,744.00
- Laborer	16	HR	\$109.00	\$1,744.00
			<b>TOTAL LABOR</b>	<b>\$9,937.70</b>
<b>EQUIPMENT:</b>				
- 83K Excavator	16	HR	\$146.00	\$2,336.00
- 3.0 CY wheel loader	16	HR	\$115.00	\$1,840.00
			<b>TOTAL EQP</b>	<b>\$4,176.00</b>
<b>Material:</b>				
1.) 7.0'X 6.0' PRECAST "BOX" MANHOLE W/ LOW PROFILE FRAME & COVER & BENCH	1	EA	\$5,508.00	\$5,508.00
2.) 4.0' DIA CATCH BASIN W/ 12" DIRECT DRIVE POSITIVE SEALS, 2.0' SUMP (MAIN) NO FRAME & LID	1	EA	\$1,089.00	\$1,089.00
3.) 3.0' DIA INLET W/ 12" DIRECT DRIVE POSITIVE SEALS	1	EA	\$826.50	\$826.50
4.) 34"X54" ERCP CL-3*	90	LF	\$95.50	\$8,595.00
5.) 12" RCP CL-5	40	LF	\$7.80	\$312.00
6.) 4" CONCRETE ADJUSTMENT RING	2	EA	\$25.00	\$50.00
7.) 2" CONCRETE ADJUSTMENT RING	2	EA	\$22.00	\$44.00
8.) 1" BUTYL ROPE	8	EA	\$7.00	\$56.00
9.) MORTAR	10	BG	\$6.33	\$63.30
10.) 4" BRICK	54	EA	\$0.45	\$24.30
11.) 3/4" STONE, BEDDING & BACKFILL W/ 6" OVER TOP OF PIPE	122	TN	\$15.25	\$1,860.50
				\$18,428.60
			10% M.U.	\$1,842.86
			<b>TOTAL MAT'L</b>	<b>\$20,271.46</b>
<b>HAUL OFF WITH DUMP FEE:</b>				
- CONCRETE & EXISTING STRUCTURES				
-71CY CLAY SPOILS				
-TRUCKING	9	LD	\$492.30	\$4,430.70
			<b>TOTAL HAUL OFF</b>	<b>\$4,430.70</b>
			<b>TOTAL PROPOSAL</b>	<b>\$41,071.66</b>
<b>EXCLUSIONS:</b>				
-NO MACHINE COMPACTION				
-NO EROSION CONTROL				
-NO PERMITS, BONDS, FEES, OR SPECIAL INSURANCE				
-NO RESTORATION				